CI 00 SC P3L 4 # 1 C/ 45 P 36 # 4 SC 45.2.1.174c L 13 Graber, Steffen Graber, Steffen Pepperl+Fuchs GmbH Pepperl+Fuchs GmbH Comment Type Е Comment Status A F7 Comment Type T Comment Status A F7 MediumDependent Interface 0.1.1 = Reserved (in 146.5.2 a third test mode for the PSD mask test has been added. which is sending Idles in Master mode, therefore it makes sense to be able to enable this SuggestedRemedy also through the test mode register) Medium Dependent Interface SuggestedRemedy Response Response Status C 0.11 = Test mode 3ACCEPT. Replace "MediumDependent" with Medium Dependent" Response Response Status C ACCEPT. Replace "0 1 1 = Reserved" with "0 1 1 = Test mode 3" SC C/ 00 P3L 5 # 2 Graber, Steffen Pepperl+Fuchs GmbH C/ 104 P 76 SC 104.9.4.3 L 44 Comment Type Ε Comment Status A ΕZ Graber, Steffen Pepperl+Fuchs GmbH physical layer (in Keywords section most of the words start with a capital letter, should be Comment Type E Comment Status A ΕZ uniform) With transfer function H2(f) specified in Equation (104-3) where f2=0.1 MHz ±1% SuggestedRemedy SuggestedRemedy Physical Layer Change in H2(f) the 2 in subscript. Change f2=0.1 MHz  $\pm 1\%$  to f2=0.1 MHz  $\pm 1\%$  (with Response Response Status C the 2 in f2 in subscript). ACCEPT. Replace "physical layer" with "Physical Layer" as per the IEEE 802.3 Working Response Response Status C Group editorial guidelines. ACCEPT. Change the 2 in "H2f" to subscript, change the 2 in "f2" to subscript, and insert non-breaking space after "±". C/ 01 SC 1.5 P 24 L 32 # 3 Graber, Steffen Pepperl+Fuchs GmbH SC 104.9.4.4 C/ 104 P77 L 11 Comment Type Ε Comment Status A ΕZ Graber, Steffen Pepperl+Fuchs GmbH **PLCS** Comment Type Comment Status A ΕZ Ε SuggestedRemedy 146.8.xxx (reference needs to be specified) **PLCA** SuggestedRemedy Response Response Status C 146.8.4 ACCEPT. Replace "PLCS" on line 32 with "PLCA" (Same resolution proposed for Response Response Status C comments #139, #3, and #188) ACCEPT. Replace "146.8.xxx" with "146.8.4".

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 6

Page 1 of 37 3/6/2018 4:20:48 PM

C/ 146 SC 146.1 Graber, Steffen	P <b>79</b> Pepperl+Fuchs 0	<i>L</i> <b>19</b> GmbH	# 7		CI 146 SC 146.1.2 P81 L 22 # 11  Graber, Steffen Pepperl+Fuchs GmbH			
Comment Type <b>E</b> Comment Status <b>A</b> EZ  10BASE-T1LPHY (add space before PHY)					Comment Type <b>E</b> Comment Status <b>A</b> EZ  There is a wrong paragrah separation between line 22 and line 24.			
SuggestedRemedy 10BASE-T1L PHY					SuggestedRemedy  Remove the "new paragraph" formatting between line 22 and line 24.			
Response ACCEPT.	Response Status C				Response Response Status C ACCEPT.			
Cl 146 SC 146.1.2 Graber, Steffen	P 81 Pepperl+Fuchs 0	L <b>3</b> GmbH	# 8		CI 146 SC 146.2 P82 L 20 # 12  Graber, Steffen Pepperl+Fuchs GmbH			
Comment Type <b>E</b> . link utilization (remo	Comment Status A			EZ	Comment Type E Comment Status R Editorial Technology Dependent Interface			
SuggestedRemedy . link utilization.					SuggestedRemedy  Remove the Technology Dependent Interface and associated primitives.			
Response ACCEPT.	Response Status C				Response Response Status C  REJECT. Technology dependent interface is used to communicate between the PHY and the Auto-			
C/ 146 SC 146.1.2 Graber, Steffen	<i>P</i> <b>81</b> Pepperl+Fuchs 0	<i>L</i> <b>11</b> ЭmbH			Negotiation Function (Clause 98). See 98.4  Cl 146 SC 146.2 P82 L 26 # 13			
Comment Type E	Comment Status A			EZ	Graber, Steffen Pepperl+Fuchs GmbH			
The MDI is specified in 146.8 (remove second dot)  SuggestedRemedy					Comment Type T Comment Status A EZ  The TX_CLK arrow has the wrong direction (signal direction should go from PCS to MII)			
The MDI is specified in Response	n 146.8. Response Status <b>C</b>				SuggestedRemedy Change arrow direction for TX_CLK signal.			
ACCEPT.						Response Status C		
Cl <b>146</b> SC <b>146.1.2</b> Graber, Steffen	P <b>81</b> Pepperl+Fuchs 0	<i>L</i> <b>17</b> GmbH	# [10		ACCEPT.			
Comment Type <b>E</b> . in the Task Force rev	Comment Status A riew process (remove second do	ot)		EZ				
SuggestedRemedy . in the Task Force rev	iew process.							

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Response Status C

Response

ACCEPT.

Comment ID 13 Pa

Page 2 of 37 3/6/2018 4:20:48 PM C/ 146 SC 146.2 P 82 L 27 # 14 Graber, Steffen Pepperl+Fuchs GmbH Comment Type Т Comment Status A F7 TXD<7:0> (MII is only 4 bits wide) SuggestedRemedy TXD<3:0> Response Response Status C ACCEPT. C/ 146 SC 146.2 P 82 L 36 # 15 Graber, Steffen Pepperl+Fuchs GmbH Comment Type Ε Comment Status A ΕZ MDI+, MDI- signals are named BI DA+ and BI DA- in the rest of the document SuggestedRemedy Change MDI+, MDI- to BI DA+, BI DA-Response Response Status C ACCEPT. SC 146.2 P 82 L 37 C/ 146 # 16 Graber, Steffen Pepperl+Fuchs GmbH ΕZ Comment Type T Comment Status A RXD<7:0> (MII is only 4 bits wide) SuggestedRemedy RXD<3:0> Response Response Status C ACCEPT. C/ 146 SC 146.2.1 P 83 L 17 # 17 Graber, Steffen Pepperl+Fuchs GmbH Comment Type Comment Status A ΕZ Chapter headlines 146.2.1 to 146.2.2.3 SuggestedRemedy Please remove these chapter headlines. Response Response Status C

ACCEPT.

Cl 146 SC 146.3.4.1 P95 L3 # [18]

Graber, Steffen Pepperl+Fuchs GmbH

Comment Type T Comment Status D State Diagram

(pcs\_reset = ON) + (receiving = FALSE) \* [(loc\_rcvr\_status = NOT\_OK) + (link\_status = FAIL) + (rcv\_jab\_detected = TRUE)]

SuggestedRemedy

Change to (pcs\_reset = ON) + [(receiving = FALSE) \* [(loc\_rcvr\_status = NOT\_OK) +

(link\_status = FAIL) + (rcv\_jab\_detected = TRUE)]]

Proposed Response Response Status Z

REJECT.

This comment was WITHDRAWN by the commenter.

The \* operator takes precedence and adding extra levels of parentheses does not improve clarity, consistent with resolution of comment 190 on draft 1.0

Comment Type T Comment Status A

State Diagram

An additional state ("WAIT SCRAMBLER") for descrambler synchronization is required for the state machine to wait until the descrambler is in sync before going into "IDLE" state. Otherwise in case the descrambler is not synchronized, it is possible that the state machine hangs in "BAD DELIMITER" state until jabber is detected and the state machine is resetted. Then the state machine is in "IDLE" state again, but not receiving valid idle data as the descrambler is not synchronized. In this case the state machine jumps from the "IDLE" state into "BAD DELIMITER" state again without syncing the descrambler, thus ending up in an endless loop.

SuggestedRemedy

Add additional state "WAIT SCRAMBLER" as described in presentation "PCS Receive State Diagram" to the PSC receive state diagram.

Response Status C

ACCEPT IN PRINCIPLE.

Add additional state as shown on slide 2 of Graber\_3cg\_01\_0318.pdf, aligning input conditions editorially with draft and the resolution of comment 18.

Cl 146 SC 146.3. Graber, Steffen	<b>4.1</b>	L 28 ns GmbH	# 20		Cl 146 SC 146.4.4. Graber, Steffen	2 P104 Pepperl+Fu	L 43 chs GmbH	# 24	
Comment Type <b>E</b> RSTCD * (valid_disp	Comment Status A preset =FALSE) (add space bef	ore FALSE)		EZ	Comment Type <b>E</b> Missing new line befo	Comment Status A re 'minwait_timer'			EZ
SuggestedRemedy RSTCD * (valid_disp	preset = FALSE)				SuggestedRemedy  Add new line before 'r	minwait_timer' to have the sa	ame style as for ot	ther sections.	
Response ACCEPT.	Response Status C				Response ACCEPT.	Response Status C			
Cl 146 SC 146.3. Graber, Steffen	<b>4.1</b>	L 36 ns GmbH	# 21		Cl 146 SC 146.4.4. Graber, Steffen	3 P105 Pepperl+Fu	L 1 chs GmbH	# 25	
Comment Type <b>E</b> RSTCD *(Rxn = ES	Comment Status <b>A</b> D_ERR4) (missing space before	e opening bracke	t)	EZ	Comment Type <b>E</b> State diagram. (remo	Comment Status A ve dot)			EZ
SuggestedRemedy RSTCD * (Rxn = ES	SD_ERR4)				SuggestedRemedy State diagram				
Response ACCEPT.	Response Status C				Response ACCEPT.	Response Status C			
Cl 146 SC 146.4. Graber, Steffen	<b>4.1</b>	L 16 ns GmbH	# 22		Cl 146 SC 146.5.1 Graber, Steffen	P <b>106</b> Pepperl+Fu	L 46 chs GmbH	# 26	
Comment Type <b>E</b> Misalignment of 'det	Comment Status A tected.'			EZ	Comment Type <b>E</b> EMC tests. (remove of	Comment Status A			EZ
SuggestedRemedy Please align the wor	rd 'detected.' below 'Reliable op	eration .'.			SuggestedRemedy EMC tests				
Response ACCEPT.	Response Status C				Response ACCEPT.	Response Status C			
Cl 146 SC 146.4. Graber, Steffen	<b>4.2</b>	L 40 ns GmbH	# 23		Cl 146 SC 146.5.4. Graber, Steffen	1 P 108 Pepperl+Fu	L 35 chs GmbH	# 27	
Comment Type <b>E</b> Missing new line be	Comment Status A fore 'maxwait_timer'			EZ	Comment Type <b>E</b> . peak-to-peak in usin	Comment Status A g normal driving levels . (ren	nove 'in')		EZ
SuggestedRemedy Add new line before	· 'maxwait_timer' to have the sar	ne style as for ot	her sections.		SuggestedRemedy . peak-to-peak using	normal driving levels .			
Response ACCEPT.	Response Status C				Response ACCEPT.	Response Status C			
ACCEPT.					ACCEPT.				

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 27

Page 4 of 37 3/6/2018 4:20:48 PM

C/ 146 SC 146.5.4.1 P 108 L 42 # 28 C/ 146 SC 146.5.4.4 P 109 **L8** # 31 Graber, Steffen Graber, Steffen Pepperl+Fuchs GmbH Pepperl+Fuchs GmbH Comment Type Ε Comment Status A F7 Comment Type Ε Comment Status A PMADefault setting is to use Auto-Negotiation (missing dot at the end of the sentence) , for the 2.4 Vpp operating mode, (it seems to make sense to add also a reference to the mode using normal driving levels, as this is described in other parts of the standard). SuggestedRemedy SuggestedRemedy Default setting is to use Auto-Negotiation. . for the 2.4 Vpp operating mode using normal driving levels . Response Response Status C Response Response Status C ACCEPT. ACCEPT IN PRINCIPLE. See comment 33: C/ 146 SC 146.5.4.2 P 108 L 48 The additional text is unnecessary and can lead to the conclusion that there is the 1Vpp Graber, Steffen Pepperl+Fuchs GmbH operating mode, as well as an additional mode using the 1Vpp + some unspecified reduced driving levels. Comment Type T Comment Status A Editorial See also 146.5.5 for normalized test pattern. (there are no more normalized test patterns C/ 146 SC 146.5.4.4 P 109 L 8 # 32 as they have been replaced by a PSD mask definition). Graber, Steffen Pepperl+Fuchs GmbH SuggestedRemedy Comment Type Ε Comment Status A F7 Please remove sentence. . operating mode and and 1.2 ± 1.0 dBm. (remove second 'and') Response Response Status C SugaestedRemedy ACCEPT. . operating mode and 1.2 ± 1.0 dBm ... C/ 146 SC 146.5.4.4 P 109 L7 # 30 Response Response Status C Graber, Steffen Pepperl+Fuchs GmbH ACCEPT. Comment Type Ε Comment Status A PMA (normal operation) add 'in Idle mode' to be consistent with the description of the test mode on page 107, line 30. SuggestedRemedy

Response

Response Status C

ACCEPT IN PRINCIPLE.

(normal operation in Idle mode)

While test mode 3 is supposed to be in idle mode, the specification is meant to reflect normal operation, not just idle mode.

Change "(normal operation)" to "(reflecting normal operation)"

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

C/ 146 SC 146.5.4.4 C/ 146 P 109 L 8 # 33 SC 146.5.4.4 P 109 L 13 # 35 Graber, Steffen Graber, Steffen Pepperl+Fuchs GmbH Pepperl+Fuchs GmbH Comment Type Ε Comment Status A PMAComment Type Ε Comment Status A F7 , for the 1.0 Vpp operating mode, (it seems to make sense to add also a reference to the , are considered in PSD measurement, (add 'the' before 'PSD measurement') mode using reduced driving levels, as this is described in other parts of the standard). SugaestedRemedy SuggestedRemedy , are considered in the PSD measurement. . for the 1.0 Vpp operating mode using reduced driving levels. Response Response Status C Response Response Status C ACCEPT. ACCEPT IN PRINCIPLE. The additional text is unnecessary and can lead to the conclusion that there is the 1Vpp C/ 146 SC 146.5.4.4 P 109 L 40 operating mode, as well as an additional mode using the 1Vpp + some unspecified Graber, Steffen Pepperl+Fuchs GmbH reduced driving levels. Comment Type Comment Status A ΕZ Ε Editorial license to change all occurances of "normal/reduced driving levels" to square brackets in Equation (146-7) 2.4Vpp/1.0Vpp operating modes. SuggestedRemedy Change 146.5.6 (P111 L47) from: "2.76 Vpp for the normal driving levels and 1.15 Vpp for Please remove the square brackets in Equation (146-7) the reduced driving levels" to "2.76 Vpp for the 2.4 Vpp operating mode and 1.15 Vpp for the 1.0 Vpp operating mode" Response Response Status C ACCEPT. Change 146.5.4.1 (P108 L35) from: "The transmitter output voltage shall be 2.4 V ± 5 % peak-to-peak in using normal driving SC 146.5.4.4 P 109 C/ 146 L 51 levels and 1.0 V ± 5 % peak-to-peak using reduced driving levels." to: Pepperl+Fuchs GmbH "The transmitter output voltage have two modes - one with a 2.4 V ± 5 % peak-to-peak (the Graber, Steffen 2.4 Vpp operating mode) and one with 1.0 V ± 5 % peak-to-peak (the 1.0 Vpp operating Comment Type ΕZ Ε Comment Status A mode)." square brackets in Equation (146-9) Change 146.5.6 (P111 L47) from: "2.76 Vpp for the normal driving levels and 1.15 Vpp for SuggestedRemedy the reduced driving levels" to "2.76 Vpp for the 2.4 Vpp operating mode and 1.15 Vpp for Please remove the square brackets in Equation (146-9) the 1.0 Vpp operating mode" Response Response Status C C/ 146 SC 146.5.4.4 P 109 19 # 34 ACCEPT. Graber, Steffen Pepperl+Fuchs GmbH # 38 Comment Status A F7 C/ 146 SC 146.5.4.4 P 110 L 1 Comment Type Ε Graber, Steffen Pepperl+Fuchs GmbH using the test fixture 2 shown in Figure 146-18, (it seems to make sense to remove the '2' as the text fixture is already described by the reference to Figure 146-18 or alternatively Comment Type Comment Status A ΕZ also name the Figure 146-18 accordingly) . is the frequency in MHz (add dot at the end of the sentence) SugaestedRemedy SuggestedRemedy . using the test fixture shown in Figure 146-18. . is the frequency in MHz. Response Response Status C Response Response Status C ACCEPT. ACCEPT.

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 38

Page 6 of 37 3/6/2018 4:20:48 PM

C/ 146 SC 146.5.4.4 P 110 # 39 C/ 146 P 113 # 42 L 11 SC 146.6.2 L 9 Graber, Steffen Graber, Steffen Pepperl+Fuchs GmbH Pepperl+Fuchs GmbH Comment Type Т Comment Status A EΖ Comment Type E Comment Status A F7 Lower PSD mask for 2.4 Vpp and 1.0 Vpp shows a wrong corner frequency of 4 MHz . can be selected by setting bits 1.2100.14 (BASE-T1L PMA/PMD Control Register) . instead of 2.5 MHz (therefore also the PSD values at 5 MHz are too high) (change 'bits' to 'bit' and BASE-T1L to BASE-T1, as this is the universal register for the BASE-T1 PHYs) SuggestedRemedy SuggestedRemedy Please change drawing to fit Equations (146-7) and (146-9). . can be selected by setting bit 1.2100.14 (BASE-T1 PMA/PMD Control Register) . Response Response Status C Response Response Status C ACCEPT. ACCEPT. SC 146.5.5.3 P 111 # 40 C/ 146 L 33 C/ 146 SC 146.6.3 P113 L 22 Graber, Steffen Pepperl+Fuchs GmbH Graber, Steffen Pepperl+Fuchs GmbH Comment Type Comment Status A F7 Ε Comment Type T Comment Status A Management . within the PHY into account.. (remove second dot) Only a few of the relevant registers are given in Table 146-4, other registers are missing. SuggestedRemedy SuggestedRemedy . within the PHY into account. Change Table 146-4 according to presentation "MDIO Register Mapping" Response Response Status C Response Response Status C ACCEPT. ACCEPT IN PRINCIPLE. See presentation Graber\_3cg\_02\_0318.pdf, slide 2. C/ 146 SC 146.5.6 P 111 L 46 # 41 Change "Reduced transmit level" to "Transmit voltage amplitude control" both in the table Graber, Steffen Pepperl+Fuchs GmbH and in the corresponding entry in Clause 45. Do not add "10BASE-T1L test mode control register" row Comment Type Ε Comment Status A ΕZ Do not add rows for Transmit fault bit or Receive fault bit status. When measured with 100 O  $\pm$  0.1 % termination, transmit differential signal at MDI shall be . (add 'the' before 'transmit' and 'the' before 'MDI') C/ 146 SC 146.7.1.3 P115 L 37 # 44 SuggestedRemedy Pepperl+Fuchs GmbH Graber, Steffen When measured with 100 O ± 0.1 % termination, the transmit differential signal at the MDI Comment Type E Comment Status A Link Segment shall be . Maximum link delay (TBD) (remove (TBD)) Response Response Status C SuggestedRemedy ACCEPT. Maximum link delay Response Response Status C ACCEPT IN PRINCIPLE. Resolved with comment#157

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 44

Page 7 of 37 3/6/2018 4:20:48 PM

C/ 146 SC 146.7.1.3 P 115 # 45 C/ 146 SC 146.1 # 47 L 39 P 121 L 39 Graber, Steffen Graber, Steffen Pepperl+Fuchs GmbH Pepperl+Fuchs GmbH Link Segment Comment Type Т Comment Status A Comment Type Ε Comment Status A F7 8834 ns (this value is calculated back from AWG14 cable insertion loss, thus estimating a . current implementation on evaluation board takes about 20 bit times maximum). This is a maximum possible length of 1589 m with 5.6 ns per m; typically AWG14 cable has a higher reference to an example implementation, please remove this text. RL than AWG18 cable, thus the IL is due to reflections at the MDI also higher and the SugaestedRemedy possible reach is lower: suggestion is to calculate with a maximum link segment length of Remove text "current implementation on evaluation board takes about 20 bit times 1500 m with 5.6 ns per m. which leads to 8400 ns of maximum link delay time; when maximum)" changing the maximum link delay time, also the timer values of Clause 98 have to be adopted accordingly, see therefore also presentation "Clause 98 Timer Values"). Response Response Status C SuggestedRemedy ACCEPT IN PRINCIPLE. Remove the text "current implementation on evaluation board takes about 20 bit times Define 8400 ns and change the low speed mode timer values mentioned in presentation maximum)" "Clause 98 Timer Values" within the draft on pages 59 to 61 and in the respective PICS on AND pages 64 and 65. Remove the editor's note on lines 31 to 36 with similar content. Response Response Status C Cl 146 ACCEPT IN PRINCIPLE. SC 146.11.4.1.1 P 124 L 28 # 48 Add sentence under first paragraph. Graber, Steffen Pepperl+Fuchs GmbH The delay is derived from the point-to-point 14 AWG link segment length of 1589 m given in Table 200A-1 using Equation 80-1 with NVP of 0.6. Comment Type Ε Comment Status A ΕZ Convert Sdn[3:0] to ternary pair (replace pair by triplet (4B3T coding instead of 3B2T Change Clause 98 Timer Values within the draft on pages 59 to 61 and in the respective coding is being used for 10BASE-T1L)) PICS on pages 64 and 65 according to SugaestedRemedy http://www.ieee802.org/3/cg/public/Mar2018/Graber 3cg 03 0318.pdf for the link segment delay 8834 ns. Convert Sdn[3:0] to ternary triplet Response Response Status C

C/ 146 SC 146.8.3 P 119 L 8 # 46 Graber, Steffen Pepperl+Fuchs GmbH ΕZ Comment Type Ε Comment Status A Return loss (add (f) after Return loss, to align this Equation with other Equations with

frequency dependency within this standard draft)

SuggestedRemedy Return loss(f)

Response Response Status C

ACCEPT.

ΕZ Comment Type Comment Status A The PCS shall be placed in loopback mode when the loopback bit in MDIO register 3.0.14. defined in 45.2.3.1.2 is set to a one. (There is an additional bit, 3.2278.14, which is defined

in the PHY specific register set, with the same loopback functionality.)

P 126

Pepperl+Fuchs GmbH

SuggestedRemedy

ACCEPT.

Graber, Steffen

C/ 146

The PCS shall be placed in loopback mode when the loopback bit in MDIO register 3.0.14, defined in 45.2.3.1.2, or the loopback bit in MDIO register 3.2278.14, defined in 45.2.3.58a.2. is set to a one.

Response Response Status C ACCEPT.

SC 146.11.4.1.3

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 49

L 6

Page 8 of 37 3/6/2018 4:20:49 PM

C/ 146 SC 146.11.4.2.1 P 126 # 50 C/ 146 L 37 SC 146.11.4.6 P 130 L 26 # 54 Graber, Steffen Graber, Steffen Pepperl+Fuchs GmbH Pepperl+Fuchs GmbH Comment Type Ε Comment Status A F7 Comment Type E Comment Status A F7 146.4.2 (font size does not fit) Less than 6.2 us (64 bit times) (should be 6.4 us instead of 6.2 us) SuggestedRemedy SuggestedRemedy Align font size with rest of the text. Less than 6.4 us (64 bit times) Response Response Status C Response Response Status C ACCEPT. ACCEPT. C/ 146 SC 146.11.4.2.1 P 126 # 51 C/ 147 SC 147.2.2.2 P 135 L 5 Graber, Steffen Pepperl+Fuchs GmbH Graber, Steffen Pepperl+Fuchs GmbH Comment Type T Comment Status A ΕZ Comment Type Comment Status A ΕZ Ε Contribute to the receive fault bit specified in 45.2.1.7.5 (PHY specific register is missing) . if such error is detected, a ESDERR symbol is sent .. SuggestedRemedy SuggestedRemedy Contribute to the receive fault bit specified in 45.2.1.7.5 and 45.2.1.174b.7 . if this error is detected, then an ESDERR symbol is sent .. Response Response Status C Response Response Status C ACCEPT. ACCEPT IN PRINCIPLE. Change "detected, a ESDERR" to "detected, an ESDERR" SC 146.11.4.2.2 P 128 L 5 C/ 146 C/ 146 SC 146A P 175 L 13 # 56 Graber, Steffen Pepperl+Fuchs GmbH Graber, Steffen Pepperl+Fuchs GmbH Comment Type Comment Status A ΕZ Ε Comment Type T Comment Status A Safety . by setting bits 1.2294.12 as . (change 'bits' to 'bit') As specific references in Annex 146A to other standards are critical to maintain, when the SuggestedRemedy other standards change, they should be avoided and a more generic text should be used. . by setting bit 1.2294.12 as . SuggestedRemedy Response Response Status C Replace text on page 175 by text provided in presentation "Intrinsically Safe Applications". ACCEPT. Response Response Status C ACCEPT IN PRINCIPLE. C/ 146 SC 146.11.4.2.2 P 128 L 26 # 53 Replace text on page 175 Lines 12-34 (the entire body text) with text on slide 2 of Graber, Steffen Pepperl+Fuchs GmbH presentation Graber\_3cg\_04\_0318.pdf. With the following changes: Change "Nevertheless the chosen 10BASE-T1L specification eases the realization of Comment Type Comment Status A F7 Ε intrinsically safe systems." to "Nevertheless the specification of 10BASE-T1L in Clause . for the 1 Vpp transmit amplitude . (everywhere else in the standards draft 1.0 Vpp is being 146 is intended to be compatible with implementation of intrinsically safe systems." used) Change "A PHY with the following options would be beneficial:" SuggestedRemedy to "The following implementation choices can simplify the process for certifying 10BASE-. for the 1.0 Vpp transmit amplitude . T1L PHYs in intrinsically safe systems:" Response Response Status C ACCEPT.

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 56

Page 9 of 37 3/6/2018 4:20:49 PM

CI 00 SC P3# 57 L 1 Graber, Steffen Pepperl+Fuchs GmbH Comment Type Ε Comment Status A F7 , specifies additions to and appropriate modifications to add 10 Mb/s, (remove 'to' after 'additions') SuggestedRemedy . specifies additions and appropriate modifications to add 10 Mb/s. Response Response Status C ACCEPT. Replace "specifies additions to and" with "specifies additions and" C/ 00 SC P 3 L 4 Graber, Steffen Pepperl+Fuchs GmbH Comment Type Comment Status R ΕZ copper (in Keywords section most of the words start with a capital letter, should be uniform) SuggestedRemedy Copper Response Response Status C REJECT. Chief Editor confirmed with Pete Anslow that previous practice has not been to capitalize all of the entries in the keywords (see "copper" in the 802.3bw Keyword list, for example).

C/ 00 SC 0	P11	L <b>48</b>	# 59	
Maguire, Valerie	The Siemon	Company		
Comment Type E	Comment Status A			ΕZ

There are two companion documents. Pete Anslow has provided proposed text.

#### SuggestedRemedy

Replace, "A companion document IEEE Std 802.3.2 defines YANG modules for legacy shared (CSMA/CD) and dedi-cated links in point-to-point and point-to-multipoint architectures (Ethernet Passive Optical Networks, EPON), as well as Power over Ethernet (PoE) ports." with "Two companion documents exist, IEEE Std 802.3.1 and IEEE Std 802.3.1 describes Ethernet management information base (MIB) modules for use with the Simple Network Management Protocol (SNMP). IEEE Std 802.3.2 describes YANG data models for Ethernet. IEEE Std 802.3.1 and IEEE Std 802.3.2 are updated to add management capability for enhancements to IEEE Std 802.3 after approval of those enhancements."

#### Response Status C

ACCEPT. Replace, "A companion document IEEE Std 802.3.2 defines YANG modules for legacy shared (CSMA/CD) and dedi-cated links in point-to-point and point-to-multipoint architectures (Ethernet Passive Optical Networks, EPON), as well as Power over Ethernet (PoE) ports." with "Two companion documents exist, IEEE Std 802.3.1 and IEEE Std 802.3.1 describes Ethernet management information base (MIB) modules for use with the Simple Network Management Protocol (SMMP). IEEE Std 802.3.2 describes YANG data models for Ethernet. IEEE Std 802.3.1 and IEEE Std 802.3.2 are updated to add management capability for enhancements to IEEE Std 802.3 after approval of those enhancements."

CI 00 SC 0 P11 L 26 # 60

Maguire, Valerie The Siemon Company

Comment Type E Comment Status A EZ

It's recommended to flag the new frontmatter text with an editor's note so that this material

will be sure to be reviewed when the document goes out for Working Group review.

#### SuggestedRemedy

Insert Editors note with the text, "Editor's Note: New front matter text needs review."

Response Status C

ACCEPT. Insert Editors note with the text, "Editor's Note: New front matter text needs review."

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 60

Page 10 of 37 3/6/2018 4:20:49 PM

C/ 146 SC 146.7.1.4 P 115 1 42 # 61

Maquire, Valerie The Siemon Company

Comment Type Т Comment Status A Link Seament

Be clear that the parameter of differential to common mode conversion applies to unshielded cabling only.

SuggestedRemedy

Change the sub-clause header from, "146.7.1.4 Differential to common mode conversion" to "146.7.1.4 Differential to common mode conversion (unshielded only)".

Response Response Status C

ACCEPT IN PRINCIPLE.

Modify first sentence to be explicit that 146.7.1.4 applies to unshielded link segments.

The differential to common mode conversion requirement applies to unshielded link segments and depends on the electromagnetic noise environment.

C/ 146 SC 146.7.1.4 P 115 L 43 # 62

The Siemon Company Maguire, Valerie

Comment Type Т Comment Status A Link Segment

Align the structure of the first sentence in clause 146.7.1.4 with the first sentence of 146.7.1.5.

SuggestedRemedy

Replace, "requirements of unshielded link segments" with "requirements of the unshielded link seament".

Response Response Status C

ACCEPT IN PRINCIPLE.

Resolved with comment#61

C/ 146 SC 146.7.1.5 P116

L 13

# 63

Comment Type T

Comment Status A

Link Seament

F7

Be clear that the parameter of coupling attenuation applies to shielded cabling only.

The Siemon Company

SugaestedRemedy

Maguire, Valerie

Change the sub-clause header from. "146.7.1.5 Coupling attenuation" to "146.7.1.5 Coupling attenuation (shielded only)" and change the text on line 14 from "of the link seament" to "of the shielded link seament".

Response Response Status C

ACCEPT IN PRINCIPLE.

Ε

Modify first sentence to be explicit that 146.7.1.5 applies to unshielded link segments.

The coupling attenuation requirement applies to shielded link segments and depends on the electromagnetic noise environment.

C/ 00 SC 0 P 11 L 36 # 64

Maguire, Valerie The Siemon Company

Overview of amendment is incorrect. Update with new text provided by David Law.

Comment Status A

SugaestedRemedy

Comment Type

Replace, "This amendment increases the maxi-mum PD power available by utilizing all four pairs in the specified structured wiring plant." with "This amendment adds power delivery using all four pairs in the structured wiring plant, resulting in greater power being available to end devices. This amendment also allows for lower standby power consumption in end devices and adds a mechanism to better manage the available power budget."

Response Status C Response

ACCEPT. Replace. "This amendment increases the maxi-mum PD power available by utilizing all four pairs in the specified structured wiring plant." with "This amendment adds power delivery using all four pairs in the structured wiring plant, resulting in greater power being available to end devices. This amendment also allows for lower standby power consumption in end devices and adds a mechanism to better manage the available power budget."

CI 00  $SC_0$ P 11 # 65 L 41 The Siemon Company Maquire, Valerie Comment Type Ε Comment Status A EΖ

Overview of amendment is incorrect. Update with new text provided by David Law.

SuggestedRemedy

Replace, "This amendment includes changes to IEEE Std 802.3-201x and its amendments, and adds Clause 136 through Clause 140, Annex 135A, Annex 135B, Annex 135C. Annex 135D. Annex 135E. Annex 135F. Annex 135G. Annex 136A. Annex 136B. Annex 136C, and Annex 136D. This amendment adds new Media Access Control (MAC) parameters, Physical Layer specifications, and management parameters for the transfer of IEEE 802.3 format frames at 50 Gb/s. 100 Gb/s. and 200 Gb/s." with "This amendment includes changes to IEEE Std 802.3-201x and its amendments, and adds Clause 131 through Clause 140 and Annex 135A through Annex 136D. This amendment adds MAC parameters. Physical Lavers, and management parameters for the transfer of IEEE 802.3 format frames at 50 Gb/s. 100 Gb/s, and 200 Gb/s."

Response Status C Response

ACCEPT. Replace, "This amendment includes changes to IEEE Std 802.3-201x and its amendments, and adds Clause 136 through Clause 140. Annex 135A, Annex 135B, Annex 135C, Annex 135D, Annex 135E, Annex 135F, Annex 135G, Annex 136A, Annex 136B, Annex 136C, and Annex 136D. This amendment adds new Media Access Control (MAC) parameters. Physical Laver specifications, and management parameters for the transfer of IEEE 802.3 format frames at 50 Gb/s, 100 Gb/s, and 200 Gb/s." with "This amendment includes changes to IEEE Std 802.3-201x and its amendments, and adds Clause 131 through Clause 140 and Annex 135A through Annex 136D. This amendment adds MAC parameters, Physical Layers, and management parameters for the transfer of IEEE 802.3 format frames at 50 Gb/s, 100 Gb/s, and 200 Gb/s."

C/ 147 SC 147.4.1.3.2 P 147 L 29 # 66 The Siemon Company Maguire, Valerie ΕZ

Comment Type Comment Status A

Typo

SuggestedRemedy

Replace, "UppePSD" with "UpperPSD" in equation (147-1).

Response Response Status C

ACCEPT

Change "UppePSD(f)" to "UpperPSD(f)" in the equation

C/ 147 P 150 SC 147.6.3 L 29 # 67

Maguire, Valerie The Siemon Company

Comment Type E Comment Status A

Capitalization error

SuggestedRemedy

Replace. "ModeconversionLoss" with "ModeConversionLoss" in equation (147-5).

Response Response Status C

ACCEPT.

C/ 146 SC 146.7.1.1 P 114 L 20

Horrmeyer, Bernd Phoenix Contact

Comment Type ER Comment Status A

Graph starts at approximately 5 dB. Smallest value when calculating insertion loss by Equation (146-14) is 10.3 dB

SuggestedRemedy

Change the smallest value of the graph to 10.3 dB

Response Response Status C

ACCEPT IN PRINCIPLE.

Resolved with comment#156

C/ 146 SC 146.7.1.2 P 115 L8 # 69

Horrmeyer, Bernd Phoenix Contact

Comment Type T Comment Status R

Why does specified range starts at 0.1 MHz? When measuring in such a low frequency range, measuring dynamics can become crucial

SuggestedRemedy

If the frequency range is necessary, specify it but do not require a measurement at low frequencies

Response Response Status C

REJECT.

The 10BASE-T1L PHY is designed to operate over single balanced twisted-pair cabling that meets the link segment requirements. The link segment specification does not include measurement specifications.

The frequency range is specified to sufficiently characterize link segment performance to support 3 level Pulse Amplitude Modulation (PAM3) transmitted at 7.5 MBd with a Tx PSD specified from fMhz=0 to fMhz=20 MHz.

Link Segment

EΖ

ΕZ

C/ 146 SC 146.8.3 P 119 # 70 L 8 Phoenix Contact Horrmeyer, Bernd Comment Type TR Comment Status A MDI Formula 146-16 results in negative value for maximum frequency of 20 MHz SuggestedRemedy correct formula Response Response Status C

ACCEPT IN PRINCIPLE.

Add to editor's note on line 13:

"Return loss value becomes negative at 20 MHz - proposals needed to modify this"

C/ 146 SC 146.7.1.2 P 114 L 49 # 71 Schicketanz, Dieter Reutlingen University

Comment Status A Comment Type T Link Segment

Editors note:

SuggestedRemedy

If agreed match values below 1 MHz to: 15 dB down to 0.6 MHz; 9+10f from .1 to .6 MHz

Response Response Status C

ACCEPT IN PRINCIPLE. Resolved with comment#72.

C/ 146 SC 146.7.1.2 P 114 / 49 # 72

Schicketanz, Dieter Reutlingen University

Comment Type T Comment Status A Link Seament

Editors note:

SuggestedRemedy

If not agreed the comment presented for draft 1.0 should be adaptet to change RI between 10 to 20 MHz from 19 to 24-5log(f)

Response Response Status C

ACCEPT. Equation and figure slide 5 of cited presentation diminico 01 0318.pdf.

C/ 146 SC 146.7.1.6 P 116 L 42 # 73

Schicketanz, Dieter Reutlingen University

Comment Type T Comment Status R Link Seament Table 146-7 shows some TBD, and comments before relating that values need to be

found. If We refer to the MICE Table with the known E1, E2, and E3 the values are given in international Standards. If we want other values we cannot call them Ex anymore.

SuggestedRemedy

Leave the table as in Draft 1.0 and add the rows with static discharge and transient burst. It was mentioned in Geneva that they were missing. Add a note below the Table note: There is a transition below 100 MHz in measurements because it gets unrealistic to measure down to .1 MHz; it would need setups in the 100m range. For coupling attenuation and shielding effectiviness it can be assumed that the limits below 30 MHz will never be lower. For differential to commen mode conversion it is similar because the values are measurend usually at short lenght.

Response Response Status C

REJECT.

The note on P115, L50 states, the basis for coupling attenuation TBDs for the electromagnetic environment are not adequately specified (TBD) for the link segment frequency range 0.1 MHz-20 MHz.

In 8023cg D1p0.pdf the Table 146-8-Electromagnetic classiesfications 10BASE-T1L link segment for Radiated RF - AM are specified from 80 MHz.

Regarding static discharge and transient burst, be explicit in additions to the table and rationale.

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Cl 146 SC 146.7.1.4 P115 L 50 # 74
Schicketanz, Dieter Reutlingen University

Comment Type T Comment Status A Link Segment

editors notes on page 115,116

SuggestedRemedy

Delete editors notes and replace Tables 146-5 and 146-6 with the values presented in Schicketanz 122017 10SPE 01 adhoc.pdf pages 7 and 8

Response Status C

ACCEPT IN PRINCIPLE.

Adopt table slide 9 of diminico\_01\_0318.pdf without TBDs for TCL and change 60 to 63 and remove one "-".

For ELTCTL use the TCL in table slide 9 in diminico\_01\_0318.pdf and the 146.7.1.1 Insertion loss to derive the limit for ELTCTL.

Add editors note. The proposed table values are based on cabling measurements that need to be aligned with the electromagnetic classifications Table 146-7.

Cl 146 SC 146.7.2.3 P117 L 41 # 75
Schicketanz. Dieter Reutlingen University

Comment Type E Comment Status A Link Segment

There is a change in alien FEXT specification. Till now IEEE802.3 specified PSAACR-F. For the first time now PSAFEXT limit is specified. The advantage is that no power backoff is necesary anymore but puts the burden on the components and installation.

SuggestedRemedy

To avoid misunderstandings this should be mentiond with a note after the introduction at line 45. Note: This is an improved definition not to be confused with PSAACR-F.

Response Response Status C

ACCEPT IN PRINCIPLE.

Add sentence to paragraph P117, L45.

Note that the MDAFEXT is specified as the power sum of the individual alien FEXT disturbers (PSAFEXT) and not individual alien ACRF disturbers (PSAACR-F).

Cl 146 SC 146.8.1 P118 L28 # 76

Schicketanz, Dieter Reutlingen University

Comment Type T Comment Status A

MDI Connectors. Liaison letters were send out to this subject. Responses should be

MDI Connectors. Liaison letters were send out to this subject. Responses should be included in the discussion.

SuggestedRemedy

Responses should be included in the discussion before making decisions.

Response Response Status C

ACCEPT IN PRINCIPLE. No change to draft

C/ 147 SC 147.6 P150 L1 # 77

Schicketanz, Dieter Reutlingen University

Comment Type T Comment Status A Link Segment

There are no link specifications for multidrop, link length and number of connections are missing also. 25m with 8 drops is a challenging target.

SuggestedRemedy

As the values till now are the same for both add in the Title multidrop. Add below that the link length is 15 m and number of connections is 4 for point-to-point and 25m and no additional connections for multidrop. Introductory words like in T1L page 113 would be useful. (no additional conneccions means that only the drops will disturb)

Response Status C

ACCEPT IN PRINCIPLE.

The 147 link segment subclause needs structure similar 146 as well as the addition of MDI and environmental subclause consistent with structure of 146.

Editor given license to implement.

Motion: Move that the IEEE P802.3cg Task Force accept slide 5 of jonesyseboodt\_3cg\_01a\_0318.pdf as an additional resolution to comment 77 Editor note: this motion changes the MDI fault sections: 146.8.4 and 147.8.3

MDI

C/ 147 SC 147.6 P 150 # 78 C/ 200 P 179 L 36 SC 200A.1 / 1 # 81 Schicketanz, Dieter Reutlingen University Schicketanz, Dieter Reutlingen University Link Segment Link Segment Comment Type Т Comment Status A Comment Type T Comment Status R The complete clause needs some wording and explanations for mode conversion and Annex 200 contains useful information but they are informative. Only clause 200A.1.1.1.2 limits for Alien Noise. could be considered normative. It was discussed like this in Geneva SuggestedRemedy SuggestedRemedy Rewrite the complete clause using 802.3bw clause 147.6 as guidance (adding alien noise). Change Normative to informative, and if necessary delete clause 200A.1.1.1.2 and insert in the main body as subclause 146.7.2.4 (link performance) Response Response Status C Response Response Status C ACCEPT IN PRINCIPLE. Resolved with comment#77. REJECT. L 52 C/ 147 SC 147.6 P 150 The Annex includes requirements for class power (normative) and associated PICS. Schicketanz, Dieter Reutlingen University 200A.1.1.1.2 Point-to-point class power requirements Comment Type T Comment Status A Link Segment The minimum continuous power that the PSE shall be capable of supplying (Ppd) for the MDI Clause missing 1000 m link seament is given inTable 200A-2 for each class. SuggestedRemedy copy MDI clause 96.8 from 802.3bw C/ 146 SC 146.10 P 121 L 39 Response Response Status C Xu. Davin Rockwell Automation ACCEPT IN PRINCIPLE. Resolved with comment#77. Comment Type Comment Status A Delav Delete "current implementation on evaluation board takes about 20 bit times maximum) ' C/ 147 SC 147.6 P 150 L 52 # 80 Schicketanz, Dieter Reutlingen University SuggestedRemedy Delete "current implementation on evaluation board takes about 20 bit times maximum) " Comment Type T Comment Status A Link Segment Response Response Status C Envinronmental specification clause missing ACCEPT IN PRINCIPLE. SuggestedRemedy Delete "current implementation on evaluation board takes about 20 bit times maximum) " copy clause 96.9 from 802.3bw as per comment, as well as Editor's note at lines 31-35. Response Response Status C C/ 147 SC 147.2 P 133 L 6 # 83 ACCEPT IN PRINCIPLE, Resolved with comment#77. Xu, Davin **Rockwell Automation** Comment Type E Comment Status A ΕZ change "plca\_en signal" to "plca\_en" SuggestedRemedy change "plca\_en signal" to "plca\_en" Response Response Status C ACCEPT.

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 83

Change "plca en signal" to "plca en"

Page 15 of 37 3/6/2018 4:20:49 PM

C/ 147 SC 147.2.2 # 84 C/ 147 P 138 L 10 SC 147.2.3 P 139 L 12 # 87 Xu, Dayin **Rockwell Automation** Xu, Dayin Rockwell Automation Comment Type Т Comment Status A State Diagram Comment Type E Comment Status A Editorial In Figure 147-4 "transmitting <= ENCODE(pcs\_txdn)" in the DATA state is wrong. SILENCE is also defined in 147.2.2.1. should be included here SuggestedRemedy SuggestedRemedy Change "For the definition of pcs reset, SYNC, ." to "For the definition of pcs reset, change "transmitting <= ENCODE(pcs txdn)" to "tx sym <= ENCODE(pcs txdn)" SILENCE, SYNC, ." Response Response Status C Response Response Status C ACCEPT. ACCEPT IN PRINCIPLE. Change "transmitting" to "tx sym" - Change "For the definition of pcs\_reset, SYNC" to "For the definition of pcs\_reset, SILENCE, SYNC" C/ 147 SC 147.2.2 P 138 L 13 # 85 - Change "147.2.2.1 and following." to "147.2.2.2." Xu. Davin **Rockwell Automation** Note the change of 1 to 2 Comment Type Comment Status A State Diagram Т C/ 147 SC 147.2.3.1 P 139 L 32 # 88 The condition to keep in DATA state is not clear Xu. Davin Rockwell Automation SuggestedRemedy Comment Type E Comment Status A PCS Add "ELSE" on the transtion from DATA to DATA itself. SILENCE has already been defined in 147.2.2.1 Response Response Status C SugaestedRemedy ACCEPT IN PRINCIPLE. Delete "SILENCE" variable definition. - 147-3: Arrow connecting "SILENT" to "SYNC1" should have the label "STD \* pcs txen = Response Response Status C - 147-3: Arrow connecting "SILENT" to "SILENT" should have the label "STD \* pcs txen = ACCEPT IN PRINCIPLE. FALSE" - 147-4; Arrow connecting "DATA" to "ESD" should have the label "STD \* pcs txen = Already dealt with by #87 FALSE" C/ 147 SC 147.2.3.2 P 139 L 37 # 89 - 147-4: Arrow connecting "DATA" to "DATA" should have the label "STD \* pcs txen = TRUE" Xu, Dayin Rockwell Automation Comment Type T Comment Status A State Diagram C/ 147 SC 147.2.2 P 138 / 29 # 86 sym rx is not defined, should be RX Xu, Dayin Rockwell Automation SuggestedRemedy Comment Status A Comment Type T State Diagram Change "sym\_rx" to "RX" Missed STD on the transition from GOOD ESD to SILENT Response Response Status C SuggestedRemedy ACCEPT. Add "STD" on the transition from GOOD ESD to SILENT Change "sym\_rx" to "RX" Response Response Status C

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

ACCEPT.

Add "STD" on the transition from "GOOD ESD" to "SILENT"

Comment ID 89

Page 16 of 37 3/6/2018 4:20:49 PM

C/ 147 SC 147.2.3 P 140 L 19 # 90 C/ 148 P 159 SC 148.4.4.1.1 L 35 # 93 Xu, Dayin Xu, Dayin Rockwell Automation Rockwell Automation Comment Type Т Comment Status A Editorial Comment Type T Comment Status A F7 Rxn-4 is not consistant with "RX" variable definition This sub-clause is only about the BEACON request, not about the BEACON indication. SuggestedRemedy Change Rxn-4 to RXn-4; search other Rxs in Figure 147-5 and replace them with RXs Change the title from "BEACON request and indication" to "BEACON request" Response Response Response Status C Response Status C ACCEPT IN PRINCIPLE. ACCEPT. Change <all> case sensitive pattern "Rxn" to "RXn" to keep consistentcy of the clause. Change the title from "BEACON request and indication" to "BEACON request" Note: at the time of comment resolution 8 occurrences were found C/ 146 SC 146.1 P 79 L 19 C/ 147 SC 147.2.3 P 140 L 19 # 91 Xu. Davin Rockwell Automation Rockwell Automation Xu, Dayin Comment Type E Comment Status A ΕZ ΕZ Comment Type T Comment Status A Missed a space between 10BASE-T1L and PHY rx data<2:0> is wrong, should be rx data<3:0> SuggestedRemedy SuggestedRemedy Add a space between 10BASE-T1L and PHY Change rx data<2:0> to rx data<3:0> Response Response Status C Response Response Status C ACCEPT. (duplicate of comment 11) ACCEPT. Change "rx data<2:0>" to "rx data<3:0>" C/ 146 SC 146.1.2.1 P 81 L 24 # 95 Xu, Davin Rockwell Automation C/ 147 SC 147.2.3 P 140 L 27 # 92 Comment Status A Comment Type E ΕZ Xu, Dayin **Rockwell Automation** wrong format EΖ Comment Type T Comment Status A SuggestedRemedy rx data<2:0> is wrong, should be rx data<3:0> remove spaces between "signa" and "Is on ..." SuggestedRemedy Response Response Status C Change rx\_data<2:0> to rx\_data<3:0> ACCEPT IN PRINCIPLE. Response Response Status C Accomplished by resolution of comment 11 ACCEPT.

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Change "rx\_data<2:0>" to "rx\_data<3:0>"

C/ 146 SC 146.2 P 82 # 96 C/ 146 P 120 L 28 SC 146.9.2 L 25 # 99 Xu, Dayin Rockwell Automation Xu, Dayin Rockwell Automation Comment Type Т Comment Status A EΖ Comment Type T Comment Status A Safetv TXD<7:0> should be TXD<3:0> 10BASE-T1L is not for automotive application, so the sentence " in automotive applications, all 10BASE-T1L.. and ISO 15764" should be removed. SuggestedRemedy SuggestedRemedy Change TXD<7:0> to TXD<3:0> Remove the sentence "in automotive applications, all 10BASE-T1L... and ISO 15764". Response Response Status C Response Response Status C ACCEPT. ACCEPT. C/ 146 SC 146.2 P 82 L 27 C/ 146 SC 146.9.2.1 P 120 L 38 # 100 Rockwell Automation Xu, Dayin Xu, Dayin Rockwell Automation Comment Type T Comment Status A ΕZ Comment Type T Comment Status A Safety RXD<7:0> should be RXD<3:0> 10BASE-T1L is not for automotive application, so the paragraph "In automotive SuggestedRemedy applications, all . e) Chemical loads: ISO 167540-5 and ISO 20653" should be removed. Change RXD<7:0> to RXD<3:0> SuggestedRemedy Response Response Status C Remove the paragraph "In automotive applications, all., e) Chemical loads: ISO 167540-5 and ISO 20653" (line 38 - line 45). ACCEPT. Response Response Status C SC 146.8.4 P 119 L 24 # 98 C/ 146 ACCEPT. Xu, Dayin Rockwell Automation C/ 146 SC 146.9.2.2 P 121 L 18 # 101 Comment Type T Comment Status A MDI Xu, Dayin Rockwell Automation 10BASE-T1L is not for automotive application, so the paragraph " For automotive applications . is/are removed" should be removed. Comment Type T Comment Status A Safety SuggestedRemedy 10BASE-T1L is not for automotive application, so the paragraph " In automotive applications, . ISO 7637-2/3" from line 18 to line 25 should be removed. Remove the paragraph of "For automotive applications . is/are removed". SugaestedRemedy Response Response Status C Remove the paragraph "In automotive applications, . ISO 7637-2/3" from line 18 to line 25 ACCEPT. Response Response Status C ACCEPT.

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

C/ 148 SC 148.4.4.1.2 P 159 L 50 # 102 Xu. Davin Rockwell Automation Comment Type т Comment Status A EΖ This sub-clause is only about the COMMIT request, not about the COMMIT indication. SuggestedRemedy Change the title from COMMIT request and indication" to COMMIT request Response Response Status C ACCEPT. Change the title from COMMIT request and indication" to COMMIT request" C/ 148 SC 148.4.4.2.1 P 160 L 25 # 103 Xu. Davin Rockwell Automation Comment Status A Comment Type Editorial text changes proposed SuggestedRemedy Change "When the PHY receives a BEACON indication from the master, it shall convery

Response Status C

ACCEPT.

asserting MII signals ."

BEACON request is generated by RS via MII to have the PHY to send BEACON on the line.

BEACON indication is generated by the PHY via MII to notify the RS that a BEACON is being received

this information to the RS by asserting MII signals ." to "When the PHY receives a

BEACON request from the master PHY, it shall indicate this information to the RS by

EDITOR: Change "When the PHY receives a BEACON indication from the master, it shall convey this information to the RS by asserting MII signals." to "When the PHY receives a BEACON, it shall indicate this information to the RS by asserting MII signals"

Cl 148 SC 148.4.4.2.2 P160 L 34 # 104

Xu, Dayin Rockwell Automation

Comment Type E Comment Status A Editorial

text changes proposed

SuggestedRemedy

Change "When the PHY receives a COMMIT indication from another PHY, it shall convery this information to the RS by asserting MII signals ." to "When the PHY receives a COMMIT request from another PHY, it shall indicate this information to the RS by asserting MII signals ."

Response Status C

ACCEPT IN PRINCIPLE.

COMMIT request is generated by RS via MII to have the PHY to send COMMIT on the line.

COMMIT indication is generated by the PHY via MII to notify the RS that a COMMIT is being received

Change "When the PHY receives a COMMIT indication from another PHY, it shall convey this information to the RS by asserting MII signals" to "When the PHY receives a COMMIT from the line, it shall indicate this information to the RS by asserting MII signals"

Cl 148 SC 148.4.5.1 P161 L 50 # 105

Xu, Dayin Rockwell Automation

Comment Type E Comment Status A Editorial

text changes proposed

SuggestedRemedy

Change "assumes the indication of the PHY ." to "assumes the early receive indication of the PHY ."  $\,$ 

Response Status C

ACCEPT.

Change "assumes the indication of the PHY" to "assumes the early receive indication of the PHY"

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 105

Page 19 of 37 3/6/2018 4:20:49 PM

C/ 147 SC 147.2.2.1 L 52 C/ 147 SC 147.2.1 P 133 P 133 # 106 L 1 # 109 Huszák, Gergelv Kone Beruto, Piergiorgio Canova Tech Comment Type Ε Comment Status A State Diagram Comment Type E Comment Status A F7 The term "SSD symbol group" is incorrect (SSD is a standalone 5B symbol, not a group of Comment #267 on draft 1.0 was approved but not fully implemented in draft 1.1 those). Moreover the wording does not harmonize with the rest of the clause SuggestedRemedy SuggestedRemedy In figure 147-2 change "plca\_en signal" arrow (from MANAGEMENT to PCS TRANSMIT Change "one SSD symbol group" to "an SSD" block) to "plca en" Response Response Response Status C Response Status C ACCEPT IN PRINCIPLE. ACCEPT. Change "one SSD symbol group" to "an SSD" Already dealt with by #83 Note: this is editor's own comment, rooted in a discussion directly following D1.0 resolution Cl 147 SC 147.2.1 P 133 / 1 # 110 C/ 147 SC 147.2.3 P 139 L 2 # 107 Beruto. Piergiorgio Canova Tech Huszák, Gergely Kone Comment Type E Comment Status A F7 Comment Type Comment Status A Editorial In figure 147-2 the MII signals should be named as in clause 22 The term "the SSD symbol" does not harmonize with the rest of the clause SuggestedRemedy SuggestedRemedy replace "TXCLK" with "TX CLK". replace "RXCLK" with "RX CLK". replace "RXDV" with Change "the SSD symbol" to "an SSD" "RX DV", replace "RXER" with "RX ER" Response Response Response Status C Response Status C ACCEPT. ACCEPT. - Replace "TXCLK" with "TX\_CLK" Change "the SSD symbol" to "an SSD" - Replace "RXCLK" with "RX CLK" Note: this is editor's own comment, rooted in a discussion directly following D1.0 resolution - Replace "RXDV" with "RX DV" - Replace "RXER" with "RX ER" C/ 147 SC 147.2.5 P 142 / 18 # 108 Huszák, Gergely Kone C/ 147 P 138 SC 147.2.2.3 L 20 # 111 Comment Type E Comment Status A Editorial Beruto, Piergiorgio Canova Tech The term "SSD symbol" does not harmonize with the rest of the clause Comment Type E Comment Status A State Diagram SuggestedRemedy In figure 147-4 some errors occurred when porting the picture to Frame from draft 1.0 Change "SSD symbol" to "SSD" SuggestedRemedy Response Response Status C In figure 147-4 substitute "STD err = TRUE" with "STD \* err = TRUE" in all transitions from ACCEPT. ESD state; add "STD" in transition from GOOD ESD to "B". See attached PDF. Change "the SSD symbol" to "an SSD" Response Response Status C Note: this is editor's own comment, rooted in a discussion directly following D1.0 resolution ACCEPT IN PRINCIPLE. - Change 2 times "STD <NL> err =" to STD \* err =" Note: second part of the comment has already been dealt with by #86

C/ 147 SC 147 2 2 3 C/ 147 SC 147.3.2 P 145 P 138 L 11 # 112 L 18 # 115 Beruto, Piergiorgio Canova Tech Beruto, Piergiorgio Canova Tech Comment Type Ε Comment Status A EΖ Comment Type E Comment Status A State Diagram In figure 147-4 in DATA state, pcs txen is a typo. It should be pcs txer. Figure 147-8 porting from draft 1.0 is incomplete SuggestedRemedy SuggestedRemedy In figure 147-4 replace "err <= err + pcs txen" with "err <= err + pcs txer" Copy figure from draft 1.0. See attached PDF Response Response Status C Response Response Status C ACCEPT. ACCEPT IN PRINCIPLE. Change "err <= err + pcs txen" to "err <= err + pcs txer" - Add a center-aligned "x x x" to the "DATA" state of DME TX" - Add the 4 missing horizontal bars being part of the C/ 147 SC 147.2.3.3 P 140 L 1 # 113 Note: See/use "Figure 0-5" of "8023\_lewis\_figs\_0p8.pdf" Beruto, Piergiorgio Canova Tech C/ 147 SC 147.5.1.2 P 149 / 17 # 116 Comment Type E Comment Status A State Diagram Beruto, Piergiorgio Canova Tech Multiple errors occurred when porting figure 147-5 to Frame from draft 1.0 Comment Type E Comment Status A **PMD** SuggestedRemedy Figure 147-11 porting from draft 1.0 is incomplete In state WAIT SYNC add space between pcs rxd and <= symbol. See attached PDF. SugaestedRemedy Replace text in state WAIT SSD with text in draft 1.0. See attached PDF. Replace text in state PRE1 with text in draft 1.0. See attached PDF. Copy figure from draft 1.0. See attached PDF In transition from BAD SSD state to WAIT SYNC state replace the "RXn != SILENCE" Response Response Status C with "RXn = SILENCE". ACCEPT. From all state when entering WAIT SYNC state replace "<=" assignment symbol with "=" comparison symbol. - Add "stub1" to the top-right side of the left stup - Add "stub2" to the top-right side of the right stup Response Response Status C Note: See/use "Figure 0-7" of "8023 lewis figs 0p8.pdf" ACCEPT IN PRINCIPLE. Make all changes highlighted on slide 6/17 of beruto\_3cg\_03\_0318.pdf C/ 148 SC 148.4.2 P 157 L 8 # 117 Beruto, Piergiorgio Canova Tech C/ 147 SC 147.2.3.3 P 141 / 1 # 114 F7 Comment Type E Comment Status A Beruto, Piergiorgio Canova Tech In figure 148-2 the MII signals should be named as in clause 22 Comment Type E Comment Status A State Diagram SuggestedRemedy Multiple errors occurred when porting figure 147-6 to Frame from draft 1.0 replace "TXCLK" with "TX CLK", replace "TXEN" with "TX EN", replace "TXER" with SuggestedRemedy "TX ER" Add text in state DATA copying from draft 1.0. See attached PDF. Response Response Status C Response Response Status C ACCEPT. ACCEPT. In figure 148-2 replace "TXCLK" with "TX\_CLK", replace "TXEN" with "TX\_EN", replace Make all changes highlighted on slide 8/17 of beruto 3cg 03 0318.pdf "TXER" with "TX ER"

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 117

Page 21 of 37 3/6/2018 4:20:49 PM

C/ 148 SC 148.4.5.1 L 12 C/ 148 P 164 # 118 SC 148.4.6.1 P 168 L 1 # 121 Beruto, Piergiorgio Canova Tech Beruto, Piergiorgio Canova Tech Comment Type Ε Comment Status A Editorial Comment Type E Comment Status A Editorial In figure 148-4 variable "framePending" should be renamed to "packetPending" Figure 148-5 should be updated integrating changes in the vellow boxes SuggestedRemedy SugaestedRemedy In figure 148-4 replace all occurrences of "framePending" with "packetPending" Replace figure 148-5 as in attached PDF Response Response Status C Response Response Status C ACCEPT. ACCEPT IN PRINCIPLE. In figure 148-4 replace all occurrences of "framePending" with "packetPending" Replace figure 148-5 as in Beruto 3cg 01 0318.pdf C/ 148 SC 148.4.5.1 P 164 L 46 # 119 C/ 148 SC 148.4.6.1 P 168 L 1 # 122 Beruto. Piergiorgio Canova Tech Beruto. Piergiorgio Canova Tech Comment Status A Comment Type E Comment Status A Editorial Comment Type E Editorial In transition from "NEXT\_TS" state to "WAIT\_TO" state there should be an "ELSE" Text formatting in figure 148-5 is not clear. SuggestedRemedy SuggestedRemedy In figure 148-4 add "ELSE" to transition between NEXT\_TS state to WAIT\_TO state in figure 148-5 substitute "SIGNAL STATUS? SIGNAL ERROR if COL = TRUE Response Response Status C NO\_SIGNAL\_ERROR else" with "if COL = TRUE SIGNAL\_STATUS <= SIGNAL\_ERROR ACCEPT. else SIGNAL STATUS <= NO SIGNAL ERROR" In figure 148-4 add "ELSE" to transition between NEXT\_TS state to WAIT\_TO state substitute "CARRIER\_STATUS? C/ 148 SC 148.4.5.1 P 164 L 46 # 120 CARRIER ON if plca crs = TRUE CARRIER OFF else" with "if plca CRS = TRUE CARRIER STATUS <= CARRIER ON Beruto, Piergiorgio Canova Tech else CARRIER STATUS <= CARRIER OFF" Comment Type E Comment Status A PI CA Response Response Status C NEXT\_TS state should be named NEXT\_TO (which stands for NEXT Transmit Opportunity) ACCEPT. SuggestedRemedy in figure 148-5 substitute "SIGNAL STATUS? SIGNAL ERROR if COL = TRUE In figure 148-4 replace NEXT\_TS with NEXT\_TO NO SIGNAL ERROR else" with "if COL = TRUE SIGNAL STATUS <= SIGNAL ERROR Response Response Status C else SIGNAL STATUS <= NO SIGNAL ERROR" ACCEPT IN PRINCIPLE. substitute "CARRIER STATUS? In figure 148-4 change "NEXT\_TS" to "NEXT\_TX\_OPPORTUNITY" CARRIER ON if plca crs = TRUE CARRIER OFF else" with "if plca CRS = TRUE CARRIER STATUS <= CARRIER ON else CARRIER STATUS <= CARRIER OFF"

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 122 Page 22 of 37 3/6/2018 4:20:49 PM

SC 148 4 6 1 C/ 147 SC 147.2.1 P 133 C/ 148 P 169 L 1 # 123 L 1 # 126 Beruto, Piergiorgio Canova Tech Beruto, Piergiorgio Canova Tech Comment Status A Comment Type Ε Comment Status A Editorial Comment Type E EΖ Text formatting in figure 148-6 is not clear. Figure 147-2 porting from draft 1.0 is incomplete SuggestedRemedy SuggestedRemedy in figure 148-6, in both TRANSMIT and FLUSH states substitute "SIGNAL\_STATUS <= add label "transmitting" on arrow between PCS TRANSMIT block to PCS RECEIVE block SIGNAL ERROR if COL = TRUE Response Response Status C NO SIGNAL ERROR else" with "if COL = TRUE SIGNAL STATUS <= SIGNAL ERROR else SIGNAL STATUS <= NO SIGNAL ERROR" ACCEPT. Add label "transmitting" to arrow between "PCS TRANSMIT" and "PCS RECEIVE" blocks Response Response Status C ACCEPT. C/ 147 SC 147.3.2 P 145 L 3 # 127 in figure 148-6, in both TRANSMIT and FLUSH states substitute "SIGNAL STATUS <= Beruto, Piergiorgio Canova Tech SIGNAL ERROR if COL = TRUE NO SIGNAL ERROR else" with "if COL = TRUE SIGNAL STATUS <= SIGNAL ERROR Comment Type E Comment Status A ΕZ else SIGNAL STATUS <= NO SIGNAL ERROR" "PDM" should be "PMD" (2 times) SuggestedRemedy C/ 148 SC 148.4.6.1 P 169 / 1 # 124 Substitute "When in multidrop mode, the PDM shall be put into high-impedance/Z state" Beruto, Piergiorgio Canova Tech with "When in multidrop mode, the PMD shall be put into high-impedance/Z state" F7 Comment Type E Comment Status A In figure 148-6 TXEN should be TX\_EN Substitute "While in point-to-point mode, the PDM shall drive" with "While in point-to-point mode, the PMD shall drive" SuggestedRemedy Response Response Status C In figure 148-6 substitute "TXEN" with "TX EN" ACCEPT IN PRINCIPLE. Response Response Status C Already dealt with by #181 ACCEPT. In figure 148-6 substitute "TXEN" with "TX EN" C/ 147 SC 147.2.1 P 133 L 4 # 128 Canova Tech Beruto, Piergiorgio C/ 148 SC 148.4.5.1 P 163 / 13 # 125 Comment Type T Comment Status A ΕZ Beruto, Piergiorgio Canova Tech Collision detection shall be disabled when operating in full-duplex mode Comment Type T Comment Status A PI CA SuggestedRemedy In figure 148-3, the transition from RECOVER state to RECOVER state should be done In figure 147-2 add an arrow named "duplex mode" from MANAGEMENT to COLLISION whenever some activity is sensed on the media ("plca eri"), not only when a good **DETECTION and PCS RECEIVE blocks** receiving is ongoing ("plca crs"). This to avoid collision when BEACON is sent Response Response Status C SuggestedRemedy In figure 148-3 substitute "plca crs = TRUE" with "plca eri = TRUE" in transition from ACCEPT. Add an arrow named "duplex mode" from "MANAGEMENT" to " COLLISION RECOVER state to RECOVER state DETECTION" and to "PCS RECEIVE" Response Response Status C Note: this is a new arrow (not present in D1.0)

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

In figure 148-3 substitute "plca crs = TRUE" with "plca eri = TRUE" in transition from

ACCEPT.

RECOVER state to RECOVER state

Comment ID 128

Page 23 of 37 3/6/2018 4:20:49 PM

Cl 147 SC 147.2.2.3 P135 L 34 # 129

Beruto, Piergiorgio Canova Tech

Comment Type E Comment Status D Editorial

Suggest to add a page break before table 147-1 to avoid the split and improve readability

SuggestedRemedy

Add page break before table 147-1

Proposed Response Status Z

REJECT.

This comment was WITHDRAWN by the commenter.

Discussed and rejected earlier (= current layout conforms standard clause formatting rules)

Cl 147 SC 147.2.3.1 P139 L33 # 130

Beruto, Piergiorgio Canova Tech

Comment Type T Comment Status A PCS

In order to support full-duplex mode, the PCS RX block should be configured accordingly

SuggestedRemedy

Appen the following variable description to the "Variables" subclause:

"duplex\_mode

indicates whether the PHY is configured for full-duplex operation (DUPLEX\_FULL) or half-duplex operation (DUPLEX\_HALF). This variable is set after bit 8 in MDIO register 0 defined in table 22-7"

Response Status C

ACCEPT.

Add the following to "147.2.3.1 Variables":

====

"duplex\_mode

indicates whether the PHY is configured for full-duplex operation (DUPLEX\_FULL) or half-duplex operation (DUPLEX\_HALF). This variable is set after bit 8 in MDIO register 0 defined in table 22-7"

====

Note: "table 22-7" is a reference

Cl 147 SC 147.2.3.1 P140 L2 # 131

Beruto, Piergiorgio Canova Tech

Comment Type T Comment Status A State Diagram

In order to support full-duplex mode, the PCS RX block should behave accordingly

SuggestedRemedy

In figure 147-5 replace "transmitting <= TRUE" with "(transmitting = TRUE \* duplex\_mode = DUPLEX\_HALF)"

Response Status C

ACCEPT.

In figure 147-5 replace "transmitting <= TRUE" (second line from top) with "(transmitting = TRUE \* duplex mode = DUPLEX HALF)"

Cl 148 SC 148.4.5.1 P 162 L 22 # 132

Beruto, Piergiorgio Canova Tech

Comment Type T Comment Status A Editorial

Editor's note about figures 148-3 and 148-4 can now be removed

SuggestedRemedy

Remove first Editor's Note

Response Status C

ACCEPT.

Remove first Editor's Note

Cl 148 SC 148.4.5.2 P165 L 37 # 133

Beruto, Piergiorgio Canova Tech

Comment Type T Comment Status A

MAX ID can be left unconfigured on slave devices, myID shall not depend on it

SuggestedRemedy

Change "Values: integer value from 0 (MASTER) to MAX\_ID" to "Value: integer value from 0 (MASTER) to 255".

Response Status C

ACCEPT. Change "Values: integer value from 0 (MASTER) to MAX\_ID" to "Value: integer value from 0 (MASTER) to 255".

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 133 Page

Page 24 of 37 3/6/2018 4:20:49 PM

**PLCA** 

SC 148.4.5.2 C/ 148 P 165 L 37 # 134 Beruto, Piergiorgio Canova Tech Comment Type Ε Comment Status A EΖ Missing carriage return before "Values:" SuggestedRemedy Add carriage return at line 37 before "Value:" Response Response Status C ACCEPT. Add carriage return at line 37 before "Value:" C/ 146 SC 146.8 P 118 L 38 # 135 Fritsche, Matthias **HARTING Technology** 

Comment Type T Comment Status A

MDI

SPE is a new physical layer and to define a plug and work system a new MDI is needed. RJ45 is reserved and used for the 2-pair and 4-pair Ethernet standards.

#### SuggestedRemedy

Alternatively for applications with lower environmental requirements a two pin shielded IP20 connector according to IEC 61076-3-125 or a two pin unshielded connector according to IEC 63171-1 shall be used in conformance to the requirements of the link segment defined in 146.7.

## Response Status C

#### ACCEPT IN PRINCIPLE.

Change "Alternatively for applications with lower environmental requirements a standard RJ45 connector may be

used. In this case pin 3 (BI\_DA+) and pin 6 (BI\_DA-) of the RJ45 connector shall be used."

to

"Alternatively for applications with lower environmental requirements a TBD connector may be used. In this case pin TBD (BI\_DA+) and pin TBD (BI\_DA-) of the connector shall be used."

and insert "Editor's note (to be removed prior to Working Group ballot): Commenters are encouraged to provide better specificity of "lower environmental requirements", e.g., MICE1 or IP20."

Cl 146 SC 146.9.1 P120 L15 # 136

Fritsche, Matthias HARTING Technology

Comment Type E Comment Status A

Safetv

IEC 60950-1 is only valid up to end of 2019 and is replaced with IEC 62368-1. We should use the new safety standard

#### SuggestedRemedy

Replace "IEC 60950-1" with " IEC 62368-1 (former IEC 60950-1)"

Response Status C

ACCEPT IN PRINCIPLE.

Add "or IEC 62368-1" after "IEC 60950-1"

C/ 146 SC 146.11.4.5 P130 L6 # 137

Fritsche, Matthias HARTING Technology

Comment Type E Comment Status A

Safetv

IEC 60950-1 is only valid up to end of 2019 and is replaced with IEC 62368-1. We should use the new safety standard

#### SuggestedRemedy

Replace "IEC 60950-1" with " IEC 62368-1 (former IEC 60950-1)"

Response Status C

ACCEPT IN PRINCIPLE.
Align with comment 136.
add "or IEC 62368-1" after "IEC 60950-1"

Cl 146 SC 146.8 P118 L34 # 138

Fritsche, Matthias HARTING Technology

Comment Type T Comment Status A

*MDI* mount

If we just specify a four pin M8/M12 or 7/8" connector, it is possible to use a bigger amount of different M8/M12 coding's from example A, B, D, and other coding's. All oth this codings are defined for special non SPE use cases only. To define a plug and work system for the market it must be defined more precisely.

#### SuggestedRemedy

For industrial applications also a two or four pin shielded M8/M12 connector according to IEC 61076-3-125 shall be used in conformance to the requirements of the link segment defined in 146.7.

Response Status C

#### ACCEPT IN PRINCIPLE.

Insert "according to IEC 61076-3-125" to read: "For industrial applications also a four pin M8/M12 according to IEC 61076-3-125 or a four pin 7/8" connector may be used as long as it conforms to the requirements of the link segment defined in 146.7."

C/ 01 SC 1.5 P 24 C/ 148 SC 148.4.2 P 157 L 12 L 32 # 139 # 142 NXP NXP Pandey, Sujan Pandey, Sujan Comment Type ER Comment Status A EΖ Comment Type TR Comment Status A **PLCA PLCS** What is the size of PLCA delay unit? SuggestedRemedy SuggestedRemedy **PLCA** Specify the size Response Response Status C Response Response Status C ACCEPT. Replace "PLCS" on line 32 with "PLCA" (Same resolution proposed for ACCEPT IN PRINCIPLE. comments #139, #3, and #188) Delay is variable, and it's described in PLCA DATA State Machine. Solved by #144 C/ 148 C/ 147 SC 147.3.3 P 145 L 39 # 140 SC 0 Ρ # 143 Pandev. Suian NXP Pandev. Suian NXP Comment Status A ΕZ Comment Type T Comment Status A Editorial Comment Type TR The symbol sequence J/J/J/K which replaces the first 16 bit of packet preamble muvID should be renamed SuggestedRemedy SuggestedRemedy The symbol sequence J/J/J/K which replaces the first 20 bit of packet preamble local ID Response Response Response Status C Response Status C ACCEPT IN PRINCIPLE. ACCEPT IN PRINCIPLE. Change "J/J/J/K which replaces the first 16 bit of" to "J/J/J/K which replaces the first 20 I would propose naming it nodelD (to be discussed with the group) bits of" EDITOR: Search and replace all occurrences of "myID" variable with "local nodeID" C/ 148 SC 148.4.2 P 157 L 33 # 141 C/ 148 SC 148.4.2 P 157 L 12 # 144 NXP Pandey, Sujan Pandey, Sujan NXP Comment Type TR Comment Status R PI CA Comment Type T Comment Status A Editorial Figure 148-2 is misleading. Figure tells that gRS will not be a part of PHY and PLCA state machines are defined outside of the PHY. Is this according to the objective of 802.3cg? delay line is not a good name SuggestedRemedy SuggestedRemedy Figure should be drawn such that PLCA RS layer should be inside the PHY **FIFO** Response Response Status C Response Response Status C REJECT. ACCEPT IN PRINCIPLE. The Reconciliation Sublaver (RS) is part of a PHY project, translating the MAC/PLS service FIFO suggests a specific implementation, I think we should be more generic. interface to signals for the PHY, and the figure is in line with other Reconciliation sublayers in 802.3 EDITOR: replace "PLCA delay line" with "variable delay line"

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 144

Page 26 of 37 3/6/2018 4:20:49 PM **PLCA** 

Cl 148 SC 148.4.6.1 P168 L1 # [145]
Pandey, Sujan NXP

Comment Type T Comment Status A

Figure 148-5: The variable a and b should be more descriptive

9

SuggestedRemedy

Response Status C

ACCEPT IN PRINCIPLE.

NOTE: malformed comment, no suggested remedy is present. But there's a problem with the figure.

EDITOR: In figure 148-5 add a re-circulating ARC on FLUSH state with condition "MCD \* a != b" with '!=" being the "not equal" sign.

At page 170, line 38: replace "a, b" description with the following TWO descriptions (one for 'a' and one for 'b'):

"a current delay counter"

"b flush counter"

Cl 22 SC 22.2.2.4 P L # 146
Pandey, Sujan NXP

Pandey, Sujan NXF

Comment Type T Comment Status R PLCA

in Table 22-1 & 22-2. Why do we need these new codes over this interface if the MAC in an SoC or Bridge is not to be modified per this project? See the Objectives.

SuggestedRemedy

Please clarify with NOTES in the draft.

Response Status C

REJECT. These new codes do not change either the Ethernet frame format at the MAC client service interface, the frame size of the current IEEE 802.3 standard, or the speed from 10 Mb/s at the interface, per the objectives. They are used as part of the new Reconciliation Sublayer, as defined in Clause 148, and the text in the second paragraph of 22.2.4 provides a description of the purpose and points to clause 148. Clause 22 is the Reconciliation Sublayer (RS), not the MAC, which is a valid target for a PHY project and within the objectives. The purpose of the signals is clear - to communicate the RS PLCA BEACON, and PLCA COMMIT. IEEE 802.3 style, evidenced by the inclusion of LPI by EEE, does not support the addition of a note to the table.

Cl 147 SC 147.4.1 P146 L 26 # 147

Zerna, Conrad Fraunhofer

Comment Type T Comment Status A PMA

Replace "generated by PRBS7 with the generating polynomial of x^7+x^6+1." with

SuggestedRemedy

"generated by PRBS7 with the generating polynomial of x^7+x^6+1 encoded using Differential Manchester Encoding (DME) as in 147.3.2."

Response Status C

ACCEPT.

Add "encoded using Differential Manchester Encoding (DME) as in 147.3.2" between

"polynomial of  $x^7+x^6+1$ " and the closing period (".")

Note: "147.3.2" is a reference

C/ 147 SC 147.4.1.3.1 P147 L 28 # 148

Zerna, Conrad Fraunhofer

Comment Type T Comment Status D

Comment Group "TX amplitude, PSD and Emissions"

Replace

with

SuggestedRemedy

 $\begin{array}{ccc} -72 & 0.3 MHz <= f < 15 MHz \\ UppePSD(f) = \{ \, \text{-}52\text{--}1.4^*f & 15 MHz <= f < 25 MHz \, \, \} \, [dBm/Hz] \\ -86 & 25 MHz <= f \end{array}$ 

--> also presentation

Proposed Response Status Z

REJECT.


This comment was WITHDRAWN by the commenter.

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 148

Page 27 of 37 3/6/2018 4:20:49 PM

**PSD** 



TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 152

Page 28 of 37 3/6/2018 4:20:49 PM C/ 147 C/ 147 SC 147.5.1.2 P 149 L 12 # 153 SC 147.6.3 P 150 L 27 # 155 Zerna, Conrad Fraunhofer Zerna, Conrad Fraunhofer Comment Type Т Comment Status A **PMD** Comment Type Т Comment Status D Link Seament Comment Group "Multi-Drop terminations" Comment Group "TX amplitude, PSD and Emissions" Replace Replace "by two 100 Ohm (nominal) resistances at the edges"  $ModeConversionLoss(f) = \{ 43 \quad 0.3MHz \le f < 20MHz \} [dBm/Hz]$ 43-20\*log10(f/20) 20MHz <= f <= 200MHzSuggestedRemedy "by two 100 Ohm (nominal) impedances satisfying with  $RL < \{ -23dB \quad 0.3MHz <= f <= 2MHz \} [dB]$ SuggestedRemedy -23dB+10\*(f-2)/18 2MHz <= f when measured with 1000hm+-1% impedance, at the edges "  $ModeConversionLoss(f) = \{ 46 \quad 0.3MHz \le f < 20MHz \} [dBm/Hz]$ Response Response Status C 46-20\*log10(f/20) 20MHz <= f <= 200MHzACCEPT IN PRINCIPLE. - Add a new sub-clause "147.7 MDI" - Add a new sub-cluase under 147.7 MDI", called "147.7.x (1 for now) MDI Return loss" --> also presentation - Add a new for formula copied from 146.8.3 with commenter's content Proposed Response Response Status Z - Also change "resitance" to "impedance" REJECT. - See also comment #77 This comment was WITHDRAWN by the commenter. C/ 147 SC 147.5.1.2 P 149 L 16 # 154 C/ 146 SC 146.7.1.2 P 114 L 38 # 156 Zerna, Conrad Fraunhofer DiMinico, Christopher MC Communications Comment Type Т Comment Status A PMD ΕZ Comment Type T Comment Status A Comment Group "Multi-Drop terminations" Fix figure to reflect textual changes of comment group Comment # 238 D1.0 to correct Figure 146-22 was not implemented by editor. SuggestedRemedy SuggestedRemedy see jpg file "draft1p1\_correction\_fig147-11\_multidropTerm.jpg" New figure needs to be generated using Equation (146-10) values. Response Response Status C Response Response Status C ACCEPT IN PRINCIPLE. ACCEPT. - Make changes as per zimmerman 3cg 01 0318.pdf: - page 5/15: "make 147.4.1.1 to 147.4.1.4 subclauses 147.4.3.1 through 147.4.3.4" C/ 146 SC 146.7.1.3 P 115 L 36 # 157 - page 5/15: 2 items under "Specify high impedance mode and test mode:" DiMinico, Christopher MC Communications - page 6/15: 3 items - pages 7-8/15: 2 items (fix typo "146.6" to "147.6" along the way) Comment Type T Link Segment Comment Status A - moreover: change the symbol used for the 3 termination points and add the label/arrow Remove TBD: 146.7.1.3 Maximum link delay (TBD) for "stub termination" with arrow style matching that of the label "edge termination", as per the attached file (147-11.png) SuggestedRemedy - pages 9-14/15: as described (renumbering to be done at the end) Remove TBD: 146.7.1.3 Maximum link delay (TBD) - See also comment #77 Response Response Status C ACCEPT.

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 157

Page 29 of 37 3/6/2018 4:20:49 PM

Editorial

C/ 148 SC 148.1 P155 L11 # 158

Zimmerman, George CME Consulting et al

Comment Type T Comment Status A Editorial

"Currently, the 10BASE-T1S PHY in Clause 147 specifies support for PLCA Reconciliation sublayer." I think what this means is better stated as "The PLCA sublayer is specified for operation with the PHY defined in Clause 147 (10BASE-T1S)."

SuggestedRemedy

Replace "Currently, the 10BASE-T1S PHY in Clause 147 specifies support for PLCA Reconciliation sublayer." with "The PLCA sublayer is specified for operation with the PHY defined in Clause 147 (10BASE-T1S)."

Response Status C

ACCEPT.

Replace "Currently, the 10BASE-T1S PHY in Clause 147 specifies support for PLCA Reconciliation sublayer." with "The PLCA sublayer is specified for operation with the PHY defined in Clause 147 (10BASE-T1S)."

Cl 148 SC 148.2 P 155 L 19 # 159

Zimmerman, George CME Consulting et al

Comment Type E Comment Status A

The Overview section should provide a description of the function that is defined, not discuss the goal of the clause itself. Descriptive text is needed.

SuggestedRemedy

Delte existing 148.2 text. Replace with "Editor's Note (to be removed prior to Working Group ballot): High level description of the operation and specification of PLCA is needed here (description only, no requirements)"

Response Response Status C

ACCEPT.

Comment: that was copied from other clauses but I agree.

EDITOR: Delete existing 148.2 text. Replace with "Editor's Note (to be removed prior to Working Group ballot): High level description of the operation and specification of PLCA is needed here (description only, no requirements)"

C/ 148 SC 148.4.2 P157 L1 # 160

Zimmerman, George CME Consulting et al

Comment Type E Comment Status A

"(plca\_en = OFF in register TBD)" - the important thing is the variable, the implementation in a register is optional and, if implemented, will be documented elsewhere. This same "in register TBD" occurs in several places (148.4.2, 148.4.3.1, 148.4.3.3, 148.4.3.4, 148.4.5.1)

SuggestedRemedy

delete "in register TBD" in 148.4.2, 148.4.3.1, 148.4.3.3, 148.4.3.4, 148.4.5.1.

Response Status C

ACCEPT.

delete "in register TBD" in 148.4.2, 148.4.3.1, 148.4.3.3, 148.4.3.4, 148.4.5.1.

Cl 148 SC 148.4.2 P157 L # [161

Zimmerman, George CME Consulting et al

Comment Type T Comment Status A

"The following provides an overview of RS PLCA operation. The actual specification of RS PLCA operation can be found in the respective RS clauses.

When TSSI support is also specified in the actual RS, the SFD detection of transmitted frames shall be detected after the PLCA variable delay line, as shown in Figure 148-2. This ensures the network latency measurement is not affected by the synchronization latency added by PLCA. No special attention is required for SFD detection of received frames." - several problems. first, what follows is not an overview of the RS PLCA operation. that should be in the overview section and is missing. Second, the statement about TSSI is a stated as a requirement which should be called out separately - or should it be a recommentation? unclear.

SuggestedRemedy

Delete "The following provides... Respective RS clauses." Add new subclause "148.4.2.1 Operation with TSSI" and put sentences from "When TSSI support... detection of received frames" in it.

Response Status C

ACCEPT.

Delete "The following provides... Respective RS clauses." Add new subclause "148.4.2.1 Operation with TSSI" and put sentences from "When TSSI support... detection of received frames" in it.

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 161

Page 30 of 37 3/6/2018 4:20:49 PM

PI CA

Editorial

C/ 148 SC 148 4 1 P 155 C/ 148 SC 148 P 164 L 38 # 162 L 47 Zimmerman, George CME Consulting et al Zimmerman, George CME Consulting et al. Comment Type T Comment Status A Editorial Comment Type T Comment Status A "specified elsewhere in this standard" - please say what clauses you are extending Figure 148-4, arc from NEXT\_TS to WAIT\_TO has no exit condition SuggestedRemedy SuggestedRemedy Change "specified elsewhere in this standard" with "specified in Clauses ...." (whatever those clauses may be). If there are specific clauses clause 148 may or may not be used Response Response Status C with, list that information too. ACCEPT. Response Response Status C Solved by #119 ACCEPT IN PRINCIPLE. EDITOR: add "else" as exit condition Change "specified elsewhere in this standard" with "specified in Clause 22" C/ 148 SC 148.4.4.2.1 P 160 / 25 C/ 148 SC 148.4.1 P 155 L 39 # 163 Zimmerman, George CME Consulting et al Zimmerman, George CME Consulting et al. Comment Type T Comment Status A Comment Status A EΖ Comment Type T "master PHY" - the terms MASTER and SLAVE are used repeatedly and even in this "this subclause" - you mean Clause 148, not just 148.4.1, no? amendment to refer to loop timing. A different relationship is meant here for the optional PLCA RS. Using master and slave is not advised. In many places, like this one, the term SuggestedRemedy is not needed, tag: PLCA MASTER Replace "this subclause" with "Clause 148". SuggestedRemedy Response Response Status C Delete "from the master" at P 160 L25. In all other cases, term master can be omitted -ACCEPT. see other comments tagged PLCA\_MASTER Replace "this subclause" with "Clause 148". Response Response Status C # 164 ACCEPT. C/ 148 SC 148.4.3.1.2 P 158 / 11 Delete "from the master" at P 160 L25. Zimmerman, George CME Consulting et al Comment Type E Comment Status A EΖ "The values ONE and ZERO are conveved to the PLCA variable plca txd<3>...." the values are conveyed BY the PLCA variables, not to the variables... SuggestedRemedy change "to the PLCA variable " to "by the PLCA variables"

Response Status C

change "to the PLCA variable" to "by the PLCA variables"

Response

ACCEPT.

# 165

# 166

**PLCA** 

Editorial

SC 148 4 5 1 C/ 148 P 161 L 26 # 167 Zimmerman, George CME Consulting et al Comment Type T Comment Status A Editorial eliminate "master" "slave" - tag: PLCA MASTER

SuggestedRemedy

Change "When PLCA functions are enabled, the master PHY (the one having myID variable set to 0) immediately" to "When PLCA functions are enabled, the PHY with myID set to 0 immediately"

Response Response Status C

ACCEPT IN PRINCIPLE.

mvID needs to be renamed as per comment #1

EDITOR: Change "When PLCA functions are enabled, the master PHY (the one having myID variable set to 0) immediately" to "When PLCA functions are enabled, the PHY with local nodeID set to 0 immediately"

P 161 C/ 148 SC 148.4.5.1 / 28 # 168 Zimmerman, George CME Consulting et al

Comment Type T Comment Status A **Fditorial** 

"Slave PHYs wait in RESYNC state until a BEACON is sent by the master PHY." - actually they wait until a BEACON is received. Tag: PLCA MASTER

SuggestedRemedy

change "is sent by the master PHY" to "is received"

Response Response Status C

ACCEPT.

change "is sent by the master PHY" to "is received"

C/ 148 SC 148.4.5.1 P 161 L 30 # 169

Zimmerman, George CME Consulting et al

Comment Type T Comment Status A Editorial

"Both the slave PHYs and the master PHY are required to detect the end of the BEACON condition before resetting the transmit opportunity timer" - actually, All PHYs are required... Use of "are required" is discouraged too. Tag: PLCA MASTER

SuggestedRemedy

Change "Both the slave PHYs and the master PHY are required to detect the end..." to "All PHYs are detect the end..."

Response Response Status C

ACCEPT. Fixed typo

Change "Both the slave PHYs and the master PHY are required to detect the end" to "All PHYs detect the end"

C/ 148 SC 148.4.5.1 P 161 L 35 # 170

Zimmerman, George CME Consulting et al

Comment Type T "while TPD is the worst-case propagation delay time between the master and all slave

Comment Status A

PHYs." actually, TPD is the worst-case propagation delay time from end-to-end of the mixing segment. Tag: PLCA\_MASTER

SuggestedRemedy

Change "between the master and all slave PHYs" to "from end-to-end on the mixing segment."

Response Response Status C

ACCEPT.

Change "between the master and all slave PHYs" to "from end-to-end on the mixing segment."

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 170

Page 32 of 37 3/6/2018 4:20:49 PM

Editorial

Cl 148 SC 148.4.5.1 P162 L 6 # 171

Zimmerman, George CME Consulting et al

Comment Type T Comment Status A Editorial

"The recovery procedure forces a slave PHY to wait for the next BEACON and a master PHY to wait for all slave PHYs to be silent for at least RECV\_BEACON\_TIMER before sending a new BEACON." eliminate master/slave Tag: PLCA\_MASTER

#### SuggestedRemedy

Change "The recovery procedure forces a slave PHY to wait for the next BEACON and a master PHY to wait for all slave PHYs to be silent for at least RECV\_BEACON\_TIMER before sending a new BEACON." to "The recovery procedure forces the PHY with myID=0 to wait for all other PHYs to be silent for at least RECV\_BEACON\_TIMER before sending a new BEACON, and all other PHYs to wait for the next BEACON to be received."

Response Status C

ACCEPT IN PRINCIPLE.

myID renamed to nodeID as per comment #1

Change "The recovery procedure forces a slave PHY to wait for the next BEACON and a master PHY to wait for all slave PHYs to be silent for at least RECV\_BEACON\_TIMER before sending a new BEACON." to "The recovery procedure forces the PHY with nodeID=0 to wait for all other PHYs to be silent for at least RECV\_BEACON\_TIMER before sending a new BEACON, and all other PHYs to wait for the next BEACON to be received."

C/ 148 SC 148.4.5.2 P165 L36 # [172

Zimmerman, George CME Consulting et al

Comment Type T Comment Status A Editorial

"The special value '0' is assigned to the master node, indicating the PHY shall generate BEACON signals. Values: integer value from 0 (master) to MAX\_ID." - eliminate master/slave, and eliminate duplicate "shall" which is really contained in the state diagram. Tag: PLCA MASTER

#### SuggestedRemedy

Change "The special value '0' is assigned to the master node, indicating the PHY shall generate BEACON signals. Values: integer value from 0 (master) to MAX\_ID." to "The special value '0' is assigned to the PHY which generates BEACON signals. Values: integer value from 0 to MAX\_ID."

Response Status C

ACCEPT.

Change "The special value '0' is assigned to the master node, indicating the PHY shall generate BEACON signals. Values: integer value from 0 (master) to MAX\_ID." to "The special value '0' is assigned to the PHY which generates BEACON signals. Values: integer value from 0 to MAX\_ID."

C/ 148 SC 148.4.5.2 P165 L41 # 173

Zimmerman, George CME Consulting et al

Comment Type T Comment Status A Editorial

"This parameter is only meaningful for the master PHY (myID = 0). For slave PHYs, MAX\_ID is ignored." - eliminate master/slave Tag: PLCA\_MASTER

#### SuggestedRemedy

Change "This parameter is only meaningful for the master PHY (myID = 0). For slave PHYs, MAX\_ID is ignored." to "This parameter is only meaningful for the PHY with myID = 0. otherwise it is ignored."

Response Status C

ACCEPT IN PRINCIPLE.

myID should be renamed as per comment #1

Change "This parameter is only meaningful for the master PHY (myID = 0). For slave PHYs, MAX\_ID is ignored." to "This parameter is only meaningful for the PHY with nodeID = 0, otherwise it is ignored."

C/ 148 SC 148.4.5.4 P166 L11 # [174

Zimmerman, George CME Consulting et al

Comment Type T Comment Status A

Editorial

"Represents the time for which the master PHY signals a BEACON condition." - isn't this timer the duration of the BEACON? - also eliminate master/slave Tag: PLCA\_MASTER

#### SuggestedRemedy

Change "Represents the time for which the master PHY signals a BEACON condition." to "Times the duration of the BEACON signal."

Response Status C

ACCEPT.

Change "Represents the time for which the master PHY signals a BEACON condition." to "Times the duration of the BEACON signal."

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 174

Page 33 of 37 3/6/2018 4:20:49 PM

SC 148 4 5 4 C/ 148 P 166 L 30 # 175

Zimmerman, George CME Consulting et al

Comment Type T Comment Status A **Fditorial** 

"During a recovery operation the master PHY needs to wait for all slave PHYs to be silent for at least RECV\_BEACON\_TIMER before sending a new BEACON request." - a BEACON is not a request, it is a BEACON, no? - also eliminate master/slave Tag: PLCA MASTER

SuggestedRemedy

Change "During a recovery operation the master PHY needs to wait for all slave PHYs to be silent for at least RECV\_BEACON\_TIMER before sending a new BEACON request," to "During recovery, RECV\_BEACON\_TIMER times the period that all PHYs need to be silent before a new BEACON may be sent."

Response Response Status C

ACCEPT.

Change "During a recovery operation the master PHY needs to wait for all slave PHYs to be silent for at least RECV BEACON TIMER before sending a new BEACON request." to "During recovery, RECV BEACON TIMER times the period that all PHYs need to be silent

C/ 148 SC 148.4.6.1 P 168 L 9 # 176

CME Consulting et al Zimmerman, George

Comment Type E Comment Status A Editorial

Nomenclature is backwards in conditionals in state diagrams of clause 148, for example "SIGNAL STATUS <= SIGNAL ERROR IF COL = TRUE" should be " If COL = TRUE SIGNAL STATUS <= SIGNAL ERROR Else SIGNAL STATUS <= NO SIGNAL ERROR"

SuggestedRemedy

Change format to if - then - else, and put complete assignments as "then" or "else" (see example in comment.) Do this for "NORMAL". "RECEIVE" and "TRANSMIT" states in Figures 148-5 and 148-6

Response Response Status C

ACCEPT IN PRINCIPLE.

See resolutions to comments 122 and 123

in figure 148-5 substitute "SIGNAL STATUS?

SIGNAL ERROR if COL = TRUE

NO SIGNAL ERROR else" with "if COL = TRUE SIGNAL STATUS <= SIGNAL ERROR else SIGNAL STATUS <= NO SIGNAL ERROR"

substitute "CARRIER STATUS? CARRIER ON if plca crs = TRUE CARRIER OFF else" with "if plca CRS = TRUE CARRIER STATUS <= CARRIER ON else CARRIER STATUS <= CARRIER OFF"

C/ 45 P 39 SC 45.2.1.174e.5 L 4 # 177

iver, venkat microchip

Comment Type T Comment Status A PMA

how is receive polarity defined for multi-drop and DME

SugaestedRemedy

not defined

Response Response Status C

ACCEPT IN PRINCIPLE. Change registers for resevered bits in Table 45-142e from "1.2300.7:3" to "1.2300.7:3", delete the entire row for Received polarity bit 1.2300.7:2 in Table 45-142e, and delete all of clause 45.2.1.174e.5 (Receive polarity (1.2300.2)) from lines 4 through 8. Renumbering following clauses accordingly.

C/ 147 SC 147.1.2 P 131 / 40 # 178

iver, venkat microchip

Comment Type T Comment Status A Editorial

use of 'can' doesn't conform to IEEE style manual creating ambiguity and possible conflict with objectives

SuggestedRemedy

The 10BASE-T1S PHY shall opererate using half-duplex point to point...Optionally, the PHY can operate using half-duplex multi-drop...Optionally, the PHY can operate using fullduplex....

Response Response Status C

ACCEPT IN PRINCIPLE.

- Change "The 10BASE-T1S PHY can operate" to "The 10BASE-T1S PHY may operate"
- Change "Additionally, the 10BASE-T1S PHY can operate" to "Additionally, the 10BASE-T1S PHY may operate"

C/ 147 SC 147.2.2.1 P 133 L 53 # 179 iver, venkat microchip

Comment Type T Comment Status A

State Diagram in clause 147 'symbol' seems to be the more common understanding than symbol group

(sorry for back tracking change I had suggested)

SuggestedRemedy

replace symbol group with symbol

Response Response Status C

ACCEPT IN PRINCIPLE. Already dealt with by #106

C/ 147 SC 147.3.3 iyer, venkat	P 145 microchip	L <b>32</b>	# 180	C/ 147 SC 147.4.1.1 P146 L 45 # 183 iyer, venkat microchip
Comment Type T	Comment Status A		Editorial	Comment Type T Comment Status A PMA if auto negotiation is optional, how can it be the default setting?
SuggestedRemedy replace symbol groups	with symbols			SuggestedRemedy delete "default setting is to use Auto Negotiation"
Response ACCEPT. Change "5B symbol gr	Response Status C oups" to "5B symbols"			Response Response Status C  ACCEPT. Remove the whole sentence " Default setting is to use Auto Negotiation."
C/ 147 SC 147.3.2 iyer, venkat	P 145 microchip	L <b>3</b>	# 181	Cl 148 SC 148.1 P155 L7 # 184  iyer, venkat microchip
Comment Type E typo	Comment Status A		EZ	Comment Type T Comment Status A PLCA maximum latency is bad
SuggestedRemedy PDM shouldbe PMD				SuggestedRemedy replace maximum with reduced
	Response Status C  E. all be" to "the PMD shall be" all drive" to "the PMD shall dr	ive"		Response Response Status C  ACCEPT IN PRINCIPLE. This is descriptive text. I propose to just remove maximum.
C/ 147 SC 147.3.2 iver, venkat	P 145	L <b>4</b>	# 182	EDITOR: replace "maximum throughput and maximum latency" with "throughput and latency"
Comment Type E	Comment Status A		EZ	C/ 148 SC 148.4.5.2 P 165 L 35 # 185  iyer, venkat microchip
SuggestedRemedy PDM shouldbe PMD				Comment Type T Comment Status A AutoNeg "may" implies actions are part of specification. But PLCA variables negotiation is not detailed in spec
Response ACCEPT IN PRINCIPI				SuggestedRemedy delete " may also be set98"
Already dealt with by #	101			Response Response Status C  ACCEPT IN PRINCIPLE. Change "Generated by the management interface (register TBD). May also be set by the Auto-Negotiation protocol as described in Clause 98."

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn SORT ORDER: Comment ID

Comment ID 185

Page 35 of 37 3/6/2018 4:20:49 PM

C/ 148 L 43 C/ 45 SC 148.4.5.2 P 165 # 186 SC 45.2.1.174a.1 P 33 L 4 # 189 iver, venkat microchip Baggett, Tim Microchip Comment Type Т Comment Status A **AutoNea** Comment Type Ε Comment Status A F7 "may" indicates actions are part of specification. But PLCA variables negotiation is not "This operation may interrupt data communication." line is not consistent with other reset detailed in spec bit descriptions which include "NOTE -". SuggestedRemedy SuggestedRemedy Change to "NOTE - This operation may interrupt data communication." delete "MAX ID may also be set..98" Response Response Response Status C Response Status C ACCEPT IN PRINCIPLE. ACCEPT. Replace "This operation may interrupt data communication." with "NOTE - This Solved by #185 operation may interrupt data communication." and apply Paragraph tag Note EDITOR: delete "MAX ID may also be set..98" Cl 45 P 37 L7 # 190 SC 45.2.1.174d.1 Baggett, Tim Microchip Insert "Editor's Note (to be removed prior to Working Group Ballot): Specify whether and how PLCA parameters may be negotiated (e.g., Clause 98)" Comment Type Ε Comment Status A F7 "This operation may interrupt data communication." line is not consistent with other reset C/ 146 SC 146.A.1 P 176 L 13 # 187 bit descriptions which include "NOTE -". iver, venkat microchip SuggestedRemedy Comment Type Т Comment Status R Safetv Change to "NOTE - This operation may interrupt data communication." figures in annex show PHY with separate TX and RX pins Response Response Status C SuggestedRemedy ACCEPT. Replace "This operation may interrupt data communication." with "NOTE - This operation may interrupt data communication." and apply Paragraph tag Note Response Response Status C Cl 45 SC 45.2.1.174d.3 P 37 L 22 # 191 REJECT. Baggett, Tim Microchip These figures are shown as a 'possible implementation' - separate inputs are shown for Comment Type E Comment Status A ΕZ clarity and maximum flexibility. Incorrect reference to 10BASE-T1L PMA control register/bit 1,2294.11 rather than 10BASE-C/ 01 SC 1.5 P 24 L 32 # 188 T1S PMA control. Baggett, Tim Microchip SuggestedRemedy Comment Type E Comment Status A ΕZ Change "1,2294,11" to "1,2299,11" Incorrect acronym "PLCS" instead of "PLCA" Response Response Status C ACCEPT. Change "1.2294.11" to "1.2299.11" SuggestedRemedy Change "PLCS" to "PLCA" Response Response Status C

TYPE: TR/technical required ER/editorial required GR/general required T/technical E/editorial G/general COMMENT STATUS: D/dispatched A/accepted R/rejected RESPONSE STATUS: O/open W/written C/closed Z/withdrawn

ACCEPT, Replace "PLCS" on line 32 with "PLCA" (Same resolution proposed for

comments #139, #3, and #188)

# 192 Cl 45 SC 45.2.1.174d.3 P 37 L 27 Baggett, Tim Microchip Comment Type E Comment Status A EΖ Incorrect reference to 10BASE-T1L PMA control register/bit 1.2294.11 rather than 10BASE-T1S PMA control. SuggestedRemedy Change "1.2294.11" to "1.2299.11" Response Response Status C ACCEPT. Change "1.2294.11" to "1.2299.11" Cl 45 SC 45.2.1.174h.1 P 41 L 23 # 193 Baggett, Tim Microchip Comment Type **E** EΖ Comment Status A Incorrect reference section 147.5.2 should be 147.4.1 SuggestedRemedy Change "147.5.2" to "147.4.1" Response

Response Status C

ACCEPT. Change "147.5.2" to "147.4.1"