

1904.2 Support for additional/future subtypes

Glen Kramer, Broadcom

Special VLC subtypes



- In the Receive and Transmit state diagrams, only the VLC_config, OMCI_subtype, and OAM_subtype need to have special treatment.
 - VLC_config need to be receivable without provisioning of any rules (in order to setup the first rule).
 - OMCI_subtype payload is not an 802.3 compliant frame and cannot go through MA_DATA interface. It must be sent to a special interface.
 - OAM_subtype has special processing to also make it receivable without a rule, in order to make it on par with OMCI and to cut on unnecessary management traffic (the rule is always the same)
- Nothing else requires a special processing.
- After system deployment, new protocols can be tunneled simply by provisioning new rules

Location of LLC sublayer (802.1Q)




Figure 8-3—MAC Bridge architecture

Each Bridge Port also functions as an end station and shall provide the MAC Service to an LLC Entity that operates LLC Type 1 procedures to support protocol identification. multiplexing, and demultiplexing, for PDU transmission and reception by the Spanning Tree Protocol Entity and other higher layer entities. Other types of LLC procedures can also be supported for use by other protocols.

LLC is defined in IEEE 802

- Ipv4,
- IPv6.
- Slow Protocols (except OAM)
- ARP.
- many others
- > 3500 Ethertypes allocated by IEEE RA





Figure 6—LLC sublayer in 802 RM

The higher layer protocol discrimination entity (HLPDE) is used by the LLC sublayer to determine the higher layer protocol to which to deliver an LLC sublayer protocol data unit (PDU). Two methods may be used in the HLPDE. The two methods are:

- 1) EtherType protocol discrimination (EPD), which uses the EtherType value made available to the LLC sublayer through the MSAP
- 2) LLC protocol discrimination (LPD), which uses the addresses defined in ISO/IEC 8802-2, including the Subnetwork Access Protocol (SNAP) format

The EPD method shall be the primary specified means for protocol identification at the LLC sublayer in IEEE 802 standards developed after January 2011, excluding amendments to existing standards.

Path through Rx State Diagram



- Once the tunnel exit rule is applied, the xPDU will pass to Frame Relay sublayer via VLCSI:MA_DATA.indication() primitive.
- If xPDU DST_ADDR ≠ local, then the xPDU frame is relayed to another port by the Frame Relay entity.
- If xPDU DST_ADDR = local, then the xPDU is passed to the LLC sublayer for dispatching to an appropriate protocol client based on Ethertype (EPD method).

Supporting other protocol types

- All protocol types that are supported by LLC can also be supported by VLC by adding appropriate rules and without any changes to the Receive and Transmit state diagrams.
- There are three methods to support higher-layer protocols:
 - 1) Define a dedicated VLC subtype for each protocol we want to support
 - 2) Use L2 encapsulation
 - 3) Define one catch-all subtype for all higher-layer protocols

Method 1: VLC subtype for each protocol

Table 5-1—Subtype field encoding

Value	Designation	Description		
0x00	VLC_config	VLC_config subtype identifies VLC_Request and VLC_Response VLCPDUs used for configuring the VLC Classification and Translation Engine (see 6.1).		
0x01, 0x02	n/a	Reserved for VLC Discovery protocol; ignored on reception.		
0x03	OAM_Subtype	<i>OAM_Subtype</i> represents the OAMPDU payload carried within the VLCPDU (see 5.2.2).		
0x04	n/a	Reserved; ignored on reception.		
0x05	L2_subtype	L2_Subtype represents a generic Ethernet frame carried within the VLCPDU (e.g., MAC-in-MAC) (see 5.2.4).		
0x06	L3_Subtype	L3_Subtype represents a generic L3 packet (plus TPID) carried within the VLCPDU (see 5.2.5).		
0x07-0x0B	n/a	Reserved; ignored on reception.		
0x0C	OMCI_Subtype	OMCI_Subtype represents the OMCI payload carried within the VLCPDU (see 5.2.3).		
0x0D	IPv4_Subtype			
0x0E	IPv6_Subtype			
0x0F	ARP_Subtype			
•••	•••			
to 0xFD	n/a	Reserved; ignored on reception.		
0xFE	OUI24_Subtype	OUI24_Subtype represents an organization-specific payload carried within the VLCPDU. The organization is identified by a unique OUI/CID value (see 5.2.6).		
0xFF	OUI36_Subtype	OUI36_Subtype represents an organization-specific payload carried within the VLCPDU. The organization is identified by a unique OUI-36 value (see 5.2.6).		

With Method 1, we need one entrance and one exist rule per each subtype per each port

Exit rule:

```
IF( DA == local AND
    Ethertype == VLC_TYPE AND
    Subtype = XX_subtype )
THEN
    REPLACE( Ethertype, TPID);
    REMOVE( Subtype );
```

Overhead is 1 byte per VLCPDU (xPDU Ethertype is replaced with VLC Ethertype + Subtype)

8/10/2020 **7**

Method 2: L2 Encapsulation



- This is a universal subtype that can carry any L2 frame as a payload
 - Can carry any protocol
- With Method 2, we need one entrance and one exist rule per port

```
- Exit rule:
IF( DA == local AND
        Ethertype == VLC_TYPE AND
        Subtype = 0x05 )
THEN
        REMOVE( DST_ADDR );
        REMOVE( SRC_ADDR );
        REMOVE( ETHERTYPE );
        REMOVE( SUBTYPE )
```

Octets DestinationAddress 6 SourceAddress 6 LengthType = 0xA8-C82 Subtype = 0x051 L2DestAddr 6 L2SrcAddr 6 L2LengthType 2 Data $31 - N^{a}$ Pad **FCS** 4

 Overhead per VLCPDU is 15 bytes (an entire Ethernet frame header + Subtype)

a – Maximum field length depends on frame type (see Figure 5-1).

VLC


payload

Method 3: Catch-all subtype

- Catch-all subtype (L3_subtype) is already defined
- L3_subtype represents all protocols that are to be handled by LLC sublayer
 - EthertypeTPID field identifies the actual protocol
- With Method 3, we need one entrance and one exist rule per port

```
- Exit rule:
    IF( DA == local AND
        Ethertype == VLC_TYPE AND
        Subtype = 0x06 )
    THEN
        REMOVE( Ethertype );
        REMOVE( Subtype )
```

Overhead per VLCPDU is 3 bytes (VLC Ethertype + Subtype)



- a Field format depends on the value of *EthertypeTPID* field.
- b Maximum field length depends on frame type (see Figure 5-1).

Conclusion



- In the state diagrams, only the VLC_config, OMCI_subtype, and OAM_subtype need to have special treatment.
 - VLC_config need to be receivable without provisioning of any rules (in order to setup the first rule).
 - OMCI_subtype is not an 802.3 compliant frame and cannot go through MA_DATA interface. It must be sent to a special interface.
 - OAM_subtype has special processing to also make it receivable without a rule, in order to make it on par with OMCI and to cut on unnecessary management traffic (the rule is always the same)
- Nothing else requires a special processing.
- After system deployment, new protocols can be tunneled, by simply provisioning new rules

Comparing 3 methods



	Method 1 Dedicated subtype	Method 2 L2_Subtype	Method 3 L3_Subtype
Number of rules needed S = number of subtypes P = number of ports	S x P	P	P
Tunneling overhead per frame	✓ 1 byte	15 bytes	✓ 3 bytes
Scalability (how many protocols can be supported)	A new subtype is required for each supported protocol. Subtype code-point space is limited	One subtype covers all protocols	One subtype covers all protocols
Extendibility (how easy it is to add support for new protocol)	Standard needs to be modified every time a user wants to tunnel a new protocol	Any protocol can be tunneled without changes to the standard	Any protocol can be tunneled without changes to the standard

8/10/2020 **11**

Conclusion



- L3_subtype is useful as a catch-all subtype. We should keep it.
- L3_subtype provides the best balance between scalability, extendibility, tunneling overhead, and the number or rules.
- L3_subtype is a bad name, because any protocol (any Ethertype/TPID) can be tunneled, not only L3 protocols
- A better name is EPD_subtype
 - EPD = Ethertype Protocol Discrimination
 - A method to distinguish protocols based on Ethertype
 - Defined in IEEE 802
 - Default method for LLC sublayer
 - See slide 4



Thank You

8/10/2020 **13**