




Extended Edge Relay

Joe Pelissier

bg-pelissier-extendeder-0111

An Extended Edge Relay



Observations

- **A VSI can migrate to different ports on the same edge relay but across different hypervisors**

A VSID can show up on two different ports of the ER at the same time

Adding Port Index as an index into the table allows this.

- **This also calls into question where to place the base component table**

The edge relay is not necessarily tied to a single station

In fact, the combination of ERs and Port Mapping S-VLAN components is not necessarily a system

This can be addressed by eliminating the base component table

Instead, create a table in each component that provides the component identification information of their neighbor components.

Each component mib info is addressed as a separate MIB rather than using eh component id / port id approach

Thank You!