CONTENTS

F	OREWORD	<u></u> 5
IN	ITRODUCTION	<u></u> 2
1	Scope	3
2	Normative references	3
3	Terms, definitions, symbols and abbreviated terms	4
	3.1 TSN-IA defined Terms	
	3.2 List of terms and definitions given in IEC 61784-2, IEEE 802, IEEE 802.3, IEEE 802.1Q and IEEE 802.1AS	
	3.3 Abbreviated terms and acronyms	5
	3.4 Conventions	
	3.4.1 Conventions for (sub)clause selections of referenced documents	<u></u> 5
	3.4.2 Convention for Capitalizations	<u></u> 7
	3.4.3 Unit conventions	<u></u> 7
4	Conformance	<u></u> 10
	4.1 Requirements Terminology	<u></u> 10
	4.2 Profile Conformance Statement (PCS)	<u></u> 10
	4.3 Required Functions for an Industrial Network	
	4.3.1 PHY and MAC selection	<u></u> 10
	4.3.2 IEEE 802.1 selection	
	4.3.3 Security selection	<u></u> 17
	4.3.4 Other IEEE 802.1 standard selections	<u></u> 18
	4.3.5 Other profiles	
	4.3.6 Management selection	<u></u> 19
5	Industrial Automation	<u></u> 19
	5.1 Overview	<u></u> 19
	5.1.1 Control Loop Basic Model	<u></u> 19
	5.1.2 Industrial Traffic Types	<u></u> 21
	5.2 Requirements	
	5.2.1 Bridge delay requirements	<u></u> 22
	5.2.2 Network access	<u></u> 22
	5.2.3 Bridge FDB requirements	<u></u> 24
	5.2.4 Bridge resource requirements	
	5.2.5 Quantities	
	5.2.6 Synchronization requirements	
<u>Aı</u>	nnex A PCS proforma - Time-sensitive networking profile for industrial automation	
	A.1 General	
	A.2 Abbreviations and special symbols	
	A.2.1 Status symbols	<u></u> 30
	A.2.2 General abbreviations	
	A.3 Instructions for completing the PCS proforma	
	A.3.1 General structure of the PCS proforma	
	A.3.2 Additional information	<u></u> 31
	A.3.3 Exception Information	
	A.3.4 Conditional status	
	A.4 Common requirements	<u></u> 32

A.4.1 Implementation identification	<u></u> 3	2
A.4.2 Profile summary, IEC/IEEE 60802	3	8
A.4.3 Implementation type	3	8
A.4.4 Common requirements— PHY and MAC	_ 3:	ш
	_	
A.4.6 Major capabilities—Bridges	3	
A.4.7 IEEE Std 802.1Q requirements—Bridges	3	ш
•	3	П
A.4.9 Security Requirements	. <u>.</u> 3	п
	_	ш
Annex Z (informative/normative) Gaps	3	L
Bibliography	<u></u> 3	9
FOREWORD		4
NTRODUCTION		2
1—Scope		8
2—Normative references		Į
		ľ
3—Terms, definitions, symbols and abbreviated terms	····	4
3.1—TSN-IA defined Terms	····	4
3.2—List of terms and definitions given in IEC 61784-2, IEEE 802, IEEE 802.3,		
IEEE 802.1Q and IEEE 802.1AS	 '	4
3.3—Abbreviated terms and acronyms		5
3.4—Conventions		5
3.4.1——Conventions for (sub)clause selections of referenced documents		5
3.4.2 Convention for Capitalizations		7
3.4.3 Unit conventions		7
1—Overview of TSN in Industrial Automation		7
4.1—Control Loop Basic Model		7
4.2—Industrial Traffic Types		6
5—Conformance	_1	L
5.1 — Requirements Terminology	4.	Ĭ
5.2—Profile Conformance Statement (PCS)	H	ļ
	. . 1 1	ļ
S—Required Functions for an Industrial Network	14	۲
6.1—PHY and MAC selection	1	θ
6.1.1 General	1	θ
6.1.2——IEEE 802.3-2015 Selections	11	θ
6.2—IEEE 802.1 selection	1	2
6.2.1—General	1:	2
6.2.2 Bridge selections	1	2
6.2.3——Applicable amendments to IEEE 802.1Q™-2018	1	4
6.2.4 Clock synchronization selection	4	4
6.2.5 Security selection	1	þ
6.2.6 Other IEEE 802.1 standard selections	1	b
6.3 Other profiles	. 1	þ
6.4 Bridge delay requirements	_1	
6.5 Network access	_1	b
6.6 Bridge FDB requirements	1	ļ
		ľ
6.7—Bridge resource requirements	2	П
D.O. LUIZUIUUS	_	4

4 – supporting ballot comment on 60802/D1.0Step 1

6.9 Management selection	22
6.9.1 General	
6.9.2 Protocols	
Annex A PCS proforma – Time-sensitive networking profile for industrial automation	23
A.1—General	
A.2—Abbreviations and special symbols	
A.2.1—Status symbols	
A.2.2—General abbreviations	
A.3 Instructions for completing the PCS proforma	
A.3.1 General structure of the PCS proforma	
A.3.2 Additional information	
A.3.4—Conditional status.	
A.4—Common requirements	
A.4.1 Implementation identification	
A.4.2——Profile summary, IEC/IEEE 60802	
A.4.3—Implementation type	
A.4.4 — Common requirements— PHY and MAC	
A.4.5 Common requirements— Bridges	
A.4.6 Major capabilities Bridges	27
A.4.7 IEEE Std 802.1Q requirements Bridges	28
A.4.8 Time Synchronization Requirements	28
A.4.9—Security Requirements	
Annex Z (informative/normative) Gaps	31
Annex Z (informative/normative) Gaps	
	32
Bibliography	8
Bibliography Figure 1 – Principle data flow of control loop	8
Figure 1 – Principle data flow of control loop	8
Figure 1 – Principle data flow of control loop	8 22
Figure 1 – Principle data flow of control loop	82245
Figure 1 – Principle data flow of control loop Figure 2 – Delay measurement reference points Table 1 – List of terms Table 2 – Layout of profile (sub)clause selection tables Table 3 – Contents of (sub)clause selection tables	822456
Bibliography Figure 1 – Principle data flow of control loop	328224566
Figure 1 – Principle data flow of control loop	8224567
Figure 1 – Principle data flow of control loop	822456710
Figure 1 – Principle data flow of control loop	3245671011
Figure 1 – Principle data flow of control loop Figure 2 – Delay measurement reference points Table 1 – List of terms Table 2 – Layout of profile (sub)clause selection tables Table 3 – Contents of (sub)clause selection tables Table 4 – Example of a selection table that apply for multiple device types Table 5 – PHY and MAC selection within IEEE 802.3-2015 Table 6 – CP 802PHY/2 PHY selection and the MAC speeds of Amendments Table 8 – Bridge selections of current amendments to IEEE 802.1QTM-2018 Table 9 – Selection of IEEE 802.1AS-2019	32456101114
Figure 1 – Principle data flow of control loop Figure 2 – Delay measurement reference points Table 1 – List of terms Table 2 – Layout of profile (sub)clause selection tables Table 3 – Contents of (sub)clause selection tables Table 4 – Example of a selection table that apply for multiple device types Table 5 – PHY and MAC selection within IEEE 802.3-2015 Table 6 – CP 802PHY/2 PHY selection and the MAC speeds of Amendments Table 8 – Bridge selections of current amendments to IEEE 802.1QTM-2018 Table 9 – Selection of IEEE 802.1AS-2019 Table 10 – MAC-Security selection	3245610111417
Figure 1 – Principle data flow of control loop Figure 2 – Delay measurement reference points Table 1 – List of terms Table 2 – Layout of profile (sub)clause selection tables Table 3 – Contents of (sub)clause selection tables Table 4 – Example of a selection table that apply for multiple device types Table 5 – PHY and MAC selection within IEEE 802.3-2015 Table 6 – CP 802PHY/2 PHY selection and the MAC speeds of Amendments Table 8 – Bridge selections of current amendments to IEEE 802.1QTM-2018 Table 9 – Selection of IEEE 802.1AS-2019	3245610111417
Figure 1 – Principle data flow of control loop Figure 2 – Delay measurement reference points Table 1 – List of terms Table 2 – Layout of profile (sub)clause selection tables Table 3 – Contents of (sub)clause selection tables Table 4 – Example of a selection table that apply for multiple device types Table 5 – PHY and MAC selection within IEEE 802.3-2015 Table 6 – CP 802PHY/2 PHY selection and the MAC speeds of Amendments Table 8 – Bridge selections of current amendments to IEEE 802.1QTM-2018 Table 9 – Selection of IEEE 802.1AS-2019 Table 10 – MAC-Security selection	82245671011141717
Figure 1 – Principle data flow of control loop	328224567101114171819
Figure 1 – Principle data flow of control loop	32822456710111417181921
Figure 1 – Principle data flow of control loop	328224567101117181921
Figure 1 – Principle data flow of control loop Figure 2 – Delay measurement reference points Table 1 – List of terms Table 2 – Layout of profile (sub)clause selection tables Table 3 – Contents of (sub)clause selection tables Table 4 – Example of a selection table that apply for multiple device types Table 5 – PHY and MAC selection within IEEE 802.3-2015. Table 6 – CP 802PHY/2 PHY selection and the MAC speeds of Amendments Table 8 – Bridge selections of current amendments to IEEE 802.1QTM-2018 Table 9 – Selection of IEEE 802.1AS-2019. Table 10 – MAC-Security selection Table 11 – Other IEEE 802.1 standard selections Table 12 – Other IEEE 802.1 TSN profiles Table 13 – Application types Table 14 – Industrial automation traffic types summary	3282247101117181921
Figure 1 – Principle data flow of control loop Figure 2 – Delay measurement reference points Table 1 – List of terms Table 2 – Layout of profile (sub)clause selection tables Table 3 – Contents of (sub)clause selection tables Table 4 – Example of a selection table that apply for multiple device types Table 5 – PHY and MAC selection within IEEE 802.3-2015. Table 6 – CP 802PHY/2 PHY selection and the MAC speeds of Amendments Table 8 – Bridge selections of current amendments to IEEE 802.1QTM-2018 Table 9 – Selection of IEEE 802.1AS-2019. Table 10 – MAC-Security selection Table 11 – Other IEEE 802.1 standard selections Table 12 – Other IEEE 802.1 TSN profiles Table 13 – Application types Table 14 – Industrial automation traffic types summary Table 15 – Required Ethernet Bridge delays.	32822456101117181921212223

supporting ballot comment on 60802/D1.0 - 5 - Step 1

<u> Table 19 – Maximum deviation to grandmaster time requirements</u>	_26
Table 20 - Maximum number of hops between grandmaster and time aware end-point	<u>.</u> 26
Table 21 - Maximum error contribution per network node	<u>.</u> 26
Table 22 – Timestamp accuracy	<u>.</u> 27
Table 23 – Synchronization Roles	<u>.</u> 28
Table 1 – List of terms	5
Table 2 – Layout of profile (sub)clause selection tables	5
Table 3 – Contents of (sub)clause selection tables	6
Table 4 – Example of a selection table that apply for multiple device types	7
Table 5 – Application types	9
Table 6 – Industrial automation traffic types summary	9
Table 7 – PHY and MAC selection within IEEE 802.3-2015	.10
Table 8 – CP 802PHY/2 PHY selection and the MAC speeds of Amendments	.11
Table 10 - Bridge selections of current amendments to IEEE 802.1Q™-2018	. 14
Table 11 - Synchronization Domains	. 15
Table 12 – Synchronization Roles	. 15
Table 13 - Maximum deviation to grandmaster time requirements	. 16
Table 14 - Maximum number of hops between grandmaster and time aware end-point	. 16
Table 15 - Maximum error contribution per network node	. 16
Table 16 - Timestamp accuracy	. 16
Table 17 - Selection of IEEE 802.1AS-2019	. 17
Table 18 - MAC-Security selection	. 17
Table 19 - Other IEEE 802.1 standard selections	. 18
Table 20 - Other IEEE 802.1 TSN profiles	. 18
Table 21 - Required Ethernet Bridge delays	. 19
Table 22 - Values of the parameter NetworkCycle	.20

FOREWORD

<< Contributor's notes:

This document has been contributed to the IEC/IEEE 60802 Joint Project via the 1^{st} Task Group ballot on D1.0.

The only intention with this document is to outline some potential slight restructuring of the Draft for consideration for the group.

The intention behind the proposal is to improve clarity and readability of the Draft (improve the "flow" of the Draft.)

No rewrite is suggested by this contribution.

The contributor has submitted separate ballot comments with respect to the content of the Draft.

This contribution only focuses on the structure. The content aimed to be kept the same as D1.0, with some illustrative suggested new text in some of the suggested new clauses. However, restructuring and reformatting may provide a different look. Furthermore, some introductory text is suggested at the beginning of some of the clauses to aid the flow of reading.

- 6 - supporting ballot comment on 60802/D1.0

Step

In order to make it clearer that this is just an individual contribution not and IEC/IEEE 60802 Draft, the FOREWORD has been replaced with this explanation and the INTRODUCTION has been removed.

Proper cross-references were used in the contribution; however, the final outcome is not under the control of the contributor.

This commenter suggests two restructuring steps. This version of the contribution only includes Step 1.

Step 1: Structure

Different kind of requirements could be distinguished clearer. There are conformance requirements. There are requirements coming from Industrial Automation being the target, e.g., from the characteristics of control loops etc. All kinds of requirements are in Clause 6 in D1.0. It would be good to have the conformance and other kind of requirements in separate Clauses.

The Conformance Clause will be not part of the "reading flow" of the document anyways, so it would be good to have it before or after the descriptive clauses. As the Conformance Clause can give orientation to the reader, this commenter suggests having the Conformance Clause right after the terms and definitions, i.e., as Clause 4.

The "Overview of TSN for Industrial Automation" Clause could be Clause 5, i.e., follow Clause 4 Conformance.

The requirements coming from the nature of Industrial Automation, could be part of Clause 5 Overview of TSN for Industrial Automation, because they are closely related to what is Industrial Automation. With that the title of Clause 5 could be "Industrial Automation" with subclauses 5.1 Overview and 5.2 Requirements and an introductory text before 5.1. Thus, Clause 5 would give input to the rest of the document, e.g., to verbal description of industrial profile(s).

If textual description will be provided for the Industrial Automation profile, then it is suggested to be Clause 6.

- 2 - supporting ballot comment on 60802/D1.0 Step 1

INTRODUCTION

Time-sensitive networking profile for industrial automation

1 Scope

4

5

6

10

- 7 This standard defines time-sensitive networking profiles for industrial automation. The profiles
- 8 select features, options, configurations, defaults, protocols, and procedures of bridges, end
- 9 stations, and LANs to build industrial automation networks.

2 Normative references

- 11 The following documents are referred to in the text in such a way that some or all of their content
- constitutes requirements of this document. For dated references, only the edition cited applies.
- 13 For undated references, the latest edition of the referenced document (including any
- 14 amendments) applies.
- 15 Editor Note: The list of normative references will be updated before CDV circulation.
- 16 IEEE P802.1AS-Rev/D7.4, June 12, 2017 IEEE Draft standard for Local and metropolitan area
- 17 networks Timing and Synchronization for Time-Sensitive Applications
- 18 IEEE Std 802.1AE™-2006, IEEE Standard for Local and metropolitan area networks Media
- 19 Access Control (MAC) Security
- 20 IEEE Std 802.1AEbnTM–2011, IEEE Standard for Local and metropolitan area networks Media
- 21 Access Control (MAC) Security Amendment 1: Galois Counter Mode—Advanced Encryption
- 22 Standard—256 (GCM-AES-256) Cipher Suite
- 23 IEEE Std 802.1AEbwTM–2013, *IEEE Standard for Local and metropolitan area networks* Media
- 24 Access Control (MAC) Security Amendment 2: Extended Packet Numbering
- 25 IEEE P802.1AEcg/D1.5, October 25, 2016, IEEE Draft Standard for Local and metropolitan area
- 26 networks—Media Access Control (MAC) Security Amendment 3: Ethernet Data Encryption
- 27 devices
- 28 IEEE Std 802.1AR™-2009, IEEE Standard for Local and metropolitan area networks Secure
- 29 Device Identity
- 30 IEEE Std 802.1Q[™]-2014, IEEE Standard for Local and metropolitan area networks Media
- 31 Access Control (MAC) Bridges and Virtual Bridged Local Area Networks, available at
- 32 <http://www.ieee.org>
- 33 IEEE P802.1Qcc/ D1.1, September 1, 2016, IEEE Standard for Local and Metropolitan Area
- 34 Networks—Bridges and Bridged Networks Amendment: Stream Reservation Protocol (SRP)
- 35 Enhancements and Performance Improvements
- 36 IEEE 802.1Qch[™]-2017, IEEE Standard for Local and Metropolitan Area Networks—Bridges and
- 37 Bridged Networks—Amendment: Cyclic Queuing and Forwarding
- 38 IEEE 802.1Qci[™]-2017, IEEE Standard for Local and Metropolitan Area Networks—Bridges and
- 39 Bridged Networks—Amendment: Per Stream Filtering and Policing
- 40 IEEE 802.1CB™-2017, IEEE Standard for Local and metropolitan area networks—Frame
- 41 Replication and Elimination for Reliability
- 42 IEEE P802.1CS/ D0.0, IEEE Standard for Local and metropolitan area networks—LRP
- 43 (Registration)
- 44 IEEE P802.1Qcj/D0.1 March 7, 2016, IEEE Standard for Local and Metropolitan Area
- 45 Networks— Bridges and Bridged Networks—Automatic Attachment to Provider Backbone
- 46 Bridging (PBB) services

- IEEE P802.1Qcp/ D0.7 December 12, 2016, IEEE Standard for Local and Metropolitan Area 47
- Networks—Bridges and Bridged Networks—Amendment: YANG Data Model 48
- IEEE P 802.1Qcr/D0.2, October 20, 2017, IEEE Standard for Local and Metropolitan Area Networks—Bridges and Bridged Networks—Amendment: Asynchronous Traffic Shaping 49
- 50
- IEEE Std 802.1X-2010, IEEE Standard for Local and Metropolitan Area Networks—Port-based 51
- Network Access Control, available at http://www.ieee.org> 52
- 53 IEEE 802.3-2015, IEEE Standard for Ethernet, available at http://www.ieee.org
- IEEE Std 802.3bp™-2016, IEEE Standard for Ethernet Amendment 4: Physical Layer 54
- Specifications and Management Parameters for 1 Gb/s Operation over a Single Twisted-Pair 55
- 56 Copper Cable
- IEEE Std 802.3br™-2016, IEEE Standard for Ethernet Amendment 5: Specification and 57
- Management Parameters for Interspersing Express Traffic 58
- 59 IEEE Std 802.3bu™-2016, IEEE Standard for Ethernet – Amendment #: Physical Layer and
- 60 Management Parameters for Power over Data Lines (PoDL) of Single Balanced Twisted-Pair
- Ethernet 61
- IEEE P802.3bv™/D3.3, 12th December 2016 Error! Bookmark not defined., IEEE Standard for Ethernet 62
- Amendment 9: Physical Layer Specifications and Management Parameters for 1000 Mb/s 63
- Operation Over Plastic Optical Fiber 64
- IEEE P802.3cg, IEEE Standard for Ethernet Amendment: Physical Layer Specifications and 65
- Management Parameters for 10 Mb/s Operation over Single Balanced Twisted-pair Cabling and 66
- Associated Power Delivery 67

Terms, definitions, symbols and abbreviated terms

- For the purposes of this document, the terms and definitions given in IEC 61784-2, IEEE 802, 70 IEEE 802.3, IEEE 802.1Q and IEEE 802.1AS and the following apply. 71
 - ISO Online browsing platform: available at https://www.iso.org/obp
 - IEC Electropedia: available at http://www.electropedia.org/

74 3.1 **TSN-IA** defined Terms

75 76

77

79

68

69

72 73

TSN Domain

- quantity of commonly managed industrial automation devices 78
 - Note 1 to entry: It is an administrative decision to group these devices

80 81 82

83 84

85

86

List of terms and definitions given in IEC 61784-2, IEEE 802, IEEE 802.3, 3.2 **IEEE 802.1Q and IEEE 802.1AS**

For ease of understanding the most important terms used within this profile document are listed but not repeated in Table 1.

Table 1 - List of terms

Term	Source
Bridge	IEEE Std 802.1Q™-2018

supporting ballot comment on 60802/D1.0 $\,-5-$ Step 1

Bridge Port	IEEE Std 802.1Q™-2018
Bridged Network	IEEE Std 802.1Q™-2018
end station	IEEE Std 802
Ethernet	IEEE Std 802.1Q™-2018
Frame	IEEE Std 802.1QTM-2018
Frame relay	IEEE Std 802.1QTM-2018
latency	IEEE Std 802.1QTM-2018
Listener	IEEE Std 802.1QTM-2018
Port	IEEE Std 802.1Q™-2018
preemption	IEEE Std 802.1Q™-2018
station	IEEE Std 802
Stream	IEEE Std 802.1Q™-2018
Talker	IEEE Std 802.1Q™-2018
time-sensitive stream	IEEE Std 802.1Q™-2018
traffic class	IEEE Std 802.1Q™-2018

3.3 Abbreviated terms and acronyms

Editor's Note: has to be updated before CDV stage!

IA Industrial automation

90 3.4 Conventions

3.4.1 Conventions for (sub)clause selections of referenced documents

(Sub)clause selections of referenced documents are done in tables, as shown in Table 2 and Table 3. The selected base specifications are indicated just before the selection table(s) or in the table title. Selections are done at the highest (sub)clause level possible to define the profile selection unambiguously.

Table 2 - Layout of profile (sub)clause selection tables

Clause Header		Presence	Constraints

87

88

89

91

92

93

95

Table 3 - Contents of (sub)clause selection tables

Column	Text	Meaning
Clause	<#>	(Sub)clause number of the base specifications
	Next clauses	any following clauses up to the last clause of the base specification
	Next Annexes	any following annexes up to the last annex of the base specification
Header	<text></text>	(Sub)clause title of the base specifications
Presence	NO	This (sub)clause is not included in the profile
	YES	This (sub)clause is fully (100 %) included in the profile
		in this case no further detail is given
	_	Presence is defined in the following (sub)clauses
	Partial	Parts of this (sub)clause are included in the profile
	Optional	This (sub)clause may be additionally included in the profile
Constraints	See <#>	Constraints/remarks are defined in the given (sub)clause, table or figure of this profile document
	_	No constraints other than given in the reference document (sub)clause,
		or not applicable
	<text></text>	The text defines the constraint directly; for longer text table footnotes or table notes may be used

 If sequences of (sub)clauses match or do not match the profile, then the numbers are concatenated.

EXAMPLE Concatenated (sub)clauses

1 – 6	_	YES	_
7 – 11	_	NO	_

Conventions for different cases in selection tables, which apply for multiple or different device types (end-station, bridge):

 1. Presence column value YES and NO Constraints given: This (sub)clause is fully (100 %) included in the profile for all device types

 2. Presence column value YES and some Constraints given: the constraints can limit the applicability to a device type

 3. Presence column value PARTIAL and general Constraints without device type constraints given: the constraints can limit the applicability to all device types

 Presence column value PARTIAL and general Constraints with device type constraints given: the constraints limit the applicability to a device types
 Presence column value NO and no Constraints given: This (sub)clause is not included

in the profile for all device types

Subclauses, which are dedicated to a specific device type, do not need to repeat the

Table 4 shows an example of a selection table that apply for multiple device types (end-station, bridge). The Clause numbers used in Table 4 corresponds to the list numbers above.

device type applicability in the Constraints column.

supporting ballot comment on 60802/D1.0 - 7 - Step 1

Table 4 - Example of a selection table that apply for multiple device types

Clause	Header	Presence	Constraints
1	Xyz	YES	_
2	Xyz	YES	Applicable to device type end- station only
3	Media Access Control (MAC) frame and packet specifications	PARTIAL	The option xyz does not apply
4	Хуz	PARTIAL	The option xyz does not apply Applicable to device type end- station only
5	Xyz	NO	_
6	End-station behavior	YES	_

121 122

120

3.4.2 Convention for Capitalizations

Capitalized terms are either based on the rules given in the ISO/IEC Directives Part 2 or emphasize that these terms have a specific meaning throughout this document.

- 125 The following capitalized terms are used:
- 126 Bridge
- 127 Ethernet
- 128 Internet
- 129 Universal Time
- 130 Working Clock

131

- 132 Parameter names are capitalized for example
- 133 MinimumFrameMemory
- 134 NetworkCycleTime
- 135 NetworkCycle
- 136 Phase
- 137 ReductionRatio
- 138 Sequence.

139 140

147 148

3.4.3 Unit conventions

- 141 This document uses
- 142 Tbps for Tbit/s
- 143 Gbps for Gbit/s and
- 144 Mbps for Mbit/s.
- This form is used by IEEE 802.3 and as this document is a profile to IEEE 802, it is better readable and consistent.

41_Overview of TSN in Industrial Automation

4.11.1 Control Loop Basic Model

- 149 Control loops are fundamental building blocks of industrial automation systems. Control loops include: process sensors, a controller function, and output signals. Control loops may require
- 151 guaranteed low latency or more relaxed bounded latency network transfer quality.

- 8 - supporting ballot comment on 60802/D1.0 Step 1

To achieve the needed quality for Control loops the roundtrip delay of the exchanged data is essential.

Figure 1 shows the whole transmission path from Controller application to Device application(s) and back. The blue and red arrows show the contributions to the e2e (end-to-end) latency respectively.

Figure 1 and Table 5 show three levels of a control loop:

- Application within End Station,
- Network Access within End Station,
- Network / Bridges within Bridges.

Applications may or may not be synchronized to the Network Access depending on the application requirements. Applications which are synchronized to Network Access are called "isochronous applications". Applications which are not synchronized to Network Access are called "non-isochronous applications".

Network Access shall be synchronized to a common working clock or to a local timescale.

Network / Bridges may or may not be synchronized to a common working clock depending on whether the Enhancements for Scheduled Traffic (IEEE 802.1Q-2018) are applied.




Figure 1 - Principle data flow of control loop

Transfer Times contain PHY and MAC delays. Both delays are asymmetric and vendor specific. Device vendors have to take into account these transfer times when their application cycle models are designed (see Figure 1).

Field Code Changed

Field Code Changed
Field Code Changed

Field Code Changed

168 169

170

171

172

154

155

156

157

158 159

160 161

162 163

164 165

166

173

Table 5 - Application types

Level	Isochronous	Application	Non-isochronous Application			
Application	tion Synchronized to network access Synchronized to local timescale					
Network access	Synchronized to working clock, Stream Class based scheduling, Preemption				Synchronized- local timescale Stream Class be scheduling, Preemption	o, sed
	Synchronized to working clock	Free running	Synchronized to working clock	Free running	Free running	
Network/Bridges	Scheduled traffic + Strict Priority + Preemption	Strict Priority or other Shaper + Proemption	Scheduled traffic + Strict Priority + Preemption	Strict Priority or other Shaper + Preemption	Strict Priority other Shaper Proemption	

174 175

176

177

178 179

180

181

4.21.1 Industrial Traffic Types

Industrial automation applications concurrently make use of different traffic schemes/patterns for different functionalities, e.g. parameterization, control, alarming. The various traffic patterns have different characteristics and thus impose different requirements on a TSN network.

Table 3 subsumes the industrial automation relevant traffic patterns to traffic types with their associated properties.

Table 6 - Industrial automation traffic types summary

Traffic type name	Periodic/ Sporadic	Guarantee	Data size	Redundancy
Isochronous cyclic real time	₽	Deadline/ bounded latency (e.g. 20%@1-6bps-/ 50%@10-Mbit/s network cycle)/ bandwidth	Bounded	Up to seamless*)
Cyclic real time	₽	Deadline/ bounded latency (e.g. n-times network cycle)/ bandwidth	Bounded	Up to seamless ¹⁾
Network control	\$	Priority	_	Up to seamless ¹⁾ -as required
Audio/video	₽	Bounded latency/ bandwidth	Bounded	Up to seamless ¹⁾ -as required
Brownfield	P	Bounded latency/ bandwidth	-	Up to rogular^{a)}
Alarms/ events	\$	Bounded latency/ bandwidth	=	Up to regular²⁾
Configuration/ diagnostics	C.	Bandwidth	-	Up to regular²⁾
Internal / Pass- through	S	Bandwidth	-	Up to regular ²⁾
Best effort	\$	=	=	Up to regular ²⁾
1) almost zoro faile	ver time;			

2) larger failever time because of network re-convergence

54 Conformance

182

183 184

185 186

187

188

189 190

191

192

193 194

195

196 197

198

199 200

201

202

203

204

205

206207

208

209

210

212

A claim of conformance to this standard is a claim that the behavior of an implementation of a bridge (X.X, X.X) or of an end station (X.X, X.X) meets the mandatory requirements of this standard and may support options identified in this standard.

5.14.1 Requirements Terminology

The Profile Conformance Statement (PCS) proformas (see Annex A) reflect the occurrences of the words "shall," "may," and "should" within this document.

5.24.2 Profile Conformance Statement (PCS)

The supplier of an implementation that is claimed to conform to this standard shall provide the information necessary to identify both the supplier and the implementation, and shall complete a copy of the PCS proforma provided in Annex A.

64.3 Required Functions for an Industrial Network

6.14.3.1 PHY and MAC selection

6.1.14.3.1.1 General

The following requirements and features according to IEEE 802.3 shall be supported:

- a) Select one of the PHY with data rates from 10 Mbps to 1 Tbps with
 - o Full duplex, and
 - $\circ\quad \text{Synchronization according IEEE 802.1AS supported}.$

Table 5 specifies the elements of IEEE 802.3-2018 applicable to this profile. At least one PHY shall be selected out of the list of possible PHYs.

b) The maximum frame size according IEEE 802.3-2015, 3.2.7, including envelope frame, shall be supported.

Editor's Note: TBD: check max frame size in 802.1Q

- C) IEEE 802.3br™-2016 (preemption) up to 1 Gb/s; beyond optional.
 NOTE May be indicated by Annex A parameter.
 - d) The selected medium shall be described in the IEEE 802.3 defined managed object.

6.1.24.3.1.2 IEEE 802.3-2015 Selections

Table 5 specifies the (sub) clause selection of IEEE 802.3-2015.

Table 5 - PHY and MAC selection within IEEE 802.3-2015

Clause	Header	Presence	Constraints
2	Media Access Control (MAC) service specification	YES	-
3	Media Access Control (MAC) frame and packet specifications	YES	-
4	Media Access Control	YES	-
5	Layer Management	YES	-
6	Physical Signaling (PLS) service specifications	YES	=
7	Physical Signaling (PLS) and Attachment Unit Interface (AUI) specifications	YES	-
8 - 77		Partial	Applies only if 4.3.1.1 fulfilled.

Formatted: Heading 2,h2,Titre 2,Titre 2

Formatted: Heading 4,h4,HEADING4,HEADING4*

supporting ballot comment on 60802/D1.0 $\,-$ 11 $\,-$ Step 1

Clause	Header	Presence	Constraints
Annex 57A - 76A	-	Partial	Applies only if 4.3.1.14.3.1.1 fulfilled.
78	Energy-Efficient Ethernet (EEE)	NO	
79	IEEE 802.3 Organizationally Specific Link Layer Discovery Protocol (LLDP) type, length, and value (TLV) information elements	YES	Relevant for IEEE 802.3br
80 - 89	-	Partial	Applies only if 4.3.1.1 fulfilled.
90	Ethernet support for time synchronization protocols	YES	Relevant for IEEE 802.3br
91 - 95	-	Partial	Applies only if 4.3.1.1 fulfilled.
Annex 83A – 93C	-	Partial	Applies only if 4.3.1.1 fulfilled.

213 214

Table 6 – CP 802PHY/2 PHY selection and the MAC speeds of Amendments

Amendment	Title	Presence	Constraints
IEEE 802.3bw™- 2015	IEEE Standard for Ethernet - Amendment 1: Physical Layer Specifications and Management Parameters for 100 Mb/s Operation over a Single Balanced Twisted Pair Cable (100BASE-T1)	Partial	Applies only if 4.3.1.1 fulfilled.
IEEE 802.3by™- 2016	IEEE Standard for Ethernet - Amendment 2: Media Access Control Parameters, Physical Layers, and Management Parameters for 25 Gb/s Operation	Partial	Applies only if 4.3.1.1 fulfilled.
IEEE 802.3bq™- 2016	IEEE Standard for Ethernet - Amendment 3: Physical Layers and Management Parameters for 25 Gb/s and 40 Gb/s Operation, Types 25GBASE-T and 40GBASE-T	Partial	Applies only if 4.3.1.1 fulfilled.
IEEE 802.3bp™- 2016	IEEE Standard for Ethernet - Amendment 4: Physical Layer Specifications and Management Parameters for 1 Gb/s Operation over a Single Twisted-Pair Copper Cable	Partial	Applies only if 4.3.1.1 fulfilled.
IEEE 802.3br™- 2016	IEEE Standard for Ethernet - Amendment 5: Specification and Management Parameters for Interspersing Express Traffic	YES	Yes to all Options in 79.5 up to 1 Gb/s; beyond optional.
IEEE 802.3bz™- 2016	IEEE Standard for Ethernet - Amendment 7: Media Access Control Parameters, Physical Layers, and Management Parameters for 2.5 Gb/s and 5 Gb/s Operation, Types 2.5GBASE-T and 5GBASE-T	Partial	Applies only if 4.3.1.1fulfilled.
IEEE P802.3bs™ /D2.2, 28th November 2016	IEEE Standard for Ethernet - Amendment #: Media Access Control Parameters, Physical Layers and Management Parameters for 200 Gb/s and 400 Gb/s Operation	Partial	Applies only if 4.3.1.1 fulfilled.
IEEE P802.3bt™/D 2.2, 28 November 2016	IEEE Standard for Ethernet - Amendment #: Physical Layer and Management Parameters for DTE Power via MDI over 4-Pair	Partial	Applies only if 4.3.1.1 fulfilled.
IEEE P802.3bu™/ D3.3, 11 October 2016	IEEE Standard for Ethernet – Amendment #: Physical Layer and Management Parameters for Power over Data Lines (PoDL) of Single Balanced Twisted-Pair Ethernet	Partial	Applies only if 4.3.1.1 fulfilled.
IEEE P802.3bv™/ D3.3, 12th December 2016	IEEE Standard for Ethernet – Amendment 9: Physical Layer Specifications and Management Parameters for 1000 Mb/s Operation Over Plastic Optical Fiber	Partial	Applies only if 4.3.1.1 fulfilled.

- 12 - supporting ballot comment on 60802/D1.0

Amendment	Title	Presence	Constraints
IEEE P802.3ca™/ D0.0, No Draft	IEEE Standard for Ethernet – Amendment #: Physical Layer Specifications and Management Parameters for 25 Gb/s, 50 Gb/s, and 100 Gb/s Passive Optical Networks	Partial	Applies only if 4.3.1.1 fulfilled.
IEEE P802.3cb- 20xx TM /D2.1, 15th December 2016	IEEE Standard for Ethernet – Amendment #: Physical Layer Specifications and Management Parameters for 2.5 Gb/s and 5 Gb/s Operation over Backplane	Partial	Applies only if 4.3.1.1 fulfilled.
IEEE P802.3cc TM / D2.0, 27th November 2016	IEEE Standard for Ethernet – Amendment #: Physical Layer and Management Parameters for Serial 25 Gb/s Ethernet Operation Over Single- Mode Fiber	Partial	Applies only if 4.3.1.1 fulfilled.
IEEE P802.3cd™/ D1.1, 2nd December 2016	IEEE Standard for Ethernet – Amendment #: Media Access Control Parameters for 50 Gb/s and Physical Layers and Management Parameters for 50 Gb/s, 100 Gb/s, and 200 Gb/s Operation	Partial	Applies only if 4.3.1.1 fulfilled.
IEEE P802.3cg™/ Draft	IEEE Standard for Ethernet – Amendment #: 10 Mb/s Single Twisted Pair Ethernet	Partial	Applies only if 4.3.1.1 fulfilled.

215 216

217

229

235 236

237

238

241

6.24.3.2 IEEE 802.1 selection

6.2.14.3.2.1 General

218 6.2.1.14.3.2.1.1 General required Bridge features

219 The following requirements and features according to IEEE 802.1 shall be supported:

- 220 a) Support the capability of 2 000 octets maximum size MAC Protocol Data Unit (PDU) on each port.
- b) Support the capability to disable MAC control PAUSE if it is implemented and support the capability to disable Priority-based flow control if it is implemented.
- c) Support the capability to disable support of Energy Efficient Ethernet.
- d) Support the strict priority algorithm for transmission selection (8.6.8.1 in IEEE Std 802.1Q-2014) on each port for each traffic class.
- e) Support a minimum of 8 Traffic Classes/Queues on every port.
- 228 f) Support flow metering according to IEEE 802.1Q, 8.6.5.
 - g) Support priority regeneration according to IEEE 802.1Q, 6.9.4.
- 230 h) Support of preemption according to IEEE 802.1Q-2018, 5.26, 6.7.2, 12.30, 17.2.23, 17.3.24, 17.4.24, 17.7.23, and Annex R.
- i) Time limits for bridge delay and delay variation according to 4.3.3.
- j) Required number of DA-MAC address entries used together with five VLANs (Default, High,
 High Redundant, Low and Low Redundant) according to ...
 - Editor's note: insert reference to appropriate section once "FDB and resource requirements" discussion is concluded.

6.2.24.3.2.2 Bridge selections

6.2.2.1.1 Selection of IEEE 802.1Q-2018 and the related Amendments

239 Selections of IEEE 802.1Q[™]-2018 are specified in Table 7. The current amendments to IEEE 802.1Q are selected inTable 8.

Formatted: Heading 4,h4,HEADING4,HEADING4*

Formatted: Heading 3,h3

Table 7 - Selection of IEEE 802.1Q-2018

supporting ballot comment on 60802/D1.0 $\,-$ 13 $\,-$ Step 1

Clause	Header	Presence	Constraints
5.3	Protocol Implementation Conformance Statement (PICS)	YES	-
5.4	VLAN Bridge component requirements	YES	=
5.4.1	VLAN Bridge component options	YES	Optional
5.4.1.1	Multiple Spanning Tree (MST) operation	YES	-
5.4.1.2	Port-and-Protocol-based VLAN classification	NO	=
5.4.1.3	Multiple MAC Registration Protocol (MMRP) operation	YES	Optional
5.4.1.4	Connectivity Fault Management (CFM)	NO	=
5.4.1.5	Forwarding and Queuing Enhancements for time- sensitive streams (FQTSS)— requirements	YES	Optional
5.4.1.6	ETS Bridge requirements	NO	
5.4.1.7	DCBX Bridge requirements	NO	_
5.4.1.8	Per-stream filtering and policing (PSFP) requirements	YES	Optional
5.4.1.9	Cyclic queuing and forwarding (CQF) requirements	YES	Optional
5.4.2	Multiple VLAN Registration Protocol (MVRP) requirements	YES	Optional
5.4.3	VLAN Bridge requirements for congestion notification	NO	-
5.4.4	Multiple Stream Registration Protocol (MSRP) requirements	YES	Optional
5.4.5	Shortest Path Bridging (SPB) operation	NO	
5.4.6	Path Control and Reservation (PCR)	NO	_
5.5	C-VLAN component conformance	YES	_
5.5.1	C-VLAN component options	YES	Optional
5.6	S-VLAN component conformance	NO	_
5.7	I-component conformance	NO	
5.8	B-component conformance	NO	=
5.9	C-VLAN Bridge conformance	YES	
5.10	Provider Bridge conformance	NO	_
5.11	System requirements for Priority-based Flow Control (PFC)	NO	-
5.12	Backbone Edge Bridge (BEB) conformance	NO	
5.13	MAC Bridge component requirements	YES	_
5.13.1	MAC Bridge component options	YES	Optional
5.14	MAC Bridge conformance	YES	-
5.14.1	MAC Bridge options	YES	Optional
5.15	TPMR component conformance	NO	-
5.16	TPMR conformance	NO	_
5.17	T-component conformance	NO	
5.18	End station requirements for MMRP, MVRP, and MSRP	YES	Optional
5.19	VLAN-aware end station requirements for CFM	NO	
5.20	End station requirements—FQTSS	YES	Optional
5.21	End station requirements for congestion notification	NO	-

- 14 - supporting ballot comment on 60802/D1.0

Clause	Header	Presence	Constraints
5.22	MAC-specific bridging methods	YES	=
5.23	EVB Bridge requirements	NO	-
5.24	EVB station requirements	NO	-
5.25	End station requirements—enhancements for scheduled traffic	YES	Optional
5.26	End station requirements—enhancements for frame preemption	YES	Optional
5.27	End-station requirements—PSFP	YES	Optional
5.28	End station requirements—Cyclic queuing and forwarding	YES	Optional

242

243

244

6.2.34.3.2.3 Applicable amendments to IEEE 802.1Q™-2018

Table 8 - Bridge selections of current amendments to IEEE 802.1Q™-2018

Amendment	Title	Presence	Constraints
IEEE P802.1Qcc™ -2018	IEEE Standard for Local and Metropolitan Area Networks – Bridges and Bridged Networks Amendment: Stream Reservation Protocol (SRP) Enhancements and Performance Improvements	YES	Optional
IEEE P802.1Qcj/D 0.1 March 7, 2016	IEEE Standard for Local and Metropolitan Area Networks— Bridges and Bridged Networks— Automatic Attachment to Provider Backbone Bridging (PBB) services	NO	-
IEEE P802.1Qcp/ D0.7 December 12, 2016	IEEE Standard for Local and Metropolitan Area Networks—Bridges and Bridged Networks— Amendment: YANG Data Model	YES	Optional if SNMP and MIBs are implemented.
IEEE P 802.1Qcr/D0. 0	IEEE Standard for Local and Metropolitan Area Networks—Bridges and Bridged Networks— Amendment: Asynchronous Traffic Shaping	YES	Optional
IEEE P 802.1Qdd/D0 .0	IEEE Standard for Local and Metropolitan Area Networks—Bridges and Bridged Networks— Amendment: RAP	YES	Optional

245 246

247

248

254

255

256

257 258

259 260

261

6.2.44.3.2.4 Clock synchronization selection

6.2.4.1 General

The IEEE 802.1AS $^{\text{TM}}$ -2019 shall apply according to Table 9.

Synchronization covering both universal time and working clock timescales is needed for industrial automation systems.

Redundancy for synchronization of universal time may be solved with "cold standby". Support of "Hot standby" for universal time synchronization is not current practice - but is an option in this document and can be used depending on the application requirements.

Redundancy for Working Clock synchronization can be solved with "cold standby" or "hot standby" depending on the application requirements. Support of "hot standby" for working clock synchronization is required.

NOTE—Global Time is often used as synonym term for "Universal Time". Wall Clock is based on Universal Time and considers time zones, daylight saving time and leap seconds.

6.2.4.21.1.1 Universal Time synchronization

Universal time is used to plant wide align events and actions (e.g. for "sequence of events").

The assigned timescale is TAI, which can be converted into local date and time if necessary.

Formatted: Heading 4,h4,HEADING4,HEADING4*

Formatted: Heading 4,h4,HEADING4,HEADING4*

supporting ballot comment on 60802/D1.0 - 15 - Step 1

The goal of Universal Time synchronization is to establish a worldwide aligned timescale for time. Thus, often satellites are used as source of the time.

6.2.4.3 1.1.1.1 Working Clock synchronization

264

273

274275

276

277

278

279

280

281

282

285

286

287

288

289

Working Clock is used to align actions line, cell or machine wide. The assigned timescale i
ARB. Robots, motion control, numeric control and any kind of clocked / isochronous application

rely on this timescale to ensure that actions are precisely interwoven as needed. Often PLCs

268 Motion Controller or Numeric Controller are used as Working Clock source.

Working Clock domains may be doubled to support zero failover time for synchronization be aligning the both timescales at the Grandmaster.

271 TBD: two WC domains needs more definitions het standby/cold standby need definitions

High precision Working Clock synchronization is a prerequisite for control loop implementations

6.2.4.41.1.1 General Requirements for Synchronization

Synchronization domain settings shall be according to Table 11 and Table 12.

Table 11 - Synchronization Domains

Domain ΙĐ **Timescales** Presence Constraints Used for network access and application synchronization. If scheduled traffic is used then YES Working Clock 20 ARB also used for Bridge synchronization. YES Universal Time 0 TAI YES Used for hot standby of Working Clock. Timescale shall be identical to Working Clock. Redundant Working 21 ARB Optional. Used for hot standby of Universal Time.
Timescale shall be identical to Universal Time. Redundant Universal 4 TAI YES Time

TRD: ID is Domain number all Timescales coded as DTD

In the working clock domain bridges shall take the roles of time aware relay and time aware endpoint, because they shall be in sync for scheduled traffic transmission.

In the Universal Time domain the role of a time aware relay is mandatory and the role of a time aware endpoint is optional for Bridges.

At least one grandmaster shall be present in every synchronization domain.

283 All members of a synchronization domain may take at least one of the roles specified in Table 284 42.

Table 12 - Synchronization Roles

I.				
Role	Working Clock		Univers	ial Time
	Bridge or Router	End Station	Bridge or Router	End Station
Time aware relay	mandatory	-	mandatory	
Time aware endpoint	mandatory	mandatory	optional	mandatory
Grandmaster capable	Optional	optional	optional	optional

Editor Note: is support of UniversalTime/Time aware endpoint mandatory or optional for end stations? Contributions are welcome.

The requirements concerning the overall maximum deviation to the grandmaster time in the synchronization domains in Table 13 shall be fulfilled.

Field Code Changed

Field Code Changed

Field Code Changed

Field Code Changed

291

292 293

294

295

296

297

298

299

300

301

302

303

304

305

306 307

Table 13 - Maximum deviation to grandmaster time requirements

Domain	Maximum absolute value of deviation from grandmaster time	Comments
Working Clock	< 1 μs	Maximum deviation +/- 1 µs
Universal Time	< 100 μs	Maximum deviation +/ 100 μs

Editor's Note: reference number of hops (100) "grandmaster time" must be defined from TAL in case of universal time

Table 14 shows the number of hops which shall be supported.

Table 14 - Maximum number of hops between grandmaster and time aware end-point

Domain	Number of hops	Comments
Working Clock	100	Grandmaster to time aware end point. May be 200 between two time aware end points.
Universal Time	100	From Grandmaster connected to the satellite receiver to each time aware endpoint.

The maximum working clock deviation between two devices, which are synchronized to the same grandmaster, shall be $< 2~\mu s$ when the working clock requirement of Table 13 is observed.

The maximum error contribution of every single network node of the domains shall be according to Table 15.

Table 15 - Maximum error contribution per network node

Error contribution	Max. error	Comments
Maximum residence time error	< 10 ns	Externally measured from the MDI to MDI at the local Bridge.
Maximum link dolay error	< 10 ns	Externally measured from the MDI to MDI at the local link—including the asymmetry error contribution.

Minimal timestamp accuracy for any kind of timestamp shall be according to Table 16.

Table 16 - Timestamp accuracy

Timostamp	Accuracy	Comments
Working Clock	<u>≤ 8 ns</u>	=
Universal time	≤ 8 ns	=

Table 17 specifies the clock synchronization profile contribution. The selection of the different clock types per device shall be provided using PICS.

Editor's Noto: add requirement about asymmetry componention

6.2.4.54.3.2.5 IEEE 802.1AS-2019 Selections

Field Code Changed

309 310

311

312

315

Table 9 - Selection of IEEE 802.1AS-2019

Clause	Header	Presence	Constraints
5.2	Protocol Implementation Conformance Statement (PICS)	YES	_
5.3	Time-aware system requirements	YES	-
5.4	PTP Instance requirements	YES	-
5.4.1	Time-aware system options	YES	Optional
5.4.2	PTP Relay Instance requirements	YES	-
5.5	MAC-specific timing and synchronization methods for IEEE 802.3 full-duplex links	YES	_
5.6	MAC-specific timing and synchronization methods for IEEE Std 802.11	YES	Optional
5.7	MAC-specific timing and synchronization methods for IEEE 802.3 EPON	NO	_
5.8	MAC-specific timing and synchronization methods for coordinated shared network (CSN)	NO	_

Editor's Note: The Time-aware system options of 5.4.1 should be examined carefully to determine if any of those options should be mandatory for the purposes of this profile. A contribution is welcome.

6.2.54.3.3 Security selection

- 313 Media Access Control (MAC) Security according to IEEE 802.1AE can be used as an option.
- Table 10 specifies the optional MAC-Security selection.

Table 10 - MAC-Security selection

Amendment	Title	Presence	Constraints
IEEE 802.1AE™- 2006	IEEE Standard for Local and metropolitan area networks – Media Access Control (MAC) Security	YES	Optional
IEEE 802.1AEbn™ -2011	IEEE Standard for Local and metropolitan area networks – Media Access Control (MAC) Security Amendment 1: Galois Counter Mode—Advanced Encryption Standard—256 (GCM-AES-256) Cipher Suite	YES	If IEEE 802.1AE™-2006 is used then this is mandatory.
IEEE 802.1AEbwT M-2013	IEEE Standard for Local and metropolitan area networks – Media Access Control (MAC) Security Amendment 2: Extended Packet Numbering	YES	If IEEE 802.1AE™-2006 is used then this is mandatory.
IEEE P802.1AEcg/ D1.5, October 25, 2016	IEEE Draft Standard for Local and metropolitan area networks—Media Access Control (MAC) Security Amendment 3: Ethernet Data Encryption devices	YES	If IEEE 802.1AE™-2006 is used then this is mandatory.
IEEE 802.1AR™- 2009	IEEE Standard for Local and metropolitan area networks – Secure Device Identity	YES	If IEEE 802.1AE™-2006 is used then this is mandatory.
IEEE 802.1X™- 2010	IEEE Standard for Local and metropolitan area networks – Port Based Network Access Control	YES	Optional
IEEE 802.1Xbx- 2014	IEEE Standard for Local and metropolitan area networks – Port Based Network Access Control Amendment 1: MAC Security Key Agreement Protocol (MKA) Extensions	YES	Optional

316 317

318

The IEEE P802.1AEcg enables multiple, per traffic class, transmit secure channels for MAC and thus will also meet strict ordering requirements (within traffic class, with express or

- 18 - supporting ballot comment on 60802/D1.0 Step 1

preemptible transmission being selected for all the priorities allocated to a traffic class) for preemption.

Secure Device Identifiers (DevIDs) are designed to be used as interoperable secure device authentication credentials with Extensible Authentication Protocol (EAP) and other industry standard authentication and provisioning protocols.

6.2.64.3.4 Other IEEE 802.1 standard selections

Table 11 specifies the other IEEE 802.1 standard selections.

Table 11 - Other IEEE 802.1 standard selections

Amendment	Title	Presence	Constraints
IEEE 802.1AB™- 2016	IEEE Standard for Local and metropolitan area networks—Station and Media Access Control Connectivity Discovery	YES	-
IEEE 802.1AC™- 2016	IEEE Standard for Local and metropolitan area networks— Media Access Control (MAC) Service Definition	YES	-
IEEE 802.1AX™- 2008	IEEE Standard for Local and metropolitan area networks—Link Aggregation	NO	-
IEEE 802.1BR™- 2012	IEEE Standard for Local and metropolitan area networks—Virtual Bridged Local Area Networks— Bridge Port Extension	NO	=
IEEE 802.1CB™- 2017	IEEE Standard for Local and Metropolitan Area Networks – Frame Replication and Elimination for Reliability	YES	Optional
IEEE P802.1CS/ D1.5	IEEE Standard for Local and metropolitan area networks—LRP (Registration)	YES	-

6.34.3.5 Other profiles

A vendor can decide to implement more than one profile per device. In this case the implemented profiles shall be coexistent. Table 12 shows other profiles.

Formatted: Heading 3,h3

327

321 322

323

324

325

326

328 329

331

Table 12 - Other IEEE 802.1 TSN profiles

Amendment	Title	Presence	Constraints
IEEE 802.1BA™- 2011	IEEE Standard for Local and metropolitan area networks—Audio Video Bridging (AVB) Systems	YES	Optional; Coexistent with this profile contribution.
IEEE 802.1CM, 2018	IEEE Standard for Local and metropolitan area networks—Time-Sensitive Networks for Fronthaul	YES	Optional; Coexistent with this profile contribution.

332 333

334

336

4.3.6 Management selection

4.3.6.1 General

End stations and bridges shall provide at least the managed objects, which are required by this 335

profile contribution, from

IEEE 802.3 337

338 IEEE 802.3br

IEEE 802.1Q 339

340 IEEE 802.1Qca

341 **IEEE 802.1Qcc**

342 IEEE 802.1CBcv

IEEE 802.1AS 343

IEEE 802.1AB

345 IETF RFC 1213

346 etc.

344

348

349

347 These managed objects shall be represented preferred in the YANG format; if the YANG (RF¢

6020) format is not available then MIB format (RFC 2358) shall be provided.

4.3.6.2 <u>Protocols</u>

Required access protocols are SNMP (RFC 4789) for a MIB representation and NETCON 350

(RFC 6241) for YANG representation of the device local data base.

351 352

353

354

357

Overview of TSN in Industrial Automation

This standard is concerned with the requirements of Industrial Automation and meeting thes

requirements with a bridged network. This clause gives an overview on Industrial Automation

355 356 and describes Industrial Automation requirements.

Overview

This subclause provides an introductory overview for the description of Industrial Automation

requirements to bridged networks provided in 6.2. 359

Control Loop Basic Model 360

361 Control loops are fundamental building blocks of industrial automation systems. Control loops

362 include: process sensors, a controller function, and output signals. Control loops may require

363 guaranteed low latency or more relaxed bounded latency network transfer quality.

To achieve the needed quality for Control loops the roundtrip delay of the exchanged data is 364

essential. 365

Formatted: Heading 3,h3

Formatted: Heading 4,h4,HEADING4,HEADING4*

Formatted: PARAGRAPH,PA,PA Zchn Zchn

shows the whole transmission path from Controller application to Device application(s) and 366 367 back. The blue and red arrows show the contributions to the e2e (end-to-end) latency 368 respectively.

and show three levels of a control loop:

- within End Station, Application
- 371 • Network Access - within End Station,
 - Network / Bridges within Bridges.

Applications may or may not be synchronized to the Network Access depending on the application requirements. Applications which are synchronized to Network Access are called "isochronous applications". Applications which are not synchronized to Network Access are called "non-isochronous applications".

377 Network Access shall be synchronized to a common working clock or to a local timescale.

Network / Bridges may or may not be synchronized to a common working clock depending on whether the Enhancements for Scheduled Traffic (IEEE 802.1Q-2018) are applied.




Figure 1 - Principle data flow of control loop

Transfer Times contain PHY and MAC delays. Both delays are asymmetric and vendor specific. Device vendors have to take into account these transfer times when their application cycle models are designed (see).

380 381 382

383

384

369

370

372

373

385

Table 13 - Application types

ĺ	<u>Level</u>	Isochronous	Application	Non-isochronous Application			
ĺ	Application	Synchronized to	network access	Synch	ronized to local tim	nescale	
	Network access	<u>St</u>	Synchronized to ream Class based so	to working clock. scheduling, Preemption Stream Cl. sched		Synchronized local timescal Stream Class ba scheduling, Preemption	<u>e.</u>
I		Synchronized to working clock	Free running	Synchronized to working clock	Free running	Free running	
	Network/Bridges	Scheduled traffic + Strict Priority + Preemption	Strict Priority or other Shaper + Preemption	Scheduled traffic + Strict Priority + Preemption	Strict Priority or other Shaper + Preemption	Strict Priority of other Shaper Preemption	±

386 387

392

5.1.2 Industrial Traffic Types

Industrial automation applications concurrently make use of different traffic schemes/patterns for different functionalities, e.g. parameterization, control, alarming. The various traffic patterns have different characteristics and thus impose different requirements on a TSN network.

<u>Table 3 subsumes the industrial automation relevant traffic patterns to traffic types with their associated properties.</u>

393

Table 14 - Industrial automation traffic types summary

Traffic type name	Periodic/ Sporadic	<u>Guarantee</u>	Data size	Redundancy	
lsochronous cyclic real-time	<u>P</u>	Deadline/ bounded latency (e.g. 20%@1 Gbps / 50%@100 Mbit/s network cycle)/ bandwidth	Bounded	Up to seamless ¹⁾	
Cyclic real-time	<u>P</u>	Deadline/ bounded latency (e.g. n-times network cycle)/ bandwidth	Bounded	Up to seamless ¹⁾	
Network control	<u>S</u>	<u>Priority</u>	=	Up to seamless ¹⁾ as required	
<u>Audio/video</u>	<u>P</u>	Bounded latency/ bandwidth	Bounded	Up to seamless ¹⁾ as required	
Brownfield	<u>P</u>	Bounded latency/ bandwidth	=	Up to regular ²⁾	
Alarms/ events	<u>S</u>	Bounded latency/ bandwidth	=	Up to regular ²⁾	
Configuration/ diagnostics	<u>S</u>	<u>Bandwidth</u>	=	Up to regular ²⁾	
Internal / Pass- through	<u>s</u>	<u>Bandwidth</u>	=	Up to regular ²⁾	
Best effort	<u>s</u>	=	ā	<u>Up to regular²⁾</u>	
1) almost zero failover time;					

Formatted: Heading 3,h3

394 395

396

397

398

399 400

5.2 Requirements

This subclause summarizes Industrial Automation requirements to bridged networks.

6.45.2.1 Bridge delay requirements

Figure 2 shows the definition the Bridge delay reference points. To make short control loop times feasible Bridge-delays shall be independent from the frame size and meet the upper limits of Table 15.




Figure 2 – Delay measurement reference points

Table 15 - Required Ethernet Bridge delays

Data rate	Value	Comment
10 Mbps	< 30 µs	Bridge delay measure from MII to MII ¹⁾
100 Mbps	< 3 µs	Bridge delay measure from MII to MII ¹⁾
1 Gbps	< 1 µs	Bridge delay measure from RGMII to RGMII ¹⁾
2,5 Gbps	< 1 µs	Bridge delay measure from XGMII to XGMII ¹⁾
5 Gbps	< 1 µs	Bridge delay measure from XGMII to XGMII ¹⁾
10 Gbps	< 1 µs	Bridge delay measure from XGMII to XGMII ¹⁾
25 Gbps – 1 Tbps:	< 1 µs	Bridge delay measure from XGMII to XGMII ¹⁾

405

406

407

408

409 410

6.55.2.2 Network access

The following network access features for end stations according to IEEE 802.1 shall be supported:

- a) Synchronization to working clock;
- b) Stream class based scheduling with:

Formatted: PARAGRAPH,PA,PA Zchn Zchn

Formatted: Heading 3,h3

supporting ballot comment on 60802/D1.0 - 23 - Step 1

- o Network cycle,
 - < 50 % bandwidth per link for < 1 Gbps for streams;
 - < 20 % bandwidth per link for >= 1 Gbps for streams;
 - < 25 % bandwidth per link for non-streams;</p>
- o Reduction ratio;
- o Phase:

412 413

414

418

419

420 421

422 423

424

425

427

429

- o Sequence;
 - Transmit of frames as a convoy starts at network cycle start with minimum interpacket gap (IPG); first isochronous cyclic real-time frames, second cyclic real-time frames, third non-stream frames;
 - o Reception of frames before assigned network cycle based deadline;
 - c) Time limits for transfer time (receive), see , shall be <= 3 μs in addition to PHY-delay and MAC-delay;
 - d) Time limits for transfer time (transmit), see , shall be <= 3 μs in addition to PHY-delay and MAC-delay;
- e) Network access parameters:
 - o NetworkCycle according to Table 16,
- o ReductionRatio according to Formula (1),
 - Phase according to Formula (2),
- o Sequence according to Formula (3).

431 432

Table 16 - Values of the parameter NetworkCycle

NetworkCycle [time]	10 Mb/s [Data rate]	100 Mb/s [Data rate]	≥ 1 Gb/s [Data rate]
31,25 µs	n.a.	n.a.	Together with all ReductionRatios
62,5 µs	n.a.	n.a.	Together with all ReductionRatios
125 µs	n.a.	n.a.	Together with all ReductionRatios
250 µs	n.a.	Together with all ReductionRatios	Together with all ReductionRatios
500 µs	n.a.	Together with all ReductionRatios	Together with all ReductionRatios
1 ms	Together with ReductionRatio ≥ 8	Together with all ReductionRatios	Together with all ReductionRatios
2 ms	n.a.	Together with all ReductionRatios	n.a.
4 ms	n.a.	Together with all ReductionRatios	n.a.

433 434

The ReductionRatio shall be created according to Formula (1).

ReductionRatio = $2^n \mid n \in \mathbb{N}_{\theta} \mid n \le 10(1)$

Where

```
- 24 - supporting ballot comment on 60802/D1.0
                                                                                               Step 1
           ReductionRatio
                                         is the result of the operation
                                         is actual factor for the operation
                                         are the natural numbers including zero
           \mathbb{N}_0
 435
 436
       The Phase shall be created according to Formula (2).
       PhaseNumber = 1 to ReductionRatio (2)
       Where
           PhaseNumber
                                         is the chosen one out the list
           ReductionRatio
                                         is the applied ReductionRatio
 437
 438
       The Sequence shall be created according to Formula (3).
             SequenceNumber = 1 to MaxListLength
                                                                                                   (3)
       Where
           SequenceNumber
                                         is the chosen one out the list
                                         is the maximum possible entries per Phase
           MaxListLength
       6.65.2.3 Bridge FDB requirements
439
                                                                                                             Formatted: Heading 3,h3
 440
       Editor's note: Contribution requested.
441
       6.75.2.4 Bridge resource requirements
                                                                                                             Formatted: Heading 3,h3
       Editor's note: Contribution requested.
 442
       6.8<u>5.2.5</u> Quantities
443
                                                                                                             Formatted: Heading 3,h3
 444
       The following quantities shall be supported in a single TSN domain:
 445
       a) Stations: >= 1 024
       b) Network diameter: >= 64
 446
       c) Streams per PLC for Controller-to-Device (C2D) communication:
 447
           - >= 512 talker and >= 512 listener streams;
 448

    >= 1 024 talker and >= 1 024 listener streams in case of seamless redundancy;

 449
       d) Streams per PLC for Controller-to-Controller (C2C) communication:
 450
           - >= 64 talker and >= 64 listener streams;
 451
           - >= 128 talker and >= 128 listener streams in case of seamless redundancy.
       e) Streams per Device for Device-to-Device (D2D) communication:
 453
           - >= 2 talker and >= 2 listener streams;
 454
           - >= 4 talker and >= 4 listener streams in case of seamless redundancy.
 455
       Example calculation of data flow quantities for eight PLCs - without seamless redundancy:
 456
           o 8 x 512 x 2
                                            = 8 192 streams for C2D communication, plus
 457
```

supporting ballot comment on 60802/D1.0 - 25 -Step 1

o 8 x 64 x 2 = 1 024 streams for C2C communication 458 0 (8 192 + 1 024) * 2 000 = 18 432 000 Bytes data of all streams 459 460

Synchronization requirements

461

471

476

485

486

487

488

489 490

491

Synchronization covering both universal time and working clock timescales is needed for industrial automation systems. 462

463 Redundancy for synchronization of universal time may be solved with "cold standby". Support of "Hot standby" for universal time synchronization is not current practice - but is an option in 464 this document and can be used depending on the application requirements. 465

466 Redundancy for Working Clock synchronization can be solved with "cold standby" or "hdt standby" depending on the application requirements. Support of "hot standby" for working clock 467 468 synchronization is required.

NOTE Global Time is often used as synonym term for "Universal Time". Wall Clock is based on Universal Time and 469 470 considers time zones, daylight saving time and leap seconds.

Universal Time synchronization

472 Universal time is used to plant wide align events and actions (e.g. for "sequence of events" 473 <u>The assigned timescale is TAI, which can be converted into local date and time if necessary</u> 474 The goal of Universal Time synchronization is to establish a worldwide aligned timescale for 475 time. Thus, often satellites are used as source of the time.

Working Clock synchronization

477 Working Clock is used to align actions line, cell or machine wide. The assigned timescale i 478 ARB. Robots, motion control, numeric control and any kind of clocked / isochronous application rely on this timescale to ensure that actions are precisely interwoven as needed. Often PLC 479 Motion Controller or Numeric Controller are used as Working Clock source. 480

481 Working Clock domains may be doubled to support zero failover time for synchronization b aligning the both timescales at the Grandmaster. 482

TBD: two WC domains - needs more definitions - hot standby/cold standby need 483 definitions 484

High precision Working Clock synchronization is a prerequisite for control loop implementations

General Requirements for Synchronization

Synchronization domain settings shall be according to and.

Table 17 - Synchronization Domains

<u>Domain</u>	<u>ID</u>	Timescales	Presence	<u>Constraints</u>
Working Clock	20	<u>ARB</u>	<u>YES</u>	Used for network access and application synchronization. If scheduled traffic is used then also used for Bridge synchronization.
<u>Universal Time</u>	<u>0</u>	<u>TAI</u>	<u>YES</u>	<u>Used for Universal Time.</u>
Redundant Working Clock	<u>21</u>	<u>ARB</u>	<u>YES</u>	Used for hot standby of Working Clock. Timescale shall be identical to Working Clock.
Redundant Universal Time	1	<u>TAI</u>	<u>YES</u>	Optional. Used for hot standby of Universal Time. Timescale shall be identical to Universal Time.

TBD: ID is Domain number - all Timescales coded as PTP

In the working clock domain bridges shall take the roles of time aware relay and time aware endpoint, because they shall be in sync for scheduled traffic transmission.

Formatted: Heading 3,h3

492 <u>In the Universal Time domain the role of a time aware relay is mandatory and the role of a time</u>
 493 <u>aware endpoint is optional for Bridges.</u>

At least one grandmaster shall be present in every synchronization domain.

494

496

497

498

499 500

501

502

503 504

505

506

507 508

509 510

511

512

495 All members of a synchronization domain may take at least one of the roles specified in .

Table 18 - Synchronization Roles

Role	Working Clock		<u>Universal Time</u>	
	Bridge or Router	End Station	Bridge or Router	End Station
Time aware relay	mandatory	=	mandatory	<u>=</u>
Time aware endpoint	<u>mandatory</u>	mandatory	<u>optional</u>	mandatory
Grandmaster capable	<u>Optional</u>	optional	<u>optional</u>	<u>optional</u>

<u>Editor Note: is support of UniversalTime/Time aware endpoint mandatory or optional for end stations? Contributions are welcome.</u>

The requirements concerning the overall maximum deviation to the grandmaster time in the synchronization domains in shall be fulfilled.

<u> Table 19 – Maximum deviation to grandmaster time requirements </u>

<u>Domain</u>	Maximum absolute value of deviation from grandmaster time	<u>Comments</u>
Working Clock	<u>< 1 μs</u>	Maximum deviation +/- 1 µs
Universal Time	<u>< 100 μs</u>	Maximum deviation +/- 100 μs

<u>Editor's Note: reference number of hops (100) – "grandmaster time" must be defined – from TAI in case of universal time</u>

shows the number of hops which shall be supported.

Table 20 - Maximum number of hops between grandmaster and time aware end-point

<u>Domain</u>	Number of hops	<u>Comments</u>
Working Clock	<u>100</u>	Grandmaster to time aware end-point. May be 200 between two time aware end-points.
<u>Universal Time</u>	<u>100</u>	From Grandmaster connected to the satellite receiver to each time aware endpoint.

The maximum working clock deviation between two devices, which are synchronized to the same grandmaster, shall be $< 2 \mu s$ when the working clock requirement of is observed.

 $\underline{\text{The maximum error contribution of every single network node of the domains shall be according } \underline{\text{to}}\,\underline{.}$

Table 21 - Maximum error contribution per network node

Error contribution	Max. error	<u>Comments</u>
Maximum residence time error	< 10 ns	Externally measured from the MDI to MDI at the local Bridge.
Maximum link delay error	< 10 ns	Externally measured from the MDI to MDI at the local link – including the asymmetry error contribution.

Minimal timestamp accuracy for any kind of timestamp shall be according to .

supporting ballot comment on 60802/D1.0 - 27 - Step 1

513

Table 22 - Timestamp accuracy

Timestamp	Accuracy	<u>Comments</u>
Working Clock	<u>≤ 8 ns</u>	=
<u>Universal time</u>	<u>≤ 8 ns</u>	=

Table 9 specifies the clock synchronization profile contribution. The selection of the different clock types per device shall be provided using PICS.

516 Editor's Note: add requirement about asymmetry compensation

517 ↔

518 6.9 Management selection

519 **6.9.1 General**

520 End stations and bridges shall provide at least the managed objects, which are required by this 521 profile contribution, from

522 IEEE 802.3

523 IEEE 802.3br

524 IEEE 802.1Q

525 IEEE 802.1Qca

526 IEEE 802.10cc

527 IEEE 802.1CBcv

528 **IEEE 802.1AS**

529 **IEEE 802.1AB**

530 IETF RFC 1213

531 etc

These managed objects shall be represented preferred in the YANG format; if the YANG (RFC 6020) format is not available then MIB format (RFC 2358) shall be provided.

6.9.2 Protocols

Required access protocols are SNMP (RFC 4789) for a MIB representation and NETCONF (RFC 6241) for YANG representation of the device local data base.

537

538

539 540

541

542 543

544

545

546

547

534

6 Industrial Automation profile

The objective of the Industrial Automation profile specified in this standard is to allow the construction of bridged networks that meet the industrial automation requirements described in Clause 5.

The bridges of an industrial automation bridged network shall meet the bridge requirements specified in Clause 4 and each link of an industrial automation bridged network is a full dupled point-to-point link. Furthermore, the industrial automation bridged network is designed, configured, and operated as described in this clause in order to meet the industrial automation requirements described in Clause 5. The end stations of an industrial automation deployment shall meet the end station requirements specified in Clause 4 in order to meet the industrial automation requirements described in Clause 5.

548 549 550

6.1 Frame size

551 The size of the Ethernet frames can influence whether or not the industrial automation requirements are met.

Formatted: No bullets or numbering, Tab stops: Not at 2.36"

Formatted: Heading 1,h1,1,_berschrift 1,titre 1

Formatted: Heading 2,h2,Titre 2,Titre 2

- 28 - supporting ballot comment on 60802/D1.0

Step

The maximum frame size is configured at each port of the industrial automation bridged network according to the maximum frame size rules that apply to IEEE 802.3 frames. That is, the maximum possible frame size from the destination MAC address through the end of the CRC is 2000 octets. For example, if nothing but the basic IEEE 802.3 headers are being used with an IEEE 802.1Q C-VLAN tag, then the maximum frame size is 1522 octets. The maximum frame size applied in a network can be smaller than the maximum frame size allowed by IEEE Std 802.3. Furthermore, the maximum frame size applied for different traffic classes can be different. The maximum frame size actually applied for the different traffic classes is used in worst-case latency calculations.

6.2 Traffic classes

6.3 Latency

6.4 Frame loss

568 <u>6.5 VLANs</u>

6.6 Synchronization

0.0 Synchronization

Redundancy for synchronization of universal time may be solved with "cold standby". Support of "Hot standby" for universal time synchronization is not current practice - but is an option in this document and can be used depending on the application requirements.

Redundancy for Working Clock synchronization can be solved with "cold standby" or "hot standby" depending on the application requirements. Support of "hot standby" for working clock synchronization is required.

Working Clock domains may be doubled to support zero failover time for synchronization by aligning the both timescales at the Grandmaster.

 All members of a synchronization domain may take at least one of the roles specified in .

Table 23 - Synchronization Roles

Role	Working Clock		<u>Universal Time</u>		
	Bridge or Router End Station		Bridge or Router	End Station	
Time aware relay	<u>mandatory</u>	=	<u>mandatory</u>	=	
Time aware endpoint	<u>mandatory</u>	mandatory	<u>optional</u>	mandatory	
Grandmaster capable	<u>Optional</u>	optional	optional	<u>optional</u>	

Editor Note: is support of UniversalTime/Time aware endpoint mandatory or optional for end stations? Contributions are welcome.

6.7 Security

IEEE Std 802.1AE enables multiple, per traffic class, transmit secure channels for MAC and thus will also meet strict ordering requirements (within traffic class, with express or preemptible transmission being selected for all the priorities allocated to a traffic class) for preemption.

Secure Device Identifiers (DevIDs) are designed to be used as interoperable secure device authentication credentials with Extensible Authentication Protocol (EAP) and other industry standard authentication and provisioning protocols.

Formatted: Heading 2,h2,Titre 2,Titre 2

supporting ballot comment on 60802/D1.0 $\,-29-$ Step 1

594 Annex A
595
596 PCS proforma – Time-sensitive netw

PCS proforma – Time-sensitive networking profile for industrial automation

A.1 General

597

598

599

600

601

602 603

604

605

606

607 608

609

619

620

621

622 623

624

625

626

627

628

629

630

631

632

633

634

635

636

637

The supplier of an implementation that is claimed to conform to a particular profile defined in this standard shall complete the corresponding Profile Conformance Statement (PCS) proforma, which is presented in a tabular format based on the format used for Protocol Implementation Conformance Statement (PICS) proformas.

The tables do not contain an exhaustive list of all requirements that are stated in the referenced standards; for example, if a row in a table asks whether the implementation is conformant to Standard X, and the answer "Yes" is chosen, then it is assumed that it is possible, for that implementation, to fill out the PCS proforma defined in Standard X to show that the implementation is conformant; however, the tables in this standard will only further refine those elements of conformance to Standard X where particular answers are required for the profiles defined here.

The profiles are not intended to be mutually exclusive; it is possible that a given implementation can support more than one of the profiles defined in this standard. If that is the case, then either the PCS for the implementation should be filled out in order to reflect the support of multiple profiles, or a separate PCS should be filled out to reflect each profile supported.

A completed PCS proforma is the PCS for the implementation in question. The PCS is a statement of which capabilities and options of the protocol have been implemented. The PCS can have a number of uses, including use by the following:

- a) Protocol implementer, as a checklist to reduce the risk of failure to conform to the standard through oversight;
 - Supplier and acquirer—or potential acquirer—of the implementation, as a detailed indication
 of the capabilities of the implementation, stated relative to the common basis for
 understanding provided by the standard PCS proforma;
 - User—or potential user—of the implementation, as a basis for initially checking the
 possibility of interworking with another implementation (note that, while interworking can
 never be guaranteed, failure to interwork can often be predicted from incompatible PCSs);
 - d) Protocol tester, as the basis for selecting appropriate tests against which to assess the claim for conformance of the implementation.

A.2 Abbreviations and special symbols

A.2.1 Status symbols

M: mandatory

O: optional

O.n: optional, but support of at least one of the group of options labeled by the same numeral n is required

X: prohibited

pred: conditional-item symbol, including predicate identification: see A.3.4

¬ logical negation, applied to a conditional item's predicate

A.2.2 General abbreviations

N/A: not applicable

PCS: Profile Conformance Statement

supporting ballot comment on 60802/D1.0 - 31 - Step 1

A.3 Instructions for completing the PCS proforma

A.3.1 General structure of the PCS proforma

639

640

644

645 646

647

648

649

650

651

652

653

661 662 663

664 665

666 667

668

669

670

671

672

673 674

685

The first part of the PCS proforma, implementation identification and protocol summary, is to be completed as indicated with the information necessary to identify fully both the supplier and the implementation.

The main part of the PCS proforma is a fixed-format questionnaire, divided into several subclauses, each containing a number of individual items. Answers to the questionnaire items are to be provided in the rightmost column, either by simply marking an answer to indicate a restricted choice (usually Yes or No) or by entering a value or a set or range of values. (Note that there are some items where two or more choices from a set of possible answers can apply; all relevant choices are to be marked.) Each item is identified by an item reference in the first column. The second column contains the question to be answered; the third column records the status of the item—whether support is mandatory, optional, or conditional; see also A.3.4. The fourth column contains the reference or references to the material that specifies the item in the main body of this standard, and the fifth column provides the space for the answers.

A supplier may also provide (or be required to provide) further information, categorized as either Additional Information or Exception Information. When present, each kind of further information is to be provided in a further subclause of items labeled Ai or Xi, respectively, for cross-referencing purposes, where i is any unambiguous identification for the item (e.g., simply a numeral). There are no other restrictions on its format and presentation.

A completed PCS proforma, including any Additional Information and Exception Information, is the Protocol Implementation Conformation Statement for the implementation in question.

NOTE Where an implementation is capable of being configured in more than one way, a single PCS may be able to describe all such configurations. However, the supplier has the choice of providing more than one PCS, each covering some subset of the implementation's configuration capabilities, in case that makes for easier and clearer presentation of the information.

A.3.2 Additional information

Items of Additional Information allow a supplier to provide further information intended to assist the interpretation of the PCS. It is not intended or expected that a large quantity will be supplied, and a PCS can be considered complete without any such information. Examples might be an outline of the ways in which a (single) implementation can be set up to operate in a variety of environments and configurations, or information about aspects of the implementation that are outside the scope of this standard but that have a bearing on the answers to some items.

References to items of Additional Information may be entered next to any answer in the questionnaire and may be included in items of Exception Information.

A.3.3 Exception Information

It may occasionally happen that a supplier will wish to answer an item with mandatory status (after any conditions have been applied) in a way that conflicts with the indicated requirement.

No preprinted answer will be found in the Support column for this item. Instead, the supplier shall write the missing answer into the Support column, together with an Xi reference to an item of Exception Information, and shall provide the appropriate rationale in the Exception item itself.

An implementation for which an Exception item is required in this way does not conform to this standard.

NOTE A possible reason for the situation described previously is that a defect in this standard has been reported, a correction for which is expected to change the requirement not met by the implementation.

684 A.3.4 Conditional status

A.3.4.1 Conditional items

The PCS proforma contains a number of conditional items. These are items for which both the applicability of the item itself, and its status if it does apply—mandatory or optional—are dependent on whether certain other items are supported.

- 32 - supporting ballot comment on 60802/D1.0

Where a group of items is subject to the same condition for applicability, a separate preliminary 689 question about the condition appears at the head of the group, with an instruction to skip to a later point in the questionnaire if the "Not Applicable" (N/A) answer is selected. Otherwise, 690 691 individual conditional items are indicated by a conditional symbol in the Status column. 692

A conditional symbol is of the form "pred: S" where pred is a predicate as described in A.3.4.2, 693 694 and S is a status symbol, M or O.

If the value of the predicate is true (see A.3.4.2), the conditional item is applicable, and its status is indicated by the status symbol following the predicate: The answer column is to be marked in the usual way. If the value of the predicate is false, the "Not Applicable" (N/A) answer is to be marked.

Predicates A.3.4.2 699

695

696 697 698

700 701

702

703

704

705

706 707

708

711

713

717

719

720

722

A predicate is one of the following:

- a) An item-reference for an item in the PCS proforma: The value of the predicate is true if the item is marked as supported and is false otherwise.
- b) A predicate-name, for a predicate defined as a Boolean expression constructed by combining item-references using the Boolean operator OR: The value of the predicate is true if one or more of the items is marked as supported.
- c) The logical negation symbol "¬" prefixed to an item-reference or predicate-name: The value of the predicate is true if the value of the predicate formed by omitting the "¬" symbol is false, and vice versa.
- Each item whose reference is used in a predicate or predicate definition, or in a preliminary 709 710 question for grouped conditional items, is indicated by an asterisk in the Item column.

References to other standards

The following shorthand notation is used in the References columns of the profile tables: 712

<standard abbreviation>:<clause-number>

where standard abbreviation is one of the following: 714

Q: IEEE Std 802.1Q AS: P802.1AS-REV 716 Dot3: IEEE Std 802.3

Hence, a reference to "IEEE Std 802.1Q-2018, 5.4.2" would be abbreviated to "Q:5.4.2" 718

A.4 Common requirements

Implementation identification

The entire PCS pro forma is a form that shall be filled out by a supplier. 721

Supplier Contact point for queries about the PCS Implementation Name(s) and Version(s) Other information necessary for full identification, e.g., name(s) and version(s) of machines and/or operating system names 723

728

Only the first three items are required for all implementations; other information may be completed as appropriate in meeting the requirement for full identification.

NOTE The terms "Name" and "Version" should be interpreted appropriately to correspond with a supplier's terminology (e.g., Type, Series, Model).

A.4.2 Profile summary, IEC/IEEE 60802

Identification of profile specification	IEC/IEEE 60802		Networking Profi mation	le for Industrial
Identification of amendments and corrigenda to the PCS proforma that have been completed as part of the	Amd.	:	Corr.	:
PCS	Amd.	:	Corr.	:
Have any Exception items been required? (See A.3.3: the answer "Yes" means that the implementation does not conform to IEC/IEEE 60802)	No	[]	Yes	[]
Date of Statement				

729 730

A.4.3 Implementation type

This form is used to indicate the type of system that the PCS describes.

731 732

735

Item	Feature	Status	References	Sup	port
BGE	Is the implementation a Bridge?	0.1		Yes []	No []
TLK	Is the implementation a Talker end station?	0.1		Yes []	No []
LSN	Is the implementation a Listener end station?	0.1		Yes []	No []

NOTE a single device can incorporate the functionality of one or more of the functions listed in this table. For example, a device could have both Talker end station and Listener end station capability.

A.4.4 Common requirements— PHY and MAC

Item	Feature	Status	References	Support	
Dot3	Does one or more Port of the device support an IEEE 802.3 MAC?	М		Yes []	No []
Dot3-1	State the number of IEEE802.3cg Ports.	0.2		Numbe	r
Dot3-2	State the number of 100 Mb/s Ports.	0.2		Numbe	r
Dot3-3	State the number of 1 Gb/s Ports.	0.2		Number	
Dot3-4	State the number of 2,5 Gb/s Ports.	0.2		Numbe	r
Dot3-5	State the number of 5 Gb/s Ports.	0.2		Numbe	r
Dot3-6	State the number of 10 Gb/s or greater Ports.	0.2		Numbe	r
Dot3-7	State the number of Ports supporting IEEE802.3bw-2015	0.2		Numbe	r
Dot3-8	State the number of Ports supporting IEEE802.3by-2016	0.2		Number	
Dot3-9	State the number of Ports supporting IEEE802.3bq-2016	0.2		Numbe	r
Dot3-10	State the number of Ports supporting IEEE802.3bp-2016	0.2		Number	

State the number of Ports supporting IEEE802.3br-2016	М	Nui	Number	
State the number of Ports supporting IEEE802.3bz-2016	0.2	Nui	nbei	r
State the number of Ports supporting IEEE802.3bs /D2.2	0.2	Nui	nbei	r
State the number of Ports supporting IEEE802.3bt /D2.2	0	Nui	nbei	r
State the number of Ports supporting IEEE802.3bu /D3.3	0	Nui	Number	
State the number of Ports supporting IEEE802.3bv /D3.3	0.2	Nui	Number	
State the number of Ports supporting IEEE802.3ca /D0.0	0.2	Nui	Number	
State the number of Ports supporting IEEE802.3cb /D2.1	0.2	Nui	Number	
State the number of Ports supporting IEEE802.3cc /D2.0	0.2	Nui	nbei	r
State the number of Ports supporting IEEE802.3cd /D1.1	0.2	Nui	Number	
Do all the IEEE 802.3 Ports support full duplex operation?	М	Yes	Yes [] No []	
Do all ports support a maximum frame size of 2000 octets?	М	Yes	[]	No []
	Supporting IEEE802.3br-2016 State the number of Ports supporting IEEE802.3bz-2016 State the number of Ports supporting IEEE802.3bs /D2.2 State the number of Ports supporting IEEE802.3bt /D2.2 State the number of Ports supporting IEEE802.3bt /D2.2 State the number of Ports supporting IEEE802.3bu /D3.3 State the number of Ports supporting IEEE802.3bv /D3.3 State the number of Ports supporting IEEE802.3ca /D0.0 State the number of Ports supporting IEEE802.3cb /D2.1 State the number of Ports supporting IEEE802.3cb /D2.1 State the number of Ports supporting IEEE802.3cd /D1.1 Do all the IEEE 802.3 Ports support full duplex operation? Do all ports support a maximum	Supporting IEEE802.3br-2016 State the number of Ports supporting IEEE802.3bz-2016 State the number of Ports supporting IEEE802.3bs /D2.2 State the number of Ports supporting IEEE802.3bs /D2.2 State the number of Ports supporting IEEE802.3bt /D2.2 State the number of Ports supporting IEEE802.3bu /D3.3 State the number of Ports supporting IEEE802.3bv /D3.3 State the number of Ports supporting IEEE802.3ca /D0.0 State the number of Ports supporting IEEE802.3ca /D0.0 State the number of Ports supporting IEEE802.3cb /D2.1 State the number of Ports supporting IEEE802.3cc /D2.0 State the number of Ports supporting IEEE802.3cd /D1.1 Do all the IEEE 802.3 Ports support full duplex operation? Do all ports support a maximum	Supporting IEEE802.3br-2016 State the number of Ports supporting IEEE802.3bz-2016 State the number of Ports supporting IEEE802.3bs /D2.2 State the number of Ports supporting IEEE802.3bt /D2.2 State the number of Ports supporting IEEE802.3bt /D3.3 State the number of Ports supporting IEEE802.3bv /D3.3 State the number of Ports supporting IEEE802.3bv /D3.3 State the number of Ports supporting IEEE802.3bv /D3.3 State the number of Ports supporting IEEE802.3c /D0.0 State the number of Ports supporting IEEE802.3c /D0.0 State the number of Ports supporting IEEE802.3cc /D2.1 State the number of Ports supporting IEEE802.3cc /D2.0 State the number of Ports supporting IEEE802.3cc /D2.0 State the number of Ports supporting IEEE802.3cd /D1.1 Do all the IEEE 802.3 Ports support full duplex operation? Do all ports support a maximum	Supporting IEEE802.3br-2016 State the number of Ports supporting IEEE802.3bz-2016 State the number of Ports supporting IEEE802.3bs /D2.2 State the number of Ports supporting IEEE802.3bt /D2.2 State the number of Ports supporting IEEE802.3bt /D2.2 State the number of Ports supporting IEEE802.3bt /D3.3 State the number of Ports supporting IEEE802.3bv /D3.3 State the number of Ports supporting IEEE802.3bv /D3.3 State the number of Ports supporting IEEE802.3cb /D3.3 State the number of Ports supporting IEEE802.3ca /D0.0 State the number of Ports supporting IEEE802.3ca /D0.0 State the number of Ports supporting IEEE802.3cb /D2.1 State the number of Ports supporting IEEE802.3cc /D2.0 State the number of Ports supporting IEEE802.3cd /D1.1 Do all the IEEE 802.3 Ports support full duplex operation? Do all ports support a maximum

A.4.5 Common requirements— Bridges

736 737

738 739

740 741

742

748

749

If item BGE in A.4.3 is supported, then the Support column in ZZZZ through ZZZZ shall be completed; otherwise the support column items in these tables shall be left blank.

The major capabilities to be supported in all Bridges are identified in ZZZZ. An Bridge shall support all mandatory requirements that apply to a VLAN-aware Bridge component, and to support IEEE Std 802.1AS.

Additional requirements for IEEE 802.1Q implementation that apply to all Bridges are identified in ZZZZ. These cover detailed requirements for tagging, VID, FID, MSRP, and forwarding support.

Additional requirements for IEEE 802.1AS implementation that apply to all AV Bridges are identified in ZZZZ.

A.4.6 Major capabilities—Bridges

Item	Feature	Status	References	Sup	port
BGE-1	Do all ports support a maximum frame size of 2000 octets?	М	4.3.2.1.1	Yes []	No []
BGE-2	Does the Bridge support disabling of priority-based flow control?	М	4.3.2.1.1	Yes []	No []
BGE-3	Does the Bridge support disabling MAC control PAUSE if implemented?	М	4.3.2.1.1	Yes []	No []
BGE-4	Does the Bridge support disabling of Energy Efficient Ethernet?	М	4.3.2.1.1	Yes []	No []
BGE-5	Does the Bridge support the strict priority algorithm on each port?	М	4.3.2.1.1	Yes []	No []

supporting ballot comment on 60802/D1.0 $\,$ – 35 – Step 1

BGE-6	Does the Bridge support 8 queues on each port?	М	4.3.2.1.1	Yes []	No []
BGE-7	Does the Bridge support priority regeneration?	М	4.3.2.1.1	Yes []	No []
BGE-8	Does the Bridge support preemption?	М	4.3.2.1.1	Yes []	No []
BGE-9	Does the Bridge meet the bridge delays specified in 5.2.1?	М	Table 15	Yes []	No []

750 751

A.4.7 IEEE Std 802.1Q requirements—Bridges

4.4.7	IEEE Std 802.1Q requirements—	Bridges			
Item	Feature	Status	References	Sup	port
B-Q-1	Does the Bridge support requirements for VLAN Bridge Components per IEEE802.1Q 5.4 and Table 7?	М	4.3.2.1.1 Table 7	Yes []	No []
B-Q-2	Does the Bridge support requirements for VLAN Bridge per IEEE802.1Q 5.4.1 and Table 7?	М	4.3.2.1.1 Table 7	Yes[]	No []
B-Q-3	Does the Bridge support MST operation per IEEE802.1Q 5.4.1.1 and Table 7?	М	Table 7	Yes []	No []
B-Q-4	Does the Bridge support MMRP operation per IEEE802.1Q 5.4.1.3 and Table 7?	0	4.3.2.1.1 Table 7	Yes []	No []
B-Q-5	State the number of Ports supporting Enhancements for scheduled traffic per IEEE802.1Q 5.4.1 and Table 7	0	Table 7	Numbe	r
B-Q-6	State the number of Ports supporting FQTSS per IEEE802.1Q 5.4.1.5 and Table 7	0	Table 7	Number	
B-Q-7	State the number of Ports supporting PSFP per IEEE802.1Q 5.4.1.8 and Table 7	0	Table 7	Numbe	r
B-Q-8	State the number of Ports supporting CQF per IEEE802.1Q 5.4.1.9 and Table 7	0	Table 7	Numbe	r
B-Q-9	Does the Bridge support MVRP per IEEE802.1Q 5.4.2 and Table 10?	0	Table 7	Yes []	No []
B-Q-10	Does the Bridge support MSRP per IEEE802.1Q 5.4.4 and Table 7?	0	4.3.2.1.1 Table 7	Yes []	No []
B-Q-11	Does the Bridge support C-VLAN requirements per IEEE802.1Q 5.5, 5.9 and Table 7?	0	4.3.2.1.1 Table 7	Yes []	No []
B-Q-12	Does the Bridge support MAC Bridge component requirements per IEEE802.1Q 5.13, 5.14 and Table 7?	0	4.3.2.1.1 Table 7	Yes [] No []	
B-Q-13	State the number of Asynchronous Traffic Shaping per IEEE P802.1Qcr D0.0 and Table 8	0	Table 8	Number	
B-Q-14	Does the Bridge support IEEE802.1Qcc-2018 per Table 8?	0	Table 8	Yes []	No []
B-Q-15	Does the Bridge support IEEE P802.1Qdd per Table 10?	0	Table 8	Yes []	No []

Item	Feature	Status	References	Su	pport
TS-1	Does the implementation support four domains as specified in ?	М		Yes []	No []
TS-2	Does the implementation comply with the maximum error contribution per network node specified in ?	М		Yes []	No []
TS-3	Does the implementation comply with the timestamp accuracy specified in ?	М		Yes []	No []
TS-4	Does the implementation comply with Time aware system requirements specified in AS: 5.3 and Table 9?	М	AS:5.3, Table 9	Yes []	No []
TS-5	Does the implementation comply with PTP instance requirements specified in AS: 5.4 and Table 9?	М	AS:5.4, Table 9	Yes []	No []
TS-5	Does the implementation comply with PTP instance requirements specified in AS: 5.4 and Table 9?	М	AS:5.4, Table 9	Yes []	No []
TS-6	List the number of ports supporting the media-independent master capability	0	AS:5.4.1, Table 9	Number	
TS-7	Is the implementation Grand Master capable as specified in AS: 5.4.1 and Table 9?	0	AS:5.4.1, Table 9	Yes []	No []
TS-8	List the number of ports supporting PTP Relay Instance capability	0	AS:5.4.2, Table 9	Numb	oer
TS-9	Does the implementation support media-independent attributes of the Announce message and the Signaling message	0	AS:5.4.1, Table 9	Yes []	No []
TS-10	Does the implementation support the SyncIntervalSetting state machine	0	AS:5.4.1, Table 9	Yes []	No []
TS-11	Does the implementation support timing and synchronization management	М	AS:5.4.1, Table 9	Yes []	No []
TS-12	List the number of ports supporting MAC-specific timing and synchronization methods for IEEE 802.3 full-duplex links	М	AS:5.5, Table 9	Number	
TS-13	List the number of ports supporting MAC-specific timing and synchronization methods for IEEE 802.11	0	AS:5.6, Table 9	Number	

756 757

A.4.9 Security Requirements

	•				
Item SEC-1	Feature Does the implementation support IEEE 802.1AE™- 2006?	Status O	References Table 10	Support	
				Yes []	No []
SEC-2	Does the implementation support IEEE 802.1AEbn™- 2011?	Dot1AE:M	Table 10	Yes []	No []
SEC-3	Does the implementation support IEEE 802.1AEbw™- 2013?	Dot1AE:M	Table 10	Yes []	No []
SEC-4	Does the implementation support IEEE 802.1AEcg?	Dot1AE:M	Table 10	Yes []	No []
SEC-5	Does the implementation support IEEE 802.1AR™- 2009?	Dot1AE:M	Table 10	Yes []	No []

supporting ballot comment on 60802/D1.0 $\,$ – 37 – Step 1

SEC-6	Does the implementation support IEEE 802.1X™- 2009?	0	Table 10	Yes []	No []
SEC-6	Does the implementation support IEEE 802.1Xbx [™] - 2014?	0	Table 10	Yes []	No []

- 38 - supporting ballot comment on 60802/D1.0 Step 1

761	Annex Z	
762	(informative/normative)	
763	_	
764	Gaps	
765	1. Regular synchronization of .1Qbv "tick" event to the 802.1AS-Rev clock	
766	2. Distributed and Centralized model "UNI" may need to be expanded.	
767 768	Need mechanism for identifying "In-sync" and "out of Sync" for all time-aware sys in the network.	tems
769	4. Network diagnostic – base on Gunter's contribution.	
770	5. Synchronization – base on Gunter's contribution.	
771	6. Defined range of destination MAC address, do we get our own OUI	
772	7. Do we need a standardized TLV for LLDP to identify the TSN domain	
773	8. Do we need a section to distinguish between constrained devices vs other devices	s?
774	9. Management Reconciliation	
775 776	 http://www.ieee802.org/1/files/public/docs2018/60802-Steindl-Configuratio 0718-v02.pdf 	n-
777 778	 Need to identify network management access protocols and select data model management. 	s for
779	11. Bridge FDB and resource requirements	
780	12. Define procedures to implement hot-stand-by masters.	
781	13. Do we need an IEC/IEEE translation dictionary?	
782	14. Reference style IEC guides in the profile.	
783 784 785	Editor's note: Do we need a different class of device for constrained devices (two mac relays for instance) or a separate profile? (Table 12-24 in 802.1Q-2018 ha example of how this might be done)?	-port s an
786	15. Do we need to specify link aggregation in support of event-based control?	
787 788	 http://www.ieee802.org/1/files/public/docs2018/60802-stanica-event-based control-1118-v02.pdf 	i -
789 790	 http://www.ieee802.org/1/files/public/docs2018/60802-stanica-link-aggrega 1118-v02.pdf> 	ation-
791	16. How do we deal with destination MAC address constraints	
792 793	 http://www.ieee802.org/1/files/public/docs2018/60802-Steindl- DaMacConstraints-0718-v02.pdf 	
794		

supporting ballot comment on 60802/D1.0 $\,-$ 39 $\,-$ Step 1

795 Bibliography

796

T97 IEEE Std 1588™-2008, IEEE Standard for a Precision Clock Synchronization Protocol for Networked Measurement and Control Systems