# 60802 Time Sync – Mean Link Delay & Timestamp Granularity

David McCall (Intel Corporation)
Version 2

### References

[1] – Geoff Garner, "<u>Initial 60802 Error Generation Time Series</u> <u>Simulation Results Version 1</u>", contribution to IEC/IEEE 60802, 22<sup>nd</sup> January 2024

[2] – Geoff Garner, "Further 60802 Error Generation Time Series Simulation Results Version 1", contribution to IEC/IEEE 60802 13<sup>th</sup> March 2024

### Content

- Background & Baseline Assumptions
- Description of Simulation
- mPathDelay Measurements and meanLinkDelay Errors
  - DTSE then TSGE (matching implementations)
  - Effect of Clock Offsets & Pdelay Turnaround
- Simulations to match Time Series Simulations in [1] & [2]
  - TSGE then DTSE

Note: In previous contributions I've often looked at modelling errors. In this contribution, I'm looking at the behaviour of implementations as a result of errors. The simulation models timestamps, not just errors.

### Background


- Mean Link Delay (*meanLinkDelay*) measurements in [1] and [2] demonstrated some unexpected behaviour, with step changes between two values either side of the actual value.
  - See slides 22 to 27
- This contribution is a detailed breakdown of the way timestamp errors, clock offsets and errors due to clock drift can contribute to errors in the individual Path Delay measurements (*mPathDelay*). It investigates how these errors, combined with the *meanLinkDelay* filtering (averaging) algorithm might produce the observed (simulated) behaviour.

### Baseline Assumptions

- Unless mentioned, the "usual" 60802 configuration applies...
  - Same timestamp and clock drift errors as [1]
    - Timestamp Granularity: 8 ns
    - Dynamic Timestamp Error: ±6 ns
  - Same parameters and configuration as [1]
    - Pdelay Interval: uniform distribution, 119 ms to 131 ms (note: different from Time Series, but does not have an effect on the end results)
    - Pdelay Turnaround: normal distribution, mean 10 ms, standard deviation 1.8 ms
      - Truncated to 1 ms and 15 ms (values outside range are rounded up or down respectively)
- mPathDelay means raw measurements of Path Delay, before input to the Mean Link Delay filter
- meanLinkDelay means output from Mean Link Delay filter
  - Filter is as described in clause D.5.7 of 60802 and is the same as used in [1]
- Note: Clock Drift is not currently simulated (but constant Clock Offsets are)

# Description of Simulation

### Path Delay Measurement




### Description of Simulation – 1


- RStudio script for R
- 1 Vector (1 dimensional array) per variable, of length runs, where runs is the number of Pdelay\_Req / \_Resp message exchanges being simulated.
  - runs is typically 10,000
- Simulation has a concept of an "ideal" clock against which two "real" clocks are measured
  - One clock for node n, which is measuring meanLinkDelay
  - One clock for node n-1, the Path Delay to which node N is measuring.
  - Each "real" clock has a constant offset (ppm) relative to the ideal clock
    - The offset can be 0 ppm

### Description of Simulation – 2

- Models a series of Pdelay\_Req and Pdelay\_Resp messages, each separated by a randomly generated Pdelay Interval and with a randomly generated Pdelay Turnaround time
  - Both are in terms of "ideal" clock
- Models "actual" timestamps for t<sub>1</sub>, t<sub>2</sub>, t<sub>3</sub> and t<sub>4</sub> in terms of "ideal" clock
- Then:



 Note that Time Series Simulation does this (and this RStudio simulation has an option to do the same)...



### Description of Simulation – 3


Carries out mPathDelay calculation:


$$PathDelay = \frac{\left(t_{4}(x) - t_{1}(x)\right) - \frac{\left(t_{3}(x) - t_{2}(x)\right)}{Neighbor\ Rate\ Ratio(x)}}{2}$$


- NRR is the actual NRR with the option for added error
  - Error is not calculated (as it is from a different process that is not modelled) but rather taken as an output from [1]. Same error file is used for all simulations.
- Carries out meanLinkDelay calculation using algorithm defined in D.5.7
  - Uses initial value of Path Delay with an error of normal distribution, mean 0
    ns, standard deviation 0.1 ns. (Avoids need to simulate start-up behaviour.)


# mPathDelay Measurements & meanLinkDelay Errors


### Path Delay Measurement












#### **4ns Granularity**



### No Clock Offsets

KEY




Path Delay

meanLinkDelay

#### Individual Path Delay Measurements

Simulated Data - Path Delay 454.21 ns - meanLinkDelay min 453.97 ns max 454.42 ns




#### **KEY**

- mPathDelay Data
- Path Delay
- meanLinkDelay

#### Individual Path Delay Measurements

Simulated Data - Path Delay 454.21 ns - meanLinkDelay min 453.89 ns max 454.33 ns




### n-1 node +1 ppm

#### KEY

- mPathDelay Data
- Path Delay
  - meanLinkDelay

#### Individual Path Delay Measurements

Simulated Data - Path Delay 454.21 ns - meanLinkDelay min 454 ns max 454.37 ns




#### **KEY**

- mPathDelay Data
- Path Delay
  - meanLinkDelay

#### Individual Path Delay Measurements

Simulated Data - Path Delay 454.21 ns - meanLinkDelay min 454.07 ns max 454.34 ns



### Observations

- Zero clock offset (note: simulation is "perfect", i.e. clocks are exactly in sync apart from initial phase offset) illustrates 4ns quantisation steps according to TSGE.
- Adding a clock offset spreads out the measurements around the quantisation steps <u>and</u> shifts the steps themselves, within broad limits.
- If the clock offset is large enough, the quantisation steps are swamped and the datapoints appear to be dispersed around the actual Path Delay

### Proposition


- The way the data is spread around the quantisation steps is related to the probability distribution of Pdelay Turnaround.
  - Test by varying the distribution of Pdelay Turnaround
- The shift of the quantisation steps is affected by both the distribution of Pdelay Turnaround and clock offset(s)
  - Test by varying the distribution of Pdelay Turnaround and the clock offsets


#### Pdelay Turnaround – Truncated Normal Distribution

 $(\mu = 10; \sigma = 1.8; truncated 1 to 15 ms)$ 

#### Individual Path Delay Measurements

Simulated Data - Path Delay 454.21 ns - meanLinkDelay min 453.92 ns max 454.41 ns







Pdelay Turnaround – Uniform Distribution 1 to 15 ms

#### Individual Path Delay Measurements

Simulated Data - Path Delay 454.21 ns - meanLinkDelay min 454.09 ns max 454.54 ns







Pdelay Turnaround – Uniform Distribution 5 to 15 ms

#### Individual Path Delay Measurements

Simulated Data - Path Delay 454.21 ns - meanLinkDelay min 453.86 ns max 454.47 ns







Pdelay Turnaround – Uniform Distribution 5 to 15 ms

#### Individual Path Delay Measurements

Simulated Data - Path Delay 454.21 ns - meanLinkDelay min 453.97 ns max 454.33 ns







Pdelay Turnaround – Uniform Distribution 5 to 15 ms

#### Individual Path Delay Measurements

Simulated Data - Path Delay 454.21 ns - meanLinkDelay min 454.06 ns max 454.4 ns







Pdelay Turnaround – Uniform Distribution 5 to 15 ms

#### Individual Path Delay Measurements

Simulated Data - Path Delay 454.21 ns - meanLinkDelay min 454.01 ns max 454.49 ns







Pdelay Turnaround – Uniform Distribution 5 to 15 ms

#### Individual Path Delay Measurements

Simulated Data - Path Delay 454.21 ns - meanLinkDelay min 453.96 ns max 454.42 ns







### No Clock Offsets

Pdelay Turnaround – Uniform Distribution 5 to 15 ms

#### Individual Path Delay Measurements

Simulated Data - Path Delay 454.21 ns - meanLinkDelay min 453.94 ns max 454.4 ns





### Observations


- The combination of TSGE, DTSE, Pdelay Turnaround distribution and Clock Offsets determines the quantisation steps and distribution around those steps of mPathDelay measurements.
- The underlying distribution of mPathDelay measurements around the actual Path Delay value remains the same, and is determined by DTSE and TSGE.
- Regardless of the above factors, taking a long "average" a described in Clause D.5.7, yields stable meanLinkDelay values well within the normative requirement of ±3 ns


#### Pdelay Turnaround – Truncated Normal Distribution

( $\mu$  =10;  $\sigma$ =1.8; truncated 1 to Pdelay Turnaround – Truncated Normal Distribution15 ms)

#### Individual Path Delay Measurements

Simulated Data - Path Delay 454.21 ns - meanLinkDelay min 454.05 ns max 454.43 ns







Pdelay Turnaround – Uniform Distribution 5 to 15 ms

#### Individual Path Delay Measurements

Simulated Data - Path Delay 454.21 ns - meanLinkDelay min 454.04 ns max 454.47 ns






# Simulations to Match Time Series Simulations


### Difference

• Simulations in previous section do this...



...which matches most implementations.

• Time Series Simulations in [1] and [2] do this...



...which the RStudio simulation can also match.

### No DTSE; No Clock Offset

#### **KEY**




Path Delay

meanLinkDelay

#### Individual Path Delay Measurements

Simulated Data - Path Delay 454.21 ns - meanLinkDelay min 454.11 ns max 454.34 ns




### No DTSE; n-1 node +0.5 ppm

#### **KEY**

- mPathDelay Data
- Path Delay
- meanLinkDelay

#### Individual Path Delay Measurements

Simulated Data - Path Delay 454.21 ns - meanLinkDelay min 454.07 ns max 454.33 ns




### ±6 ns DTSE; No Clock Offset

#### **KEY**

- mPathDelay Data
- Path Delay
- meanLinkDelay


#### Individual Path Delay Measurements

Simulated Data - Path Delay 454.21 ns - meanLinkDelay min 453.99 ns max 454.47 ns




# ±6 ns DTSE; No Clock Offset– Probability Density (100,000 Messages)

#### mPathDelay Probability Density



### ±6 ns DTSE; No Clock Offset – QQ Plot




### ±6 ns DTSE; n-1 node +0.5 ppm

#### KEY

- mPathDelay Data
- Path Delay
  - meanLinkDelay


#### Individual Path Delay Measurements

Simulated Data - Path Delay 454.21 ns - meanLinkDelay min 453.94 ns max 454.44 ns




### ±6 ns DTSE; n-1 node +0.5 ppm – Probability Density (100,000 Messages)

#### mPathDelay Probability Density



### ±6 ns DTSE; n-1 node +0.5 ppm – QQ Plot



### Observations & Recommendation

- RStudio simulation shows some similarities with [1] and [2]
  - Quantisation steps due to TSGE with distribution either side of steps due to DTSE.
- But no evidence of "sticking" on a particular step for any length of time with consequent visible step changes
- Without step changes, normative requirements on meanLinkDelay are easily met.
  - This is regardless of whether Timestamp Granularity is applied before or after Dynamic Timestamp
     Error
- Currently there is no theory for why [1] and [2] exhibit the step-change behaviour.
   (Especially what causes a move from one step to another.)
- Recommendation: do not alter meanLinkDelay normative requirements from d2.2 values.

# Thank you