

802.1AXdz

YANG for Link Aggregation:

Editor's Report: November 2024
Version 1

Stephen Haddock
November 13, 2024

802.1AXdz status

- AXdz-d0.2 went to Task Group ballot on October 30, 2024 through November 3, 2024.
- Ballot results:
 - 3 yes; 4 no; 11 abstain.
 - 24 comments from 4 commenters.
- Preliminary disposition:
 - [802-1AXdz-d0-2-pdis-v01.pdf](#)

Quick (hopefully) resolutions

- 14 comments are simple/obvious changes.

Easy Editorial: 7, 10, 19, 22, 24

Easy Technical Required: 2, 11, 20

Ranges: 13, 14, 15, 16, 17, 21

Comment numbers in
blue were discussed in
YANGsters

Discussion Topics

- Proposed Reject: 6, 8, 18
- Defaults: 12, 5, 9
- UML-like diagram: 1
- DRNI if-features: 3, 4
- System MAC address: 23


Effect of Activity flags in the admin port states when Sonny connects to Cher

Sonny \\ Cher		Actor_Admin.Activity : Partner_Admin.Activity			
		1 : 1	1 : 0	0 : 0	0 : 1
Actor_Admin.Activity :\\ Partner_Admin.Activity	1 : 1	Both sing (Both transmit LACPDUs)	Both sing	Cher sings. Sonny sings when hears Cher.	Both sing
	1 : 0	Both sing	Both sing	Cher sings. Sonny sings when hears Cher.	Both sing
	0 : 0	Sonny sings. Cher sings when hears Sonny.	Sonny sings. Cher sings when hears Sonny.	Neither sing	Sonny sings
	0 : 1	Both sing	Both sing	Cher sings	Both sing, then both stop when hear the other. Timeout and repeat.


#12

Current

#23



Proposed



Current and proposed example config (json)

```
• {  
•   "ieee802-dot1ax-linkagg:linkagg": {  
•     "key-group": [  
•       {  
•         "name": "Key-1",  
•         "actor-admin-key": 1,  
•         "actor-system": "00-80-C2-00-00-01"  
•       }  
•     ]  
•   },  
•   "ietf-interfaces:interfaces": {  
•     "interface": [  
•       {  
•         "name": "eth1",  
•         "type": "iana-if-type:ethernetCsmacd",  
•         "ieee802-dot1ax-linkagg:aggport": {  
•           "key-group-name": "Key-1"  
•         }  
•       },  
•       {  
•         "name": "lag1",  
•         "type": "iana-if-type:ieee8023adLag",  
•         "ieee802-dot1ax-linkagg:lag": {  
•           "key-group-name": "Key-1"  
•         }  
•       }  
•     ]  
•   }  
• }
```

```
• {  
•   "ieee802-dot1ax-linkagg:linkagg": {  
•     "agg-system": [  
•       {  
•         "name": "my-system"  
•       }  
•     ],  
•     "key-group": [  
•       {  
•         "name": "Key-1",  
•         "actor-admin-key": 1,  
•         "agg-system-name": "my-system"  
•       }  
•     ]  
•   },  
•   "ietf-interfaces:interfaces": {  
•     "interface": [  
•       {  
•         "name": "eth1",  
•         "type": "iana-if-type:ethernetCsmacd",  
•         "ieee802-dot1ax-linkagg:aggport": {  
•           "key-group-name": "Key-1"  
•         }  
•       },  
•       {  
•         "name": "lag1",  
•         "type": "iana-if-type:ieee8023adLag",  
•         "ieee802-dot1ax-linkagg:lag": {  
•           "key-group-name": "Key-1"  
•         }  
•       }  
•     ]  
•   }  
• }
```


Next steps

- Working Group Ballot?


Back up slides

Proposed

#23



Alternative



Thank You