```
+----------------------------------------------------------------------+
| IEEE 802.1 REVISION REQUEST 0092                                     |
+----------------------------------------------------------------------+
```

DATE: 27 December, 2012
NAME: Sung Hyuk Byun
COMPANY/AFFILIATION: ETRI
E-MAIL: shbyun@etri.re.kr
REQUESTED REVISION:
        STANDARD: 802.1Qbg-2012
        CLAUSE NUMBER: 41.5.2
        CLAUSE TITLE: Bridge VDP state machine

RATIONALE FOR REVISION:
In Figure 41-8 Bridge VDP state machine, WAIT_STATION_CMD state include following
equation :
    vsiState = operCmd.Mode1;
But, there is no definition of operCmd.Mode1 in the standard.
operCmd.Mode1 should be a mistyping of operCmd.TLVtype.

PROPOSED REVISION TEXT:
Change the following equation at WAIT_STATION_CMD state of Figure 41.8, Clause
41.5.2
    vsiState = operCmd.Mode1
with
    vsiState = operCmd.TLVtype

IMPACT ON EXISTING NETWORKS:

There is no impact on existing networks.

```
+----------------------------------------------------------------------+
|  Please attach supporting material, if any                           |
|  Submit to:- Tony Jeffree, Chair IEEE 802.1                          |
|   and copy:- Glenn Parsons, Vice-Chair IEEE 802.1                    |
|     E-Mail: stds-802-1-maint-req@ieee.org                            |
|                                                                      |
|               +------- For official 802.1 use -----------+          |
|               | REV REQ NUMBER: 0092                      |          |
|               | DATE RECEIVED: 01/09/2013                 |          |
|               | EDITORIAL/TECHNICAL                       |          |
|               | ACCEPTED/DENIED                           |          |
|               | BALLOT REQ'D YES/NO                       |          |
|               | Status: R                                 |          |
|               +-------------------------------------------+          |
+----------------------------------------------------------------------+
```